

# FLRPC: Proton Driver

**Bob Kephart**

**March 24, 2004**

# Outline

---

- **FLRPC: Proton Driver Working Group**
- **Proton Driver Design Studies**
  - 8-GeV synchrotron
  - 8-GeV Superconducting Linac ← bulk of the talk
  - MI upgrades
- **FLRPC: PD recommendations**
- **Conclusions**



# Studies of the FNAL Proton Source

- Several studies have had the goal of understanding the limitations of the existing source and suggesting upgrades
- **Proton Driver Design Study I:**
  - 16 GeV Synchrotron (TM 2136) Dec 2000
- **Proton Driver Design Study II (draft TM 2169) :**
  - ✓ 8 GeV Synchrotron May 2002
  - ✓ 2 MW upgrade to Main Injector May 2002
  - ✓ 8 GeV Superconducting Linac: Feb 2004
- **Proton Team Report (D Finley):** Oct 2003
  - **Report:** [http://www.fnal.gov/directorate/program\\_planning/studies/ProtonReport.pdf](http://www.fnal.gov/directorate/program_planning/studies/ProtonReport.pdf)
  - **Limitations of existing source, upgrades for a few 10's of \$ M.**
  - “On the longer term the proton demands of the neutrino program will exceed what reasonable upgrades of the present Booster and Linac can accommodate → FNAL needs a plan to replace its aging LINAC & Booster with a new more intense proton source (AKA a **Proton Driver**)



# Fermilab:Long Range Planning

---

- **In April of 2003 the Fermilab Director formed a committee to provide advice on the long range scientific program of the laboratory. FLRP Membership & Charge:**  
[http://www.fnal.gov/directorate/Longrange/Long\\_rang\\_planning.html](http://www.fnal.gov/directorate/Longrange/Long_rang_planning.html)
- **Excerpt from the charge to the LRP committee:**
  - “ I would like the Long-range Planning Committee to develop in detail a few realistically achievable options for the Fermilab program in the next decade under each possible outcome for the linear collider. ....”
- **It was clear from the start that a new intense proton source to serve long baseline neutrino experiments was one such option...**



# FLRP:PD Working group

## PD Subcommittee:

**Bob Kephart, chair**

**Steve Geer**

**Chris Hill**

**Peter Meyers**

**Sergei Nagaitsev**

## Technical Advisors

**Dave Finley**

**John Marriner**

**Shekar Mishra**

**Victor Yarba**

## Proponents

**Weiren Chou**

**Bill Foster**



Fermi National Accelerator Laboratory

A Department of Energy National Laboratory  
Managed by Universities Research Association

## Fermilab Long Range Planning Committee Working Groups

Physics Working Group Convenor: <a href="#">Chris Hill</a> <a href="#">Documents</a>	Neutrinos Working Group Convenor: <a href="#">Gary Feldman</a> <a href="#">Documents</a>
Linear Collider Working Group Convenor: <a href="#">Steve Holmes</a> <a href="#">Documents</a>	Large Hadron Collider Working Group Convenor: <a href="#">John Womersley</a> <a href="#">Documents</a>
Proton Driver Working Group Convenor: <a href="#">Bob Kephart</a> <a href="#">Documents</a>	Accelerator R&D Working Group Convenor: <a href="#">Steve Geer</a> <a href="#">Documents</a>
Particle Astrophysics Working Group Convenor: <a href="#">Josh Frieman</a> <a href="#">Documents (when available)</a>	Non-(Particle Physics) Working Group Convenor: <a href="#">Joel Butler</a> <a href="#">Documents</a>
Resources Working Group Convenor: <a href="#">Hugh Montgomery</a> <a href="#">Documents (when available)</a>	International Lab Issues Working Group Convenor: <a href="#">Documents (when available)</a>



**Past BD Head (proton economics)**

**Past BD Head**

**Past deputy head MI project**

**SCRF R&D (started TD RF group)**

**Synchrotron based Proton Driver**

**SCRF Linac based Proton Driver**



# FLRP:PD Working group

---

- **Had a series of 14 meetings**
  - Well attended by Expert Participants
  - 27 additional people made presentations or important contributions to the meetings
  - 3 joint meetings with other LRP sub committees
- **To obtain input from the community an open session took place on Oct 9, 2003**
- **“FLRP Retreat” Jan 9-10**
  - “Draft Proton Driver Recommendations
- **Final Report and recommendations in Mar 2004**
- **PD meetings has now evolved into a regular Proton Driver R&D/Design meeting**
  - More people joining the effort




# Proton Driver Design Studies

- **8 GeV Synchrotron (TM 2169)**
  - Basic plan is to replace the existing Booster with a new large aperture 8 GeV Booster (also cycling at 15 Hz)
  - Takes full advantage of the large aperture of the Main Injector
  - Goal= 5 times # protons/cycle in the MI (  $3 \times 10^{13} \rightarrow 1.5 \times 10^{14}$  )
  - Reduces the 120 GeV MI cycle time 20% from 1.87 sec to 1.53 sec
  - The plan also includes improvements to the existing linac (new RFQ and 10 MeV tank) and increasing the linac energy (400→600 MeV)
  - The increased number of protons and shorter cycle time requires substantial upgrades to the Main Injector RF system
- **Net result = increase the Main Injector beam power at 120 GeV by a factor of 6 (from 0.3 MW to 1.9 MW)**



# PD: 8 GeV Synchrotron



- Sited West of the existing booster
- Twice the shielding of the current booster
- Large aperture magnets
- Collimators contain losses to avoid activation of equipment





# PD: 8 GeV Synchrotron

- **Synchrotron technology well understood**
  - May be cheaper than an 8 GeV linac
  - We have more experience with this kind of machine
- **But...**
  - Doesn't replace entire linac → 200 MHz PA's would still be a vulnerability, aging linac equipment still an issue
  - Cycle time is still 15 Hz → it would still take 5/15 of a sec to fill MI with 6 booster batches → limits upgrades to the MI cycle time (Beam power is proportional to # p/cycle x cycles/sec)
  - Large aperture rapid cycling magnets → development
  - Significant interruption of operations to upgrade linac and break into various enclosures (vs Run II)
  - Losses, instabilities, etc... vs ultimate performance ?



# PD: 8 GeV SC Linac

- Basic concept, design, (& slides) are due to **Bill Foster** at FNAL
- Observation: \$/ GeV for SCRF has fallen dramatically → can consider a solution in which H- beam is accelerated to 8 GeV in a SC linac and injected directly into the Main Injector
- Why an SCRF Linac looks attractive:
  - Many components exist (few parts to design vs new booster synchrotron)
    - Copy SNS, RIA, & AccSys Linac up to 1.2 GeV
    - Use “TESLA” Cryo modules from 1.2 → 8 GeV
  - Probably simpler to operate vs two machines (ie linac + booster)
  - Produces very small emittances vs a synchrotron
  - Delivers high beam powers simultaneously at 8 & 120 GeV
- Injection into MI is done with 90 turns of small transverse emittance beam ( $2\pi$  mm-mrad, 95% normalized) which is “phase space painted” into MI ( $40\pi$ ) aperture in 1 ms → MI “fill time” that is negligible vs MI ramp times (more later)





[illegible]

Fermilab  
Technical Division



# DOE Program Review: FLRP:Proton Driver

March 24, 2004

11



# Other Possible SCRF Linac Missions

---

- **Principle Mission: Proton superbeams for Neutrinos**
  - 8 GeV or 120 GeV from MI (NUMI/Off-axis = NOvA)
- **Also:**
  - Protons for future 120 GeV fixed target experiments and continued anti-proton production
- **Other possibilities:**
  - Protons:
    - Could Drive a Future Neutrino Factory
    - Could Drive a Spallation Neutron source
    - Could serve as a low emittance injector to a future VLHC
  - Accelerate electrons ?
    - Could drive an x-ray FEL
    - Could be useful for LC beam or technology studies



# Technological Synergies

---

- **Lots of labs use or plan use of SCRF**
- **This provides many opportunities for collaboration and shared infrastructure/development costs**
- **Other Accelerators:**
  - Existing: ATLAS (ANL), CBEAF, FNPL, TTF-I (DESY)
  - Construction: SNS (ORNL), DESY FEL
  - Proposed:
    - Cold Technology Linear Collider (TESLA),
    - RIA (ANL)
    - Light sources: LUX (LBNL), Cornell light source, PERL (BNL), MIT (Bates)
    - Electron cooling in RHIC (BNL), eRHIC (BNL)
    - BNL proton superbeam proposes 1.2 GeV SCRF Linac
    - SC linac is being discussed as part of the LHC upgrade
    - Medical isotope production, etc



# A Draft Design Study exists

SCRF Proton Driver – working Draft Writup\_v42.doc Created on 11/15/2003 3:03 PM

\*\*\* DRAFT \*\*\*

FINAL-TM-2169 (Part II)

**8 GeV Superconducting Injector Linac  
Design Study**

1	INTRODUCTION.....	5
2	MOTIVATION FOR THE 8 GeV LINAC.....	7
2.1	Multi-Mission Linac.....	7
2.2	Main Injector Operations with the 8 GeV Linac.....	8
2.3	Relevance to Future Accelerator Projects.....	9
2.4	Superconducting RF Technology.....	11
3	DESIGN OVERVIEW.....	13
3.1	Front-End Warm Linac (0-87 MeV) Overview.....	13
3.2	Superconducting RF (SCRF) Linac (87 MeV – 8 GeV) Overview.....	14
3.3	RF Power Systems - Overview.....	15
3.4	Civil Construction Overview.....	16
3.5	Site Selection.....	18
3.6	One-Tunnel vs. Two-Tunnel Machine Layout.....	19
3.7	Underground Klystron Gallery.....	20
3.8	Tunnel Depth and Shielding.....	20
4	CHOICE OF PRIMARY PARAMETERS.....	21
4.1	Beam Energy.....	21
4.2	Beam Charge per Pulse.....	21
4.3	Beam Current and Pulse Width.....	21
4.4	Linac Pulse Repetition Rate (Average Beam Power).....	22
4.5	Different Particle Types in the 8 GeV Linac.....	23
5	ACCELERATOR PHYSICS.....	24
5.1	Baseline Lattice and Cavity Layout.....	24
5.2	Transverse Focusing.....	25
5.3	Longitudinal Focusing and Frequency Jumps.....	26
5.4	Linac Aperture.....	26
5.5	H-Stripping from Magnetic Fields and Energy Upgrades.....	28
5.6	Energy Stability and Cavity Resonance Control.....	29
5.7	Multiple Cavities per Klystron.....	29
5.8	Debuncher Cavity (Optional).....	30
6	RUNNING ELECTRONS AND PROTONS IN THE SAME LINAC.....	31
6.1	Efficiency for accelerating e+ with cavities designed for lower Beta.....	31
6.2	Cavity Phase Shifts Between e- and p with Many Cavities per Klystron.....	32
6.3	Sharing Transverse Focusing between Electrons & Protons.....	33
7	FRONT-END LINAC.....	34
7.1	Technological Options for the Front-End Linac.....	34
7.2	Front-End Accelerator Physics and Tank Design.....	34

- **Web Link:**

<http://tdserver1.fnal.gov/project/8GeVLinac/DesignStudy/>  
131 page document

- **Plan: Next Few Weeks:**

- Merge with PD II Design Study

- **Technically it looks to be feasible**

- **Principle issue is the cost**

- SNS was very expensive but there are reasons that this was so...

- TESLA appears to be very cheap / GeV

- Need to do a careful Technical Design Report including optimization and costs

- **That's the plan (more later)**



# 8 GeV Linac Baseline

Design Study (130 pages): <http://tdserver1.fnal.gov/project/8gevlac>

---

- Warm Copper DTL
- 805 MHz SNS & RIA Cavities to 1.3 GeV
- Modified TESLA (1207.5 MHz) to 8 GeV
- 48 “TTF-style” Cryomodules
- 384 Cavities (assuming TESLA-500 Gradients)

## New Technology:

*Extend TESLA RF Fan-Out to Proton/H- Linac*


- *41 Klystrons in baseline design*







# TESLA-Style Cryomodules for 8 GeV



## Design conceptually similar to TESLA


- No large cold gas return pipe
- Cryostat diameter ~ LHC

**RF Couplers are KEK / SNS design, conductively cooled for 10 Hz operation**

**Cold string length ~ 300m  
vs every module in SNS  
=> cheaper (more like TESLA)**




# 8 GeV Linac Baseline 2 MW




## 8 GeV 2 MW LINAC

41 Klystrons (3 types)  
31 Modulators 20 MW ea.  
7 Warm Linac Loads  
48 Cryomodules  
384 Superconducting Cavities




10 Klystrons  
96 cavites in 12 Cryomodules



## "TESLA" LINAC

1207 MHz Beta=1

24 Klystrons  
288 cavites in 36 Cryomodules



# 8 GeV Linac Parameters

## 8 GeV LINAC

Energy	GeV	8
Particle Type	H- Ions, <del>Protons</del> , or Electrons	
Rep. Rate	Hz	10
Active Length	m	671
Beam Current	mA	25
Pulse Length	msec	1
Beam Intensity	P / pulse	1.5E+14 (can be H-, P, or e-)
	P/hour	5.4E+18
Linac Beam Power	MW avg.	2
	MW peak	200

## MAIN INJECTOR WITH 8 GeV LINAC

MI Beam Energy	GeV	120	
MI Beam Power	MW	2.0	
MI Cycle Time	sec	1.5	filling time = 1msec
MI Protons/cycle		1.5E+14	5x design
MI Protons/hr	P / hr	3.6E+17	
H-minus Injection	turns	90	SNS = 1060 turns
MI Beam Current	mA	2250	




# RF System for 1.2→ 8 GeV Linac

---

- **Assumes TESLA-style RF distribution works**
  - One TESLA multi-beam Klystron per ~12 Cavities
- **Requires a “fast ferrite” E-H tuner to control the phase and amplitude to each cavity**
  - The fundamental technology is proven in phased-array radar transmitters.
  - This R&D was started by SNS but dropped due to lack of time.
  - R&D is required to optimize the design for the Linac, funding in TD FY04 budget to start this effort
  - Also needed if Linac alternates between e and P.
- **Modulators are identical to TESLA modulators**



# RF Fanout at Each Cavity




# ELECTRONICALLY ADJUSTABLE E-H TUNER

MICROWAVE INPUT POWER  
from Klystron and Circulator

## E-H TUNER

ELECTRONIC TUNING  
WITH BIASED FERRITE



Attractive  
Price Quote  
from AFT  
( $\ll$  Klystron)

**TWO COILS** PROVIDE INDEPENDENT  
**PHASE AND AMPLITUDE** CONTROL OF CAVITIES



# Cost Optimizations & Options

---

- **Staging: Extend Klystron Fanout 12:1 → 36:1**
  - Drop beam current, extend pulse width
  - Drop rep. rate & avg. power 2 MW → 0.5 MW at 8 GeV
  - Still delivers 2 MW from MI at 120 GeV
- **Consider SCRF Front End (RIA Spokes)**
- **Assume TESLA 800 surface fields will work:**
  - Baseline 5 GeV linac by assuming TESLA 500 gradients,
  - Deliver 8 GeV linac by achieving TESLA 800 gradients.

**384 Cavities → 240 cavities ;      Linac Length: 650m → 400**



# Frequency Options

---

## 1. Standardize on SNS / RIA (805 MHz)

- Develop “modified TESLA” 1207.5 MHz cavities
- Develop Modified Multi-Beam Klystron
- Develop new spoke resonator family if SCRF

## 2. Standardize on TESLA (1300 MHz)

- Develop new family of “TESLA-Compatible”  $\beta < 1$  cavities
- Already 3 vendors for main MBK
- Develop new spoke resonator family if SCRF






# Main Injector with 8 GeV Linac

- **H<sup>-</sup> stripping injection at 8 GeV**
  - 25 mA linac beam current
  - 90-turn Injection gives MI Beam Current  $\sim 2.3$  A  
(*SNS has 1060 turn injection at 1 GeV*)
  - preserve linac emittances  $\sim 2\pi$  (or even  $\sim 0.5\pi$  (95%) at low currents)
  - phase space painting needed at high currents
  - avoids space charge limitations present at lower energy
- *can put a **LOT** of beam in MI !*
- **1.5 Second Cycle time to 120 GeV**
  - filling time 1 msec or less
  - no delay for multiple Booster Batches
  - no beam gaps for “Booster Batches” -- only Abort gap
  - Even faster MI cycle times can be considered ( x 2 ?)




# 120 GeV Main Injector Cycle with 8 GeV Synchrotron





# 120 GeV Main Injector Cycle with 8 GeV Linac, e- and P

**Main Injector: 120 GeV, 0.67 Hz Cycle, 2.0 MW Beam Power**  
**Linac Protons: 8 GeV, 4.67 Hz Cycle, 0.93 MW Beam Power**  
**Linac Electrons: 8 GeV, 4.67 Hz Cycle, 0.93 MW Beam Power**  
**8 GeV Linac Cycles 1.5E14 per Pulse at 10Hz**



# Linac Allows Reduced MI Beam Energy without Compromising Beam Power

Main Injector: 40 GeV, 2.0 Hz Cycle, 2.0 MW Beam Power  
Linac Protons: 8 GeV, 4.0 Hz Cycle, 0.8 MW Beam Power  
Linac Electrons: 8 GeV, 4.0 Hz Cycle, 0.8 MW Beam Power  
8 GeV Linac Cycles 1.5E14 per Pulse at 10Hz



- # neutrinos ~ same
- Reduces tail at higher neutrino energies.
- May be a useful operating mode

**MI cycles to 40 GeV at 2Hz, retains  
2 MW MI beam power**



# Comparison of PD options

Parameters	Present Proton Source	Proton Driver synchrotron (PD2)	Proton Driver SCRF Linac	Proton Driver SCRF Linac and MI upgrade ?
<b>Linac</b> (Pulse Freq)	5 Hz	15 Hz	10 Hz	10 Hz
Kinetic energy (MeV)	400	600	8000	8000
Peak current (mA)	40	50	28	28
Pulse length ( $\mu$ s)	25	90	1000	1000
<b>Booster</b> (cycles at 15 Hz)				
Extraction kinetic energy (Gev)	8	8	-	-
Protons per cycle	$5 \times 10^{12}$	$2.5 \times 10^{13}$	-	-
Protons per hour	$9 \times 10^{16}$ (5 Hz)	$1.4 \times 10^{18}$	-	-
8 GeV Beam Power (MW)	0.033 ( 5 Hz)	0.5	2	2
<b>Main Injector</b>				
Extraction Energy for NuMI ( GeV)	120	120	120	120
Protons per cycle	$3 \times 10^{13}$	$1.5 \times 10^{14}$	$1.5 \times 10^{14}$	$1.5 \times 10^{14}$
fill time (sec)	0.4 ( 5/15+0.1)	0.4 ( 5/15+0.1)	0.1	0.1
ramp time (sec)	1.47	1.13	1.4	0.7
cycle time (sec)	1.87	1.53	1.5	0.8
Protons per hour	$5.8 \times 10^{16}$	$3.5 \times 10^{17}$	$3.5 \times 10^{17}$	$6.6 \times 10^{17}$
Ave Beam Power (MW)	0.3	1.9	1.9	3.6

- **My conclusions: The SCRF Linac PD is more likely to deliver the desired performance, is more “flexible” machine than the synchrotron based PD, and has more “growth” potential**



# FLRPC: PD Recommendations

---

- We recommend that Fermilab prepare a case sufficient to achieve a statement of mission need (CD-0) for a 2 MW proton source (Proton Driver). We envision this project to be a coordinated combination of upgrades to existing machines and new construction.
- We recommend that Fermilab elaborate the physics case for a Proton Driver and develop the design for a superconducting linear accelerator to replace the existing Linac-Booster system. Fermilab should prepare project management documentation including cost & schedule estimates and a plan for the required R&D. Cost & schedule estimates for Proton Driver based on a new booster synchrotron and new linac should be produced for comparison. A Technical Design Report should be prepared for the chosen technology.



# CONCLUSIONS

---

- Understanding the physics of neutrino oscillations, the mass hierarchy, and perhaps CP violation in the neutrino sector requires a new generation of long baseline neutrino experiments → a new intense proton source (Proton Driver)
- Similar in scope to the Main Injector Project (cost/schedule)
- A 8 GeV Synchrotron or a Superconducting Linac appear to be both technically possible. However the SCRF linac has many attractive features if it can be made affordable
- The FNAL management has requested (charge) that the 8 GeV linac design be developed including cost & schedule information so that a technology choice can be made.
- Documentation in support of establishment of mission need, including both technical design and physics studies, will be produced in the next year.
- It is likely this will lead to a request for CD-0 from the DOE

