

## Linear Collider R&D

### Shekhar Mishra

Linear Collider R&D
Technical Division
Fermilab
3/24/04



### **Contents**

- Introduction
- Accelerator Physics Studies at Fermilab
  - Damping Ring
  - Emittance Preservation in Linac
  - Engineering Test Facility
- Status of Current R&D
  - Warm Technology
  - SCRF Technology
- Fermilab & LC Technology Decision
- Summary



### Introduction

- Fermilab is the only laboratory in the US Laboratory that is collaborating on both warm (NLC) and SRF (TESLA) linear collider technology R&D.
- Accelerator Physicists and Engineering staff from Technical
   Division and Accelerator Division have contributed significantly
   to both the Linear Collider designs.
- Fermilab ESS has played a leading role in the US site studies for the Linear Collider sites in Illinois and California.
- Fermilab Particle Physicists are working on four major detector components R&D and coordinating simulation efforts.

# Accelerator Physics Studies

- The key to the success of the Linear Collider is production and transport of low emittance beam to IR.
- At the start of our accelerator physics effort we have decided to look at
  - Damping Rings for TESLA and Pre-Damping Ring for NLC
  - Emittance preservation in LINAC and alignment requirements.
  - Electron Beam Physics modeling tools

# TESLA Damping Ring

- TESLA design of Linear Collider requires 2820 bunches of electrons at ~335 nsec spacing. This makes the TESLA Damping Ring rather long.
- The present design of the TESLA Damping Ring though technically sound is 17 kms long. The key limitation being faster kicker.
- We are investigating several ideas on a faster kicker scheme by developing a common lattice design.
- We are developing conceptual design(s) for these kickers and how to test its performance.

# Damping Ring Studies

Multi-Bunch Trains with inter-train gaps


empty buckets

extraction

line

filled buckets

RF cavities




- always inject and eject the last bunch in a train
- kicker rise time < 6 ns, but fall time can be ~gap length
- beam loading maintained by ~100 m ring with shared RF system
- ~6 km ring filled by transfers of undamped trains from the ~100 m ring

  J. Rogers

injection



### Longitudinal RF followed by Dispersive Section




- kicker rise, fall times can be 4× bunch spacing
- could be combined with #1 to accommodate longer fall-time kicker

### D. Rubin




# Fourier Series Kicker




- kicker is a series of N transverse RF cavities tuned to frequencies which differ by ~3 MHz.
- proper adjustment of amplitudes and phases kicks one bunch while leaving the next (N-1) undisturbed.
- SCRF + transverse kick minimizes beam-induced fields in cavities.
   G. Gollin





6 kms, 6 straight sections, 25 wigglers.

Workshop at Fermilab: ANL, LBNL, SLAC, Cornell, DESY, FNAL...



# Comparison of two designs

Parameter	Small ring (e <sup>+</sup> /e <sup>-</sup> )	Dogbone (e <sup>+</sup> /e <sup>-</sup> )
Energy	5 GeV	5 GeV
Circumference	6.12 km	17 km
Horizontal emittance $\gamma e_x$	$2.5 \times 10^{-6} \text{ m}$	$8 \times 10^{-6} \text{ m}$
Vertical emittance $\gamma e_y$	$0.02 \times 10^{-6} \text{ m}$	$0.02 \times 10^{-6} \text{ m}$
Transverse damping time $\tau_d$	28 ms / 44 ms	28 ms / 50 ms
Current	444 mA	160 mA
Energy loss/turn	7.3 MeV / 4.7 MeV	21 MeV / 12 MeV
Radiated power	3.25 MW / 2.1 MW	3.2 MW / 1.8 MW
Tunes $Q_x$ , $Q_y$	62.18, 28.38	72.28, 44.18
Chromaticities $\xi_x$ , $\xi_y$	-112, -64	-125, -68

We are working on further developing these Kicker ideas.


### Low Emittance Transport in Main Linac

- Damping Rings generate Low Emittance Beam this Emittance must be preserved through, Bunch Compressor, Main Linac and the Beam Delivery System.
- Emittance Budget in Main Linac (NLC) from DR extraction: 3.3% in horizontal and 50% of vertical plane.
- Emittance growth in the Linac is caused by
  - Single Bunch: Transverse wakefield resonantly drives the tail of bunch in betatron oscillation
  - Multi Bunch: Leading bunch deflects trailing bunch center.
  - Incoherent Sources: Misalignments and quadrupole errors
  - Ferbrication error (Straightness of RF structure and HOM frequency error.) reduces the effect of LR wake suppression.




# Study of Beam Based Alignment

- Alignment tolerances can not be met by *ab initio* installation.
- Quads and RF structures need to be aligned with beam-based measurements.
- Two methods
  - French Curve: Read all BPMs, compute magnet moves, align RF
  - Dispersion Free Alignment




- Temotely controlled Translation Stages for quads and RF girders
- High resolution BPMs in Quads and RF structures



DFS: Lower mean emittance growth than FC


DFS is More effective in vertical plane.

### **Structure-to-Girder Offset**




Structure-to-Girder misalignment (x Normal)

### **BPM Resolution**



- $\rightarrow \gamma e_y \& \gamma e_x$  growth in FC:
  - lesser dependence, but,
  - much above tolerance.

- $\triangleright \gamma e_y \& \gamma e_x$  growth in DFS:
  - depends heavily on BPM resolution.
  - should remain within Nominal values.





# Engineering Test Facility for LC

- At present there are Test Facilities at SLAC, KEK and DESY that are designed to do LC R&D.
- We believe that next generation of LC Engineering Test Facility is needed for a complete system test of the Linear Collider and accelerator physics.
- The scope of such a facility needs to be defined.
- To be most effective this proposal should be developed by the U.S./International linear collider collaboration(s).
- Fermilab is taking a leading in organizing the ETF effort.
   We assume that the emerging design would go to the Global Design Organization as a proposal.



# Thoughts on the Scope of ETF

- It must be done with International collaboration.
- It should have the capability to do perform beam studies.
- ETF could be 1% demonstration machine for the technology chosen by ITRP in the final machine configuration.
- It could have an Injector, Linac (5 GeV), Damping Ring, post damping ring Linac (~0.5 GeV-5.0 GeV)
- It could be a development facility for the Instrumentation, controls etc needed for the LC.
- It could be a development facility for one of a kind device.
- It could be used for industrialization/ later testing of the major component.

# **NLC R&D Overview**

- X-Band RF Structure Design and Fabrication
  - Review of cell table of SLAC disk design, construction with local industry, QC of the RF disk
  - Frequency tuning of the single disk (if needed).
  - Fabrication of 60 cm RF structure
  - Frequency tuning of the assembled RF Structure
- RF Design work
  - Design of the Fermilab wave guide coupler for FXB, FXC and FXD Structures
  - FXD HOM extraction design and analysis
  - Design of Fermilab Structure FXE

# RF Structure Factory



RF Quality Control Clean Room (Class 3000)

 Disks & Couplers are precision machined, no diamond turning (industrial vendors) • Brazed structures, no diffusion bonding

A Structure during Bead-Pull Measurements & Tuning





### Warm LC RF Structure Disks

- FXB: 60 cm. Long, high phase advance (150 deg.), traveling wave structures (aka H60VG3, no slots ) were produced. (FXB001-006)

**–FXC:** 60 cm. long, 61 mm o.d. cells; 150 degree phase advance; 3% group velocity; slotted cells with .17 a/λ; fully brazed construction w/o H<sub>2</sub>; Fermilab Wave guide (FWG) I/O couplers and matching cells, no HOM extraction,  $\frac{4 \text{ tuning holes}}{4 \text{ tuning holes}}$  instead of the 2 in FXB structures. (FXC001-005)




•FXD: 60 cm. long, 61 mm o.d. cells; 150 degree phase advance; 4% group velocity; tapered design with slotted cells and .17 a/ $\lambda$ ; fully brazed construction w/o H2; FWG I/O couplers; I/O HOM extraction; twofold interleaving design feature. (FXD001-006)




• FXE: Fully Fermilab Designed

### **FX-band Structures at NLCTA**

- Four structures currently operating at NLCTA were fabricated by Fermilab.
- FXB-006 is the first structure built by anyone to achieve NLC specification for gradient and breakdown rate (<0.1 breakdown/hour @ 60 Hz, 400 nsec, 65MV/m)





FXB-006 FXC-001


■ FXC003 has also met the NLC design goals.



### Processing results from the 4 latest NLC/GLC prototype structures


### 3 out of 4 exceed breakdown rate requirements at 65 MV/m

### NLC/GLC design pulse







### FXC-003 golden run at 65 MV/m with the NLC/GLC design pulse




Breakdown rate: 0.038 /h (3 trips in 80h at 65 MV/m)

### Eight Pack Phase 2: Power Handling






# **Strongback Production**







• We produced nine structure supporting systems known as "strongbacks" (six for NLCTA use at SLAC, and three for use in girder development at FNAL)




# **Vibration studies @ MP8**

### Studies:

- Effect of cooling water on structures stability
- Comparison of Al and SS strongbacks
- Effect of vacuum on vibration transmission
- Transmission of vibration to quads (PM EM)

Study on more realistic supports

- Effect of movers on structure stability
- Adding more constrains: waveguides



In Collaboration with SLAC and Northwestern University we are setting up a ground motion experiment in the NUMI/MINOS tunnel.

# Overview of SCRF activities

### Linear Collider R&D

- For TESLA we built modulators and electron guns for TTF at DESY (AD) and designed vertical test dewars and cryostats
- The A0 photo-injector at FNAL is very similar to TTF and uses TESLA acceleration cavities
- We also are designing and building a 3.9 GHz 3<sup>rd</sup> harmonic cavity. The purpose is to diminish the beam energy spread so that the electron pulse length can be made very short via a magnetic chicane

### CKM

 FNAL has been doing R&D to build 3.9 GHz transverse kick cavities for an experiment proposed at FNAL that needs an RF separated K beam

### Proton Driver

• FNAL has a design study in progress for an intense Proton Source based upon a 8-GeV SC linac

## **FNAL SCRF Technical Capabilities**

- Both in the FNAL Accelerator Division (AD) and Technical Division (TD) have significant design capabilities useful for SCRF work
  - Cryogenic Engineering and Design
    - Engineers with experience on big cryogenic systems (Tevatron)
    - Designed 1.8 K cryostats for LHC IR quadropoles in TD
    - Test them at 1.8 in FNAL Magnet Test Facility
  - RF Engineering and Design
    - RF design engineers
    - Modern FR Engineering Software and design tools
    - Computing equipment
    - Improved modeling/analysis techniques
    - (eg working on the design of xband NLC structures and couplers)
- We also have been collaborating with ANL and DESY on SRF Cavity Surface Treatment Facility and plan to expand our collaborations with other labs and universities


# SCRF R&D


- ► FNAL is currently doing some Superconducting RF R&D that can benefit to the TESLA proposal (3-d harmonic system development)
- TD RF group is working on SCRF R&D for two FNAL projects that build SCRF capabilities relevant to a LC if the technology decision is for a cold machine
  - CKM: Collaboration with BD. Goal is to provide SC RF cavities (transverse kick mode) to be used to generate a separated charged K beam for the CKM experiment
  - A0 3<sup>rd</sup> Harmonic cavity: Goal is to provide a 3.9 GHz accelerating cavity to reduce longitudinal energy spread of high current electron pulses from the A0 photo-injector. (Note: TESLA would like us to build one of these for TTF-II also so there continues to be collaboration in this area)

# SCRF R&D

- Building our capabilities for the future
  - Develop and build elements of a SRF module fabrication and test infrastructure
  - Design and build a prototype of a 3.9 GHz accelerating cavity for the Photo-Injector Test Stand


Develop a microphonics compensation system





### 3.9 GHz accelerating cavity

- 9-cell cavity and helium tank design and fabrication
- HOM coupler design and fabrication
- Cell and cavity design and prototyping










### SCRF Module Fabrication

Cryostat for CKM cavity testing









### **SCRF** Module Fabrication


### Microphonics Detuning Compensation





Automatic compensation with adaptive feedforward control method demonstrated in a 13-cell CKM cavity at room temperature.









# Cold Test of the 3.9GHz 3-cell cavity in the Vertical Cryostat

Tested after 140 µm BCP, heat treatment and HPR










# **Surface treatment facility**

**Process Compartment Design** 

Mockup @ FNAL TD MDL







# **Eddy Current Scanner**

**Scanning Equipment From SNS** 

• IB2 temporary location

Power hookup


• 100 psi Air line connection

Leveling





### Linear Collider Site Studies





### Fermilab and LC Technology Decision

- We are also developing detector collaboration with in US and except that Fermilab will play a major role in such a collaboration.
  - Fermilab has considerable experience in building large detectors, Silicon, Tracking Chambers, Muon & Calorimeter.
  - Computing Infrastructure and GRID
- •Illinois and Fermilab is an ideal choice for the Linear Collider site.
- We are working with local universities and ANL to bid to host Linear Collider in Illinois after the technology selection.

# Summary

- Fermilab has made significant contributions to both the NLC and TESLA R&D.
- Fermilab is aligning itself to be a significant player in the Linear Collider
  - We will continue and expand our efforts in the accelerator, detector and IL site studies.
  - We are increasing our effort in the accelerator physics in Main Linac and Damping Ring.
  - We are proposing to build a LC ETF (warm or cold) at Fermilab to be in line with technology decision with U.S. and International linear collider collaborations.
- We are increasing Fermilab and Illinois presence within the LC collaboration(s).
- We are taking an active role in US and International efforts on LC. Fermilab DOF Annual Review