



CDF Upgrade Status

Patrick Lukens
Fermilab



CDF Upgrades

- Silicon Detector
- Calorimeter upgrades
 - Preshower replacement
 - Current Preshower is gas chamber – 4 crossing memory
 - Replacement is scintillator
 - Same technology as endplug
 - EM Timing
 - Provide timing information from EM calorimeter
- Data Acquisition/Trigger Upgrades – to handle 1 kHz
 - TDC replacement
 - Level 2 trigger decision crate
 - Track trigger upgrade
 - Event builder upgrade
 - Level 3 computer upgrade
 - Silicon trigger upgrades



Recent Events

- The most significant event of the past year for the CDF Upgrade programs was the cancellation of the silicon detector upgrade.
- There is now a new baseline for the project
 - Scope of all non-silicon upgrades remains the same.
 - Some elements of the silicon project were retained
 - Items for long term maintenance
 - The silicon work is being “closed out” in a meaningful way
 - “Preproduction” staves (~7%) being assembled and read out
 - Results will be published – interest in the work at BNL, Jeff. Lab



New Baseline

- The rebaselining of the CDF upgrades was approved at the ESAAB on 8 Dec 2003.
- Silicon costs include money spent to date and a few items that were retained.

	2002 Baseline (\$K)		New Scope (\$K)	
	Cost	Cont.	Cost	Cont.
Silicon	\$ 12,008	\$ 5,145	\$ 2,527	\$ 396
Calorimeter	\$ 342	\$ 335	\$ 342	\$ 335
DAQ	\$ 3,788	\$ 1,678	\$ 3,788	\$ 1,678
Admin.	\$ 1,285	\$ 407	\$ 1,006	\$ 302
Total	\$ 17,422	\$ 7,565	\$ 7,663	\$ 2,711
	24,987		10375	




Silicon Upgrades

- Several silicon related subprojects were retained in the rebaseline exercise.
 - Money may be needed to preserve the existing detector longer and with higher occupancy than planned.
- Radiation monitoring, interlock upgrades, DAQ upgrades, and SVT upgrades have budget set aside.
- A Silicon Longevity Committee was created to identify the areas where upgrades/replacements are needed.
 - This will guide our direction here.



Calorimeter Upgrades

- The Preshower project has begun module production
- Parts are ordered and are coming in
 - 700 (of 2600) scintillator tiles this month
 - All phototubes are in hand
 - 4 CPR modules by April, 2 wedges/week afterwards.
- Good chance to be ready for a fall 2004 installation.




PMT holder



Preshower Installation

- Installation requires the calorimeter arches to be extracted
- Procedures are being developed to do this in the collision hall.
- During last week's access
 - Discussed JHA, installation procedures
 - Finalized scaffold design
 - Tested PMT box installation

CPR location





TDC Progress

- Prototype TDC released for fabrication in January
 - First board with power distribution and VME interface delivered in February 10
 - No problems found with VME or power
 - Released assembly of 2 fully populated boards
 - Two fully populated boards delivered March 1
 - Complete test of interface to VME
 - Tests of TDC chip functionality
 - Preparing tests of trigger output
- All tests so far are successful (~60% of functionality tested)
 - Few problems solved by modifying firmware



New TDC Board

Altera Stratix:

- TDC
- L1/L2 Buffering/Readout
- XFT Hit Generation

VME Interface

Input
Connectors
And
LVDS
Receivers

CDF
Clock and
Control
Interface

Trigger
Output
Drivers
(to XFT)

DC Power
convertors




Level 2 Trigger Upgrade

- Level 2 replaces the Alpha based system
- Based on multiple Pulsar boards – PC for algorithms
- Faster, more maintainable than original system
- Production orders placed for the full set of Pulsars
- Commissioning is planned for this summer
 - Each data path should be run by June
 - Full parasitic operation before the shutdown in August.



Pulsar Design

→ modular/universal/self-testable



Pulsar design philosophy: able to interface with any user data with any link format (e.g. S-LINK or GbE) via mezzanine
Many applications within & outside CDF (compatible with Atlas)



Track Trigger Upgrade

- Track Trigger (XFT) design
 - Improves timing resolution at the trigger level
 - Incorporates stereo information at the trigger level
- Recent luminosity increases and COT aging issues have reinforced our need for this upgrade.
 - Also made it difficult, since the manpower is diverted.
- This project is behind schedule
 - The group is still committed to building it.
 - Simulation of our operating conditions is in progress
- We plan a review of the schedule/scope for early May



Event Builder Status

- Originally an upgrade of the ATM switch, new baseline is based on Gigabit ethernet.
- The project is well underway:
 - Final system switch installed on the 3rd floor
 - VME to switch readout: VMIVME-7805
 - GbE switch: Cisco 6509
 - Expertise on board (from both CD and CDF)
 - Working prototype by Aug 2004
- Completion on schedule (Summer 2005) should not be a challenge.



Fall 2004 shutdown

- Our goals for the shutdown (23 Aug. – 5 Dec.) are
 - Complete the EM timing installation
 - Endplug is done, central remains (10% done now, working well)
 - Install as much Preshower system as possible
- At this point, we do not plan to set the duration of the shutdown
 - Our work will fit in the time available.
- Our schedule for installation activities is ~10 weeks.
 - Maintenance may add more, so the time will be tight



Conclusions

- Calorimeter activity is working hard towards the goal of readiness for a 2004 installation
 - Timing is ready now
 - Hardware is available
 - Commissioning is in progress for portions installed
 - Preshower is confident they can make it.
 - Still many modules to build
 - Installation procedure is not yet fully designed
 - Module production has begun, phototubes are in hand



Conclusions

- TDCs have made progress
 - More people are needed, and a couple are close to joining.
- XFT has a large group, and can probably rally
 - Internal review of this in May.
- Event builder upgrade is probably fine.
- Silicon plans need to be resolved
 - Longevity committee will guide this.