



Overview of Plans for High Intensity Neutrino Beams

R. Dixon




Overview

- High Intensity Neutrino Beams using existing Accelerator infrastructure
 - Historical Perspective
 - Status of Plan
 - Preview of upgrades necessary





Historical Highlights


- 2005-- Laboratory and DOE conclude that Tevatron is likely to be decommissioned by about 2010
- 2005-- Proton Plan to increase proton intensities for NuMI and the Booster Neutrino Beam (BNB) baselined
- Dave McGinnis (and others) realize that decommissioning the collider frees up infrastructure that could be used to support the Laboratory's neutrino program before or instead of a Proton Driver
- Alternate Proton Source (APS) concept developed by Dave McGinnis
 - Plan has the advantage that it can be staged
 - Early stages are relatively low cost and there is benefit after each stage is completed
- APS shown to Physics Advisory Committee at June, 2005 meeting
 - Plan was discussed as a backup plan for NOvA should there be no Proton Driver
- Spring, 2006 becomes an official part of Lab strategy for providing neutrino beam to NOvA
 - I charge a small group led by Alberto Marchionni to develop a plan for 700 kW
 - Work begins work to define a project-- SNuMI (Superbeam upgrade to NuMI)




Accelerator Layout









The power of neutrino beams




J-Park: path to a few MW facility is being studied



NuMI Operational Issues*




*slide courtesy Jim Hylan




Charge for First Stage

- “I would now like you to develop a conceptual design and cost estimate for a modification to the Recycler and Main Injector to provide a 0.7 MW 120 GeV beam to NuMI after the collider program ends. The main feature of this upgrade is to convert the Recycler into a proton accumulator, shortening the Main Injector cycle time from 2.2 seconds to 1.5 seconds. . .
- The conceptual design should consider all aspects of high power acceleration and transport; beam stability, RF power, instrumentation, collimation, transport and targeting, radiation shielding, groundwater and air activation for all facilities . . .”




Complete Proton Plan

- 400 KW Neutrino Beam
 - Booster at 9 Hz
 - Intensity = $\sim 5 \times 10^{12}$ per batch
 - MI ~ 4 to 5×10^{13} per cycle
- Requires Proton Plan improvements to Linac, Booster, and MI
 - Highlights
 - Loss Reduction in Booster and Main Injector
 - Increase cycle time of Booster
 - Booster injection improvements
 - New correction elements
 - Slip Stacking in the Main Injector
 - MI aperture and collimation




700 kW Neutrino Beam


- Upgrade Booster to 15 Hz operation
- Convert Recycler to Proton Pre-injector
 - Construct new Injection line from MI-8 line into Recycler
 - Add 2 RF systems to Recycler
 - Implement Slip Stacking in Recycler
- Results
 - Reduces cycle time of MI to ~1.5 sec
 - MI Intensity --> 5.4×10^{13}
 - Beam Power ~ 700 kW




1 Megawatt Neutrino Beam


- Tevatron decommissioned
 - Add injection line from Booster to the Antiproton Accumulator
 - Momentum Stack up to 4 Booster batches in the Accumulator
 - Transfer accumulator beam into Recycler
- What is needed
 - New RF system in Main Injector
 - New injection line for the Accumulator





Construction for Accumulator Adding Accumulator






Beam, Target, and Horn

- Issues

- Beam certification-- probably straightforward
- Target-- NOvA medium energy horn less constrained than present situation ==> flexibility in design
- Thermal shock
- Humidity in Target Chase
- Decay Pipe Window
- Hadron Absorber
- Shielding assessment and ground water protection




Possible Schedule Scenario

- Shutdown in 2010 for approximately a year to complete work for achieving 1MW
 - Turn beam on in 2011 at 700 kW
 - Running at 1 kW steadily in 2013


This does not take full advantage of staging

Staging gives us additional flexibility



Benefits of Staging

- Because the concept uses existing infrastructure the performance can be broken into stages
- Project staging has the important benefit of providing
 - a fraction of the total performance
 - at a fraction of the total cost
- The schedule for each stage is driven by physics need and funding availability
- Each stage is based on standard accelerator technology and accelerator parameters that are currently achievable.



Summary

- Upgrading existing infrastructure can deliver up to 1 Megawatt neutrino beams without large costs
- Technical Challenges do not appear insurmountable
 - No new technology is necessary
 - Some construction
 - Total cost < \$50M
- Conservative schedule scenario has 1 MW beam by 2013
 - 700 kW beam could be running in 2011