



Report for ILC-PAC

SCRF and ML Technology

Presented by Akira Yamamoto
ILC-GDE PM-SCRF and KEK
for Project Managers
Marc Ross, Nick Walker, and A. Yamamoto

To be presented at ILC-PAC Review, May 9, 2009

090509 ILC-PAC Review: SCRF 1



Outline


- Introduction
- R&D Status
- Plan for Technical Design Phase
- Global Plan and Project Management
- Summary

090509 ILC-PAC Review: SCRF 2



SCRF Technology Required

Parameter	Value
C.M. Energy	500 GeV
Peak luminosity	$2 \times 10^{34} \text{ cm}^{-2} \text{ s}^{-1}$
Beam Rep. rate	5 Hz
Pulse time duration	1 ms
Average beam current	9 mA (in pulse)
Av. field gradient	31.5 MV/m
# 9-cell cavity	14,560
# cryomodule	1,680
# RF units	560





090509 ILC-PAC Review: SCRF 3



TDP Goals of ILC-SCRF R&D

- **Field Gradient**
 - 35 MV/m for cavity performance in vertical test (S0)
 - 31.5 MV/m for operational gradient in cryomodule
 - to build two x 11 km SCRF main linacs
- **Cavity Integration with Cryomodule**
 - “Plug-compatible” development to:
 - Encourage “improvement” and creative work in R&D phase
 - Motivate practical ‘Project Implementation’ with sharing intellectual work in global effort
- **Accelerator System Engineering and Tests**
 - Cavity-string test in one cryomodule (S1, S1-global)
 - Cryomodule-string test with Beam Acceleration (S2)
 - With one RF-unit containing 3 cryomodule

090509 ILC-PAC Review: SCRF 4


ilc Status of 9-Cell Cavity



- Europe (DESY, Saclay)
 - Gradient: > ~ 40 MV/m (max),
 - Industrial (bulk) EP demonstrated
 - Field emission reduced with ethanol rinsing
 - Surface process with baking in Ar-gas
- Americas (Jlab, Cornell, FNAL/ANL)
 - Gradient: > ~ 40 MV/m (max),
 - Field emission reduced by Ultrasonic Degreasing with Detergent
- Asia (KEK, IHEP, RRCAT)
 - Gradient: 36MV/m (LL, KEK-JLab), 32 MV/m (TESLA-like, KEK)

090509 ILC-PAC Review: SCRF 5

ilc DESY: Ethanol Rinse Effect

Cavity gradient may be improved by 'ethanol rinse', and Field emission significantly reduced.

090509 ILC-PAC Review: SCRF 6

ilc Understanding of Sources for Quench


From TTC-09a Summary (by H. Padamsee)

- Sources for quench below 25 MV/m have been identified
- Thermometry first used to locate quench regions followed by optical inspection.
- Quench sites are predominantly bumps and pits on the equator e-beam weld (EBW), or in the heat affected zone.

Picture example reported


A13 Cell #5 FE28, pit inside equator EBW

HAZ 100-200 μm dia.



JLab


Z130 Cell #3 18deg, pit at equator EBW ~500 μm dia.



quench at 18-22MV/m DESY





090509 ILC-PAC Review: SCRF 7


ilc After Better Understanding To Exclude Mechanical Defect




Field gradient improved by 'ethanol rinse', and it may be more evident, if the "lowest sample" (limited due to different reasons) may be eliminated.

090509 ILC-PAC Review: SCRF 8






- Five 9-cell cavities: built by ACCEL, and processed/tested at Jlab.
 - All of them processed with one bulk EP followed by one light EP and by ultrasonic pure-water cleaning with detergent (2%).



- ### ilc Outline
- Introduction
 - R&D Status
 - **Plan for Technical Design Phase**
 - Global Plan and Project Management
 - Summary
- 090509 ILC-PAC Review: SCRF 16



Standard Procedure Established

Standard Fabrication/Process	
Fabrication	Nb-sheet purchasing
	Component Fabrication
	Cavity assembly with EBW
Process	EP-1 (~150um)
	Ultrasonic degreasing with detergent, or ethanol rinse
	High-pressure pure-water rinsing
	Hydrogen degassing at > 600 C
	Field flatness tuning
	EP-2 (~20um)
	Ultrasonic degreasing or ethanol (or EP 5 um with fresh acid)
	High-pressure pure-water rinsing
	Antenna Assembly
	Baking at 120 C
Cold Test (vertical test)	Performance Test with temperature and mode measurement

Key Process

Fabrication

- Material
- EBW
- Shape

Process

- Electro-Polishing
- Ethanol Rinsing or Ultra sonic. + Detergent Rins.
- High Pr. Pure Water cleaning

090509 ILC-PAC Review: SCRF 18

A New High Resolution, Optical Inspection

For visual inspection of cavity inner surface.

~600µm beads on Nb cavity

camera & lens

motor & gear for mirror

sliding mechanism of camera

Camera system (7µm/pix) in 50mm diameter pipe.

perpendicular illumination by LED & half mirror

tilted sheet illumination by Electro-Luminescence

DESY and FNAL starting to use this system in cooperation with KEK

090509 ILC-PAC Review: SCRF 19

Comparison with each treatment

EP-1 (25 + 100 um removed)

After Fabrication

EP-1 (25 um removed)

090509 ILC-PAC Review: SCRF 21

How May We Reach Our Goal?

Yield

Eacc [MV/m]

Push Quench Limit:
• Defects from material
• Defects from fabrication (EBW)
• Renewed studies

Push Quench & field emission Limit
• Classical defect/field emitter
• EP specific...

Prepared by R. Geng (Jlab)

090509 ILC-PAC Review: SCRF 23

ilc Cavity: Plug-compatible Interface

Component interfaces are reduced to the minimum necessary to allow for system assembly

090509 ILC-PAC Review: SCRF 25

ilc Importance of Plug-compatibility in R&D Stage

- Creative/Innovative work for further improvement with keeping “redundancy” and “replaceable >> plug-compatible” condition
- Seek for Cost-effective Fabrication for “mass production”
- Global cooperation and share for intellectual engagement

090509 ILC-PAC Review: SCRF 26

ilc Superconducting RF Technology

Critical R&D

- 35 MV/m Gradient Yield in 9-cell cavities
- 31.5 MV/m average gradient in a cryomodule
- Linac “String Test”

090509 ILC-PAC Review: SCRF 28

ilc S1-Global Collaboration

Complement ary activity to

090509 ILC-PAC Review: SCRF 29

ilc SRF Test Facilities

FNAL
NML facility
Under construction
first beam 2010
ILC RF unit test

DESY
TTF/FLASH
~1 GeV
ILC-like beam
ILC RF unit
(* lower gradient)

KEK, Japan
STF (phase I & II)
Under construction
first beam 2011
ILC RF unit test

090509 ILC-PAC Review: SCRF 30

ilc Beam Acceleration Test Plan

with RF unit at Fermilab and KEK in TDP-2

ILC bunch Laser
capture cavity
ILC RF unit : 3 cryomodules
RF gun cavity
SMW RF power (#1)
SMW RF power (#2)
10MW Multi-beam Klystron (#3)
Bouncer Modulator
Front end electronics
energy analyzer
dump
dump
*detail design is not yet done. (just for imagination)

~36m
~65m

090509 ILC-PAC Review: SCRF 32

ilc KEK STF-2 Pre-accelerator part

Compact light source accelerator:
- Use of STF RF-gun and capture cavities :
- **Granted separately, and to be complete by 2012**

Compact Light Source accelerator in STF Phase 2

STF Laser
Light Source Laser
STF RF-gun
STF Capture Cavities
S11 Cryomodule
STF Phase 2 accelerator

090509 ILC-PAC Review: SCRF 33

ilc Cavity- and Cryomodule-String Test Program (S1G, S2) at KEK

C. Year	2008	2009	2010	2011	2012	2013	2014
Cavity String (S1-Global)	Cavity	>>	Ins Test				
Cryomodule String Test (S2)	*High Pressure Code Regulation/Stamp to be applied						
Quant. Beam* (Compact L.S.)		Cavity	>>	Inst. Test			
Cryomodule 1*		Cavity	>>	>>		Ins & T	
Cryomodule 2,3*			Cavity	>>	>>		Ins Ins & T
	Technical Design Phase					Development to be continued	

090509 ILC-PAC Review: SCRF 34

ilc Cavity- and Cryomodule String Test Program at FNAL

	FY08	FY09	FY10	FY11	FY12	FY13
ILC C+CM		CM1	CM2	CM3 (Type IV)	CM4 (PX)	rf unit sys tst
ILC RF Power			MBK modulator	PFN		
SRF Infrastructure				NML complete		CAF complete (1 CM/month)
Project X		CDR		FE decision Final gradient decision		rf unit sys tst

• Cryomodule-string/RF-unit Test to start in FY12

090509 ILC-PAC Review: SCRF 35

ilc A string test in each region

- Complementary testing:
 - Each region must develop industry and must develop 'ownership' of this critical technology
- No one system will exactly represent the baseline reference design RF unit design (before 2012)
 - FNAL: beam format [under review]
 - KEK: number of cryomodules [1 (of 3) by end 2012]
 - DESY: gradient [~27MV/m average over 3 cryomodules]
- Strategy must account for infrastructure limitations and construction schedules at each of the three main linac test facilities under development.

090509 ILC-PAC Review: SCRF 36


ilc Outline

- Introduction
- R&D Status
- Plan for Technical Design Phase
- Global Plan and Project Management
- Summary

090509 ILC-PAC Review: SCRF 37

ilc GDE Project Structure

090509 ILC-PAC Review: SCRF 38



Project Plan in 2008-2010

- Field gradient (S0)
 - To be re-optimized, based on the R&D progress (2010),
- Plug-compatibility
 - Common interface conditions being fixed ,
 - Overview document published
- System engineering/test plan, (S1, S2)
 - Work sharing in cavity string in global effort (S1-Global)
 - Accelerator system test with beam
 - Necessary detailed study and re-coordination under limited resources, including schedule
- Effort for "Accelerator Design and Integration" optimization,
 - Cluster or Distributed RF power sources and distribution,
- Prepare for AAP Interim Review in April, 2009
- Global Communication and cooperation with Laboratories & Industries
 - Visit Labs: DESY, INFN, CERN, CEA/Saclay, LAL/Orsay, CIEMAT, FNAL, SLAC, Cornell, Jlab, LANL, TRIUMF, KEK, IHEP, PKU, TU, PAL, KNU, IUAC, RRCAT, BARC, TTIF, VECC,
 - Visit Industries: ACCEL, ZANON, AES, Niowave, MHI, PAVAC

ILC-PAC Review: SCRF

Visit to Cavity Manufacturers: 2009

Europe:
RI << ACCEL
ZANON

Amecas:
AES
NIOWAVE
PAVAC

Asia:
MHI

Notes:
AES: Advanced Energy Systems
RI: Research Instruments (previously, ACCEL)
MHI: Mitsubishi Heavy Industries

ILC-PAC Review: SCRF

Objectives of Visiting

- Learn industrial status and possible future at cavity manufacturers, through visiting the factory, presentations and discussions with factory staff,
- Communicate TD-Phase R&D Plan, and inform necessary boundary conditions, "plug-compatibility", in the word-wide R&D stage,
- Request close collaboration with laboratories to further industrial R&D effort, particularly, to improve "field gradient" and "cost effective production" to prepare for the industrialization (mass production),
- Establish close communication and confident relationship between ILC-GDE and manufacturers.

ILC-PAC Review: SCRF

ilc Visit to Cavity Manufacturers: 2009

Company	# employees	Features	Date
AES	~26	Experience with RICH magnet production in the previous company, Dedicated for SC/NC RF technology	Feb. 24
NIOWAVE	~40	A New company dedicated for Niobium and microwave technology	Feb. 25
ACCEL/RI	~100	Most experienced company with SCRF, and adaptable for production scale of European XFEL	Mar. 4
ZANON	~200	Much experienced with plumbing work and SCRF cavities, and with HERA cryostat, Adaptable for scale of European XFEL	Mar. 6
MHI	>>1,000	A leading company in heavy-industries in Japan, and experienced with SC/NC RF cavities and accelerator technologies	Mar. 10
PAVAC	~30	A unique features with EBW machine itself and SCRF cavity manufacturing	May 7

090509 ILC-PAC Review: SCRF 44

ilc Toward Industrialization

- Global status of Industries
 - Research Instruments and Zanon in Europe
 - AES, Niowave, PAVAC in Americas
 - MHI in Asia

Project Scope			
Euro XFEL	~800	2 years	~1 cavity / day
Project X	~400	3 years	~2 cavities/ week
ILC	~15,500	4 years	~20 cavities / day
(÷ 3 regions)			~7 cavities / day)

- Industrial Capacity: status and scope
 - No company currently has required ILC capacity
 - Understand what is needed (and cost) by 2012

090509 ILC-PAC Review: SCRF 45

ilc Industrialization and cost reduction

- Re-visit previous effort, and update the cost-estimate for production
 - Review the RDR cost estimate (based on TESLA)
 - Include recent R&D experience (industry/lab)
- Encourage R&D Facilities for industrialization
 - Develop cost-effective manufacturing, quality control and cost-reduction in cooperation with industry
- Reflect the R&D progress for cost-reduction
 - Baseline ⇒ Forming, EBW, assembly work...

090509 ILC-PAC Review: SCRF 46

ilc A Plan for R&D facilities and Preparation for Industrialization

- Bench-mark R&D facility (pilot plant) to study cost-effective manufacturing,
 - Forming and preparation machining,
 - Pre-surface treatment and preparation,
 - EBW process with efficient automation,
 - In-line Inspection during fabrication process for quick-feedback,
- R&D facilities to be sited at Laboratories
 - Effort to seek for the most cost-efficient manufacturing with keeping information to be open,
 - Development to seek for a bench-mark, manufacturing facilities (design and/or itself can be applicable for the real production.
 - It is important for industries to participate to the program since Day-1. for planning.
- We may discuss a possibility
 - An industrial meeting to be held as a satellite meeting at the 1st IPAC, Kyoto, May, 2010.

090509 ILC-PAC Review: SCRF 48

ilc Global Plan for SCRF R&D
A Summary

Calendar Year	2007	2008	2009	2010	2011	2012
Technical Design Phase	TDP-1			TDP-2		
Cavity Gradient R&D to reach 35 MV/m		Process Yield > 50%		Production Yield >90%		
Cavity-string test: with 1 cryomodule		Global collab. For <31.5 MV/m>				
System Test with beam 1 RF-unit (3-modulce)		FLASH (DESY)		STF2 (KEK) NML (FNAL)		
R&D/prepare for Industrialization						

090509 ILC-PAC Review: SCRF 49

ilc Summary

- **Technical Design Phase in progress:**
 - **Phase-1: Technical reality to be examined,**
 - 35 MV/m with yield 50 % in surface process
 - - 33 MV/m with yield 50 % is being achieved
 - 31.5 MV/m with the cavity-string in a cryomodule
 - **Phase-2: Technical credibility to be demonstrated**
 - 35 MV/m with the yield 90 % for 9-cell in manufacturing
 - Beam acceleration with the field gradient 31.5 MV/m.
- **We aim for**
 - Global R&D efforts toward "High Gradient" keeping "plug-compatibility" concept.
 - Cooperation of world-wide Institutions and Industries crucially important and expected to prepare for industrialization.

090509 ILC-PAC Review: SCRF 50