

### Near Detector Site Review

May 1, 2007



• As part of our normal and ongoing Engineering Design Review and Risk Management Program, we conducted an informal internal review of the excavation options for the NOvA Near Detector on April 27, 2007.

#### · Reviewers:

- Elaine McCluskey
- Chris Laughton
- Steve Dixon
- Tim Trout
- Mike Andrews




## Relevant Questions

- How much does it cost? How much confidence do we have in the cost estimate?
- How long does it take? How does it impact timing and duration of shutdowns?
- Physics impact?
- Does it have to be moved out of the way?
  - How hard is it to move?
  - How long does it take?
  - How much lead time is required?
  - How do we preserve secondary containment during the move?
  - How do we store the scintillator?



# Various Options

Some not shown here






# Minimal Excavation Option

There are a number of features associated with the minimal excavation option that are troublesome.

- Enclosed volume for fire suppression requires walls, doors, etc.
- Detector must be movable to free up access through half of MINOS tunnel.
  - Detector must be drained before moving.
  - Scintillator must be stored
    - Hundreds of 55 gallon drums
    - Under floor storage tanks
- Detector move must not compromise secondary containment when the detector is reassembled
- More electrical and plumbing disconnects in order to move detector.



# Moving the Near Detector





## New Proposal


Proposal for new cavern adjacent to the MINOS tunnel. Requires 735 yd<sup>3</sup> of excavation, compared to ~100 yd<sup>3</sup>.

#### Advantages:

- Detector does not block the tunnel and never has to be moved or disassembled.
- The minimal excavation increases the span of the tunnel. The new cavern does not.
- Secondary containment is simplified.
- Fire suppression enclosure simplified.
- Excavation of side cavern is less of a disturbance to others in the MINOS tunnel.

#### Disadvantages:

• Costs more.





### Cost

- The cost of the excavation is thought to be less than \$1M.
- 3 rationality exercises were presented to support this estimate (NOvA-doc-1127).
- There are additional substantial costs associated with outfitting and infrastructure. Many of these are in common with other options.
- In the process of identifying these costs for the new cavern option, similar to what we have done for the minimal excavation option.

| FERMILAB: | FESS | COST | <b>ESTIMATE</b> |
|-----------|------|------|-----------------|
|           |      |      |                 |

| Project Te   | NOvA Near Detector Tunnel Mods  | 6-7-14   | Status. | Date:<br>9/22/2006 | Revision Date |
|--|---|----------|---------|--------------------|---------------|
| TEM NO   | DESCRIPTION OF WORK:  | QUANTITY | UNITS   | UNIT COST          | AMOUNT        |
| 01   | GENERAL CONDITIONS \$33,200   |          |         |                    |               |
| dumpsters<br>dust walls 2<br>dust wall ma<br>Demobilizati  | Mobilization w/crew for 5 days including training                     | - 5      | day     | \$2,200.00         | \$11,000.0    |
|  | dumpeters   |          | - Is    | \$2,000.00         | \$2,000.0     |
|  | dust walls 2 men 3 days   | . 45     | fes     | \$50.00            | \$2,400.0     |
|  | dust wall materials plywood/herucite                                  | :1180    | af      | \$1.50             | \$1,800.0     |
|  | Demobilization/cleanup-w/crew 5 days                                  | - 5      | day     | \$2,200.00         | \$11,000.0    |
|  | Temp power for Minos Hall   | 1        | ts      | \$6,000.00         | \$5,000.0     |
|  | DEMOLITION \$6,100  |          |         |                    |               |
|  | Cut and pull back existing cables 2 men 1 day                         | 16       | ties    | \$85.00            | \$1,400.0     |
|  | Remove existing conduits & unistrut racks 2 men 2 days                | 32       | ties    | \$85.00            | \$2,700.0     |
|  | Haul out demoed materials.  | - 1      | - Is    | \$2,000.00         | \$2,000.0     |
| Drift 6 bits crew = 1 i 1 i Install roc Install cor Rock Nas Forkittbo Maniet in Disset mat Explosive Gunde m Concrete | EXCAVATE & FINISH TUNNEL ALCOVE \$94,200                              |          |         |                    |               |
|  | Drift & blast alcove 25' l x 6' w x 18" h w/ crew 3 weeks             | 15       | days    | \$2,500.00         | \$37,500.0    |
|  | crew = 1 blast foreman, 1 driller, 1 equip oper, 2 laborers           | - 2      | - 4     | 7-11107            | 227300        |
|  | 1 OH crane operator crawler drift, 1 air compressor, hos-             |          |         |                    |               |
|  | Install rock bolts & gunite w/ crew one week                          | - 5      | days    | \$2,500.00         | \$12,500.0    |
|  | Install concrete slab & trench drain w/ crew 3 days.                  |          | days    | \$2,500.00         | \$7,500.0     |
|  | Rock hauling offsite  | 100      | cy      | \$12.00            | \$1,200.0     |
|  | Forkilf/bobcat in tunnel  | 15       | da      | \$500.00           | \$7,500.0     |
|  | Manift in tunnel for high access                                      | 15       | da      | \$500.00           | \$7,500.0     |
|  | Blast mat rental assume 10 for 2 weeks                                | 100      | day     | \$50.00            | \$5,000.0     |
|  | Explosives  | - 1      | - h     | \$3,000.00         | \$3,000.0     |
|  | Gunite materials  | . 1      | ls.     | \$2,500.00         | \$2,500.0     |
|  | Concrete floor/french drain materials                                 | - 1      | - In-   | \$5,000.00         | \$5,000.0     |
|  | Bolting materials   | 1        | ts      | \$5,000.00         | \$5,000.0     |
|  | WALLS & FINISHES \$22,600   |          |         |                    |               |
|  | 8" glazed cmu walls ea end of detector & parallel                     | 890      | nf      | \$12.00            | \$10,600.0    |
|  | 2 prs-double 4' x 10' doors hollow metal rated                        | - 4      | 60      | \$2,000.00         | \$8,000.0     |
|  | scaffolding   | - 3      | . bi    | \$2,000.00         | \$2,000.0     |
|  | fire caulking around piping/conduit                                   | . 1      | ls      | \$2,000.00         | \$2,000.0     |
| 05   | MECHANICAL/ELECTRICAL 567,000   |          |         |                    |               |
|  | install unistrul utility supports off civiling of alcove 2 men 2 days | 32       | hm      | \$85.00            | \$2,700.0     |
|  | Unistrut materials & equipment  |          | ls.     | \$2,500.00         | \$2,500.0     |
|  | Reinstall 500 MCM ground cable  | 200      | 36      | \$10.00            | \$2,000.0     |
|  | 1.25" conduit 50" long with connections to existing                   | 50       | - 16    | \$15.00            | \$800.0       |
|  | Repull cables in 1.25° conduit  | 200      | H.      | \$12.00            | \$2,400.0     |
|  | 2-3" conducts 50" long with connections to existing                   | 100      | 16      | \$25.00            | \$2,500.0     |
|  | Controls cable & terminations   |          |         |                    |               |
|  | repult 2 fiberoptic trunk tines                                       | 400      | 16      | \$1.00             | \$400.0       |
|  | repull CATV, FIRUS, telephone, other                                  | 800      |         | \$1.00             | \$800.0       |



### Summary

- Sense of Committee was that new cavern is the more attractive option.
- Concern about cost.
- NOvA Collaboration voiced support for excavation to accommodate Near Detector at correct angle to beam up to a cost of ~ half a kton of Far Detector mass ~ \$4M.
- Excavation is entirely conceptual. Requires 100% contingency.
- After successful CD-2 review, when we can spend money on final designs, we will hire an outside firm to do an engineering design of the cavern to determine its real cost.