


---

# Accelerator Operations and Plans

R. Dixon

---




## Major Accomplishments FY05-FY06

---

- Electron Cooling Demonstrated (July 2005)
- Recycler-Only Operations (October 2005)
- Peak Luminosity of  $172 \times 10^{30} \text{cm}^{-2} \text{sec}^{-1}$  (average) (January 2006)
  - CDF Luminosity  $185 \times 10^{30} \text{cm}^{-2} \text{sec}^{-1}$
- Weekly integrated luminosity of  $24.4 \text{pb}^{-1}$  (December 2005 )
  - CDF Luminosity  $26 \text{pb}^{-1}$
- Antiproton Stack of  $436 \times 10^{10}$  in the Recycler (January 2006)
- Amount of antiprotons stacked in 1 hour  $20.1 \times 10^{10}$  (February 2006)




# Peak Luminosity






## Integrated Luminosity per Week






# Integrated Luminosity





# Tevatron Failures

- During the first 1/3 of FY06, Tevatron operations has been plagued by three Tevatron magnet failures
- The FY06 average number of store hours per week is 85 hours and is down by:
  - 21% from the FY06 goal (105 hours)
  - 30% from FY05 average (124 hours)
- This loss of running time accounts for most of the shortfall of the FY06 integrated luminosity






Tevatron Component Failures in Run II		
Date	Description	Sector
29-Apr-01	Cryostat vacuum leak	D13
21-May-01	Helium leak at correction element feed-through	F13
8-Jul-01	Helium leak on spool	F47
18-Aug-01	Helium leak	F44
1-Mar-03	Safety lead ground fault	A13
5-Dec-03	Helium leak at correction element feed-through	C19
20-Dec-03	Cryostat vacuum leak	B14
15-Mar-04	Helium leak	A44
21-Nov-05	Helium leak caused by stuck Kautzky valve	B17
14-Jan-06	Cryostat vacuum leak (air)	A44
22-Feb-06	Helium leak caused by stuck Kautzky valve	F47



# Tevatron Quenches

- All three Tevatron magnet failures were induced by components that failed to operate properly during "mild" quenches
  - Mild quench - 10-15K magnet temperature, < 1 hour recovery
  - Major quench - 100k magnet temperature, multi-hour recovery
- In July 2003, we declared the collider commissioned.
- We developed an operational attitude that emphasized focused and organized studies.
- Since then, the number of Tevatron quenches is down dramatically





## Tevatron Repairs

- Two of the magnet failures were the result of failed “Kautzky” (pressure relief) valves.
  - We view this as a systematic failure
  - We are replacing the failed part in all of the Tevatron Kautzky valves (~1200) during this shutdown
- We have also added a second shift during the shutdown to replace (or repair) all known cold leaks (F4, E2, A3, B4)







## Major Accomplishments - Recycler Electron Cooling





- The maximum antiproton stack size in the Recycler is limited by
  - Stacking Rate in the Debuncher-Accumulator at large stacks
  - Longitudinal cooling in the Recycler
- Longitudinal stochastic cooling of 8 GeV antiprotons in the Recycler is now replaced by Electron Cooling
  - Electron beam: 4.34 MeV - 0.5 Amps DC -99% recirculation efficiency






# Recycler Electron Cooling


- Electron cooling commissioning
  - Electron cooling was demonstrated in July 2005 two months ahead of schedule.
  - By the end of August 2005, electron cooling was being used on every Tevatron shot
- Electron cooling goals
  - Can presently support final design goal of rapid transfers (30eV-Sec/2hrs)
  - Can presently reliably support stacks  $> 400 \times 10^{10}$ 
    - FY06 design goal =  $250 \times 10^{10}$
  - Have achieved 1850 mA of electron beam (500mA final design goal.)






## Recycler-Only Operations


- Recycler had been participating in Collider Operations in the Combined Shot mode because the Recycler Stack size has been limited to  $\sim 120 \times 10^{10}$  pbars
  - Longitudinal Cooling
  - Transverse Stability
- With Electron Cooling operational and the transverse dampers commissioned, the Recycler stack size can now be increased to over  $400 \times 10^{10}$  pbars
- The Collider complex has transitioned from Combined Shot mode to Recycler-Only mode
  - Faster average stacking.
  - Smaller pbar emittances in the TEV
  - In Recycler-Only mode we no longer need
    - The Accumulator shot lattice
    - Pbar-TeV shot setup
    - Dual energy ramps in the Main Injector
    - Complicated RF states
  - In addition, the Neutrino program benefits because the Accumulator will spend most of the time with small stacks, hence fast cycle times.
- Transition was completed by October 1, 2005 - 1 month ahead of schedule







# Recycler-Only Operations






# Recycler Cooling Sequence







## Recycler Shutdown Tasks

- Flying Wire upgrade
  - Reduce the Carbon Fiber wire diameter from 33 to 5 microns
- Damper upgrade (80 MHz Damper system)
  - Shorter kickers installed at higher beta
  - Switch to VME board designed for damper
- Vacuum maintenance
  - Firing of TSP's ring wide
  - Leak Check
- RF upgrade
  - Water cooling for RF amplifiers
- Installation of a ground bypass around the cooling section
  - Connect low reactance cable to the Recycler beam pipe
  - Should reduce induced currents by a factor of ~10 (from ~100 mA to ~10 mA)
- Shielding for cameras in the MI tunnel
  - CCD cameras to be used with Optical Transition Radiation instrumentation
- Upgrade of the SF<sub>6</sub> gas recirculation system






# Tevatron Improvements


- Completed Tevatron BPM system installation and commissioning
  - An order of magnitude improvement in proton position measurements and new for pbars
  - Position resolutions in the range of  $\sim 10\text{-}25\ \mu\text{m}$
- 28 cm  $\beta^*$  + optics correction
  - Lattice measurements exploited new BPM electronics
  - Tested at end of stores; implemented in September
- Pbar tune stabilization during HEP
  - Keep pbar tunes  $> 7/12$  as beam-beam tune shift decreases over a store
  - Helps maintain pbar lifetime
- Orbit stabilization during HEP
  - Compensate for "fast" low-beta quad motion
  - Eliminate halo spikes @ CDF & D0, maintain lifetime





# Tevatron Tune and Orbit Compensation





# Tevatron Work Highlights in 2006

## ▪ Shutdown Tasks

- Fix known cold leaks (F4, E2, A3, B4)
- Replace poppets on He Kautzky valves ( $\approx 1200$ )
- Re-shim remaining 228 dipoles
- Unroll magnets
  - Quads in D1, A3  $> 5$  mrad
  - Various magnets  $> 1$  mrad since 2004 shutdown
- Replace 3 separators @ A49
- Install new separators @ A17, B48 (1 each)
- Install TEL-2
- Pull cables for new sextupole circuits (chromatic compensation)
- Complete IPM installation
- Install new crystal collimator-- **Awaiting parts**
- Infrastructure maintenance (feeders, cryo, etc.)

## ▪ Commissioning Tasks


- Re-commission with beam...lots of changes
  - Adjust coupling following the dipole re-shimming, unrolls
  - Implement new helices for injection and HEP
- Adjust IP positions
  - Already aware of low- $\beta$  quad + detector motion
- Commission TEL-2
- Continue commissioning of IPM and OTR
- Complete chromatic compensation (split sextupole circuits)
  - Finish constructing new power supplies
  - Connect new cables to sextupoles, run with existing settings
  - Machine studies to implement lattice corrections
- **Commission new BLM electronics**
- Conduct machine studies on new working points (1/2, 2/3)



## Antiproton Production

---

- The cornerstone of the Run II upgrades is antiproton production.
- In June 2005, we realized that antiproton production was falling behind expectations.
- We formed a team of twenty people divided into four groups dedicated to increasing the antiproton production rate.
  - Booster Extraction - Goal:  $4.5e12$ /batch with a longitudinal emittance of  $0.12$  eV-sec/bucket and a momentum spread of  $18$  MeV
  - Main Injector Slip Stacking - Goal -  $8e12$  protons on target with a  $1.5$  nS bunch length and an acceleration efficiency of  $95\%$  and single point Rad limit of  $1$  Rad/hr in the MI tunnel.
  - Antiproton Source - Goal -  $8e12$  protons on target every  $2.0$  secs with a production of  $17e-6$
  - Instrumentation
- The team met twice a week at Tuesdays and Thursdays at 9 am in the Huddle to discuss overall progress and integration with collider operations.



# Protons on Target

## Booster



- Longitudinal Dampers
  - Dipole Mode 0, 1, 2, 52
  - Quadrupole Mode 1
- RF Cavity balancing


## Main Injector

- Beam Loading
- Longitudinal Matching
- Bunch length on target during Mixed mode cycles

	Initial	3/1/2006	Final	Status	
Intensity	3.9	4.2	4.5	4.5	$\times 10^{12}$
Emittance	0.2	0.12	0.12	0.08	eV-Sec
Momentum Spread	18	18	18	12	MeV


	Initial	3/1/2006	Final	Status	
Average Intensity	6.2	7.2	8	7.6	$\times 10^{12}$
Bunch Length	2	1.5	1.5	1.8*	nS
Efficiency	75	95	95	90	%






## Antiproton Production and Protons on Target

- Average over  $7.6 \times 10^{12}$  protons on target
- Have achieved  $8.5 \times 10^{12}$  protons on target for sustained periods of time
- Reliability of Booster bunch rotation vs the number of Booster RF stations is the current key issue.






## Studies, Studies, Studies

---

- Originally planned to dedicate 14 days of antiproton studies during low luminosity running
  - First Tevatron Failure (B11 Separator)
    - Tue Nov 22 to Thu Dec 15
    - 23 days of dedicated studies
  - Second Tevatron Failure (A44 vacuum)
    - Sun Jan 15 to Thu Jan 26
    - 12 days of dedicated studies
  - Accumulator Aperture Work
    - Done during low luminosity running
    - Wed Feb 15 to Fri Feb 17
    - 3 days of dedicated studies
-



## December Antiproton Study Period Statistics


---

- Length of Time: Tue Nov 22 to Thu Dec 15
- Number of Elog shift pages: 72
- Number of Recorded Debuncher Orbits: 857
- Number of Recorded AP2 Orbits: 775
- Number of Commissioned items: 12
- Number of Major Accomplishments:  $6 + \frac{1}{2} + \frac{1}{2}$
- Number of Confusions (at the time):  $\infty$
- Number of Other Things Done: 8+1
- ♣ Number of "Next Times" Known Items:  $7\frac{1}{2}$




# December Antiproton Study Period

- Instrumentation Commissioned
  - Debuncher Reverse Proton Turn-By-Turn system
  - Debuncher Reverse Proton partial turn extraction up AP2
  - Debuncher Component Centering
  - Debuncher Orbit-Quad offset
  - AP2 Orbit-Quad offset
  - AP2 Beam Line Correction
  - One-Shot TLG for getting Debuncher beam
  - Admittance measurement from data-logger
  - "Deb Heat Rev p's to AP2" aggregate
  - AP2-Debuncher Injection region setup
  - Auto-tune 120 GeV orbit of P1-P2-AP1
- Scheduled Studies Accomplishments
  - Lattice measurements for Debuncher and AP2
  - Determine Debuncher Orbit/BPM-Quad offsets
  - Corrected Debuncher Vertical Orbit to Quad Centers
  - Centered Debuncher Components about orbit
  - Determine AP2 Orbit/BPM-Quad offsets
  - Set Orbit, Stands and Settings for AP2-Debuncher Injection Region
  - Corrected AP2 Orbit to near Quad Centers
  - Installed AP2 lattice that matches to current Debuncher Lattice



## January Antiproton Study Period

- Quad Steering of the AP1 line
  - Not finished
- Alignment of the Debuncher horizontal orbit and moveable devices.
  - Did not do arcs
  - Need to Energy align the AP2-Debuncher-Accumulator
  - Horizontal Aperture up to  $35\pi$ -mm-mrad!!!
- Installation and commissioning of Debuncher lattice modifications
  - First round done
  - Vertical aperture up to  $34\pi$ -mm-mrad
- Removal of the Debuncher Schottkies
  - Completed
- Obstruction search of the AP2 line.
  - Completed - none found
- Installation of 4 additional AP2 trims
  - Two trims installed
  - Two trims staged
- D/A Beam based alignment
  - Completed to the Q3-Q6 straight section
- Accumulator orbit and aperture optimization
  - Backed out of orbit changes
    - Need to update quad centering software
    - Need to de-bug running wave software
  - Will only complete moveable devices
  - Quadrupole Pickup found to be an aperture restriction




# Beam Based Alignment Orbit Changes


Debuncher Vertical Beam Positions: Recalled Record 1740 Minus 916




AP2 Horizontal Beam Positions Record 995 - Record 228



AP2 Vertical Beam Positions Record 995 - Record 228






## Antiproton Stacking - Stacktail System

---


- The measured Accumulator 2-4 GHz Stacktail system can support a flux of 30mA/hr.
  - The currently used 2-4 GHz core momentum system is the same frequency as the Stacktail system
    - At a flux of 15mA/hr, the core 2-4 GHz system can support a exponential gain slope that is a factor of two larger than the gain slope of the Stacktail.
    - As the number of particles in the core increases, the factor of 2 gain slope is exceeded and the core pushes back on the Stacktail and the flux must be reduced.
  - For large fluxes into the Stacktail, the 2-4 GHz core momentum system cannot support a core.
-



## Antiproton Stacking - Stacktail System and the Core 4-8 GHz System


---

- To support a core at high flux, the 4-8 GHz core momentum system must be used.
- Because the 4-8 GHz core system runs at twice the frequency, the electrodes are  $\frac{1}{2}$  the size so the system has a factor of two smaller momentum reach.
- Moving the core closer to Stacktail to accommodate the smaller reach resulted in system instabilities at moderate stacks.
- We now :
  - Use the 2-4 GHz core momentum system to augment the hand-off between the Stacktail and the 4-8 GHz core momentum system
  - Run the 4-8 GHz core momentum system at MUCH larger gain.
  - Run the Stacktail during deposition debunching to pre-form the distribution to match the Stacktail profile





# Stacking Performance

## D:IC728 vs M:Tor109



## Stack Rate vs Stack Size





# Antiproton Parameters

Phase	Antiproton Parameters						
	1	2	3	4	5	6	
Zero Stack Stacking Rate	13.0	16.0	18.9	30.2	30.2	30.2	x10 <sup>10</sup> /hour
	13.0	16.0	16.6	25.2	25.2	25.2	
	13.0	16.0	16.6	20.2	20.2	20.2	
	13.0	16.0	16.0	16.0	16.0	16.0	
Average Stacking Rate	6.3	7.4	9.6	21.7	21.7	21.7	x10 <sup>10</sup> /hour
	6.3	7.4	8.5	14.8	17.4	17.4	
	6.3	7.4	8.5	11.3	11.3	13.3	
	6.3	7.4	8.3	8.3	8.3	9.7	
Stack Size transferred	158.2	163.8	211.5	476.5	476.5	476.5	x10 <sup>10</sup>
	158.2	163.8	187.9	324.7	382.5	382.5	
	158.2	163.8	187.9	248.6	248.6	293.5	
	158.2	163.8	181.5	181.5	181.5	214.5	
Stack to Low Beta	117.1	124.5	169.2	381.2	381.2	381.2	x10 <sup>10</sup>
	117.1	124.5	144.7	253.3	298.3	298.3	
	117.1	124.5	144.7	191.4	191.4	226.0	
	117.1	124.5	138.0	138.0	138.0	163.0	
Pbar Production	16.0	15.0	16.0	21.0	21.0	21.0	x10 <sup>-6</sup>
	16.0	15.0	15.0	17.5	17.5	17.5	
	16.0	15.0	15.0	16.0	16.0	16.0	
	16.0	15.0	15.0	15.0	15.0	15.0	
<b>Design (30mA/hr)</b> <b>Fallback (25mA/hr)</b> <b>Fallback (20mA/hr)</b>	<b>FY04 Plan</b>	<b>Slip Stacking 8/8/2005</b>	<b>Recycler Ecool 2/27/2006</b>	<b>StackTail 5/14/2007</b>	<b>Helix 6/30/2008</b>	<b>Reliability 8/31/2009</b>	



## Future Pbar Work

---

- Lithium Lens (0 - 15%)
  - Lens Gradient from 760T/m to 1000 T/m
- Slip Stacking (7%)
  - Currently at  $7.5 \times 10^{12}$  on average
  - Design  $8.0 \times 10^{12}$  on average
- AP2 Line (5-30%)
  - Lens Steering
  - AP2 Steer to apertures
  - AP2 Lattice
- Debuncher Aperture (13%)
  - Currently at 30-32um
  - Design to 35um
- DRF1 Voltage (5%)
  - Currently running on old tubes at 4.0 MEV
  - Need to be at 5.3 MeV
- Accumulator & D/A Aperture (20%)
  - Currently at 2.4 sec
  - Design to 2.0 sec
- Stacktail Efficiency
  - Can improve core 4-8 GHz bandwidth by a factor of 2
- Timeline Effects
  - SY120 eats 7% of the timeline



## Antiproton Production Prospects


---

- With the progress of the past studies, it is very likely that we will achieve  $30 \times 10^{10}/\text{hr}$  within the next year (Feb 07).
  - Using the conservative end of the range will give a 60% increase in stacking ( $32 \times 10^{10}/\text{hr}$ ).
  - Using the upper end of the range will give a 125% increase in stacking ( $45 \times 10^{10}/\text{hr}$  - Run 2 Upgrade "stretch" goal)
- Goals
  - Achieve  $25 \times 10^{10}/\text{hr}$  by September 2006
    - AP2 Line (5-30%)
    - Accumulator & D/A Aperture (20%)
  - Decide on the Stacktail Upgrade
    - To take advantage of the Stacktail upgrade,
      - a large antiproton flux is needed ( $>30\text{mA}/\text{hr}$ )
      - rapid transfers to the Recycler to keep the accumulator core small.
    - The Stacktail upgrade will remove our ability to go to even modest stack sizes.



## FY06 Goals


- To meet the FY06 design goal of  $800\text{pb}^{-1}$ , we will have to run at the design curve parameters for 130 store hours per week after the shutdown.
  - FY06 original target was 105 store hours per week
  - FY05 averaged 124 store hours per week






## Machine Study Priority

- The FY06 antiproton production rate goal is  $24 \times 10^{10}$ /hour
- The Run II Upgrade goal is to stack at  $30 \times 10^{10}$ /hour by May 2007
- Our goal is to achieve
  - $25 \times 10^{10}$ /hour by September 2006
  - $30 \times 10^{10}$ /hour by February 2007
- To achieve the antiproton production rate goal and the integrated luminosity goal, we will have to continue to carefully balance machine study time against running time
- Antiproton studies will continue to receive the highest priority
  - Average 2-3 shifts per week of dedicated & parasitic studies (25% pbar tax)
- Tevatron studies will be allocated to follow the natural rhythm of the machine
  - FY05-FY06 average >1 shift per week.






## Summary

---

- Despite the rash of recent Tevatron failures, FY05-FY06 has been a spectacular year for Run II
  - Relativistic electron cooling commissioned
  - Recycler-only operations
  - Peak Luminosity of  $172 \times 10^{30} \text{cm}^{-2} \text{sec}^{-1}$  (average)
  - Weekly integrated luminosity of  $24.4 \text{pb}^{-1}$  (average)
  - Antiproton stack of  $436 \times 10^{10}$  in the Recycler
  - Antiproton production rate of  $20.1 \times 10^{10} / \text{hour}$  (average)
- We are taking well-defined steps to improve Tevatron reliability
  - Repair of all known cold leaks
  - Kautzky valve repair
- The FY06 integrated luminosity goal will be difficult but possible to achieve.
- The focus of accelerator studies for the remainder of FY06 will be antiproton production



## Core 4-8 GHz Momentum Cooling System Bandwidth

- 1 GHz of bandwidth at 7 GHz is ~3x more powerful than 1 GHz of bandwidth at 2.5 GHz
- By replacing the trunk coaxial cable with optical fiber, the 4-8 GHz system will be 5.7x more powerful than the 2-4 GHz system

