


MINER ν A II: Detector, Project and Conclusions



Kevin McFarland
University of Rochester
FNAL PAC
12 December 2003

Goals of MINERvA Require...





- Identification and separation of exclusive final states
 - Quasi-elastic $\nu_{\mu}n \rightarrow \mu^{-}p$, $\nu_{e}n \rightarrow e^{-}p$
 - Single π^0 , π^{\pm} final states
 - Muon and electron energy measurement
- Must observe recoil protons
 - Important for $\nu n \rightarrow \mu^{-}p$, $\nu n \rightarrow \mu^{-}p\pi^0$, etc.
- π^0 , μ^{-} reconstruction. Hadronic energy
 - Adds a lot of mass. B-field for charge
- Nuclear targets (high A, Fe of interest for MINOS)

Detector Overview




- Active target, surrounded by calorimeters
 - upstream calorimeters are Pb, Fe targets
- Magnetized side and downstream tracker/calorimeter

Fully-Active Target: Extruded Scintillator




Basic element: 1.7x3.3cm triangular strips.
1.2mm WLS fiber readout in groove at bottom

Assemble
into planes




X-View



Absorbers
between planes
e.g., E- or H-CAL,
nuclear targets

U/V-View

Or replace strips
with absorber
(outer detector)




Active Target Module



- Planes of strips are hexagonal
 - rotate 60° to get U,V views
 - X+U+X+V make a module

Inner, fully-active
strip detector

Outer Detector
magnetized sampling
calorimeter




- More on construction, calorimeters later

Light Yield



- **Critical question:** does light yield allow for low quantum efficiency photosensor?
- Study: use MINOS light MC, *normalized to MINOS results*, MINERvA strips
- Sufficient light, even for single-ended fiber readout, with MAPMT Quantum Efficiencies...





Electronics

(photosensors, electronics are cost drivers)




- FE Readout Based on existing TRiP ASIC
 - builds on FNAL investment. cost effective.
 - chips from this submission are “free” (no user currently)
 - ADC (dual range) plus few ns resolution timing




readout scheme by P. Rubinov, FNAL

Tracking in Active Target




- Coordinate resolution from triangular geometry is excellent
 - ~2-3 mm in transverse direction from light sharing




- technique pioneered by D0 upgrade pre-shower detector


Proton Reconstruction







- Reminder: proton tracks from quasi-elastic events are typically short. Want sensitivity to $p_p \sim 500$ MeV



Performance: Vertex Reconstruction




- Excellent tracking resolution
(results from full GEANT MC, Kalman filter track fitter)




Two-track vertex resolution

Resolution vs. multiplicity

Performance: Particle Identification






- Particle ID by dE/dx in strips




- Many dE/dx samples for good discrimination




Chi2 differences between right and best wrong hypothesis




Calorimeters




- Three types of calorimeters in MINERvA
 - ECAL: between each sampling plane, 1/16" Pb laminated with 10mil stainless ($X_0/3$)
 - HCAL: between each sampling plane, 1" steel ($\lambda_0/6$)
 - OD: 4" and 2" steel between radial sampling layers
- ECAL and HCAL absorbers are plates, rings





Calorimeters (cont'd)




- OD: 4" and 2" steel between radial sampling layers
 - coil at bottom of the detector provides field in steel





Performance: π^0 Energy and Angle Reconstruction



Coherent,
resonance
events with
 π^0




- π^0 's cleanly identified
- π^0 energy resolution $\frac{RMS(E_\pi)}{E_\pi} = \frac{5.5\%}{\sqrt{E_\pi (GeV)}}$
- π^0 angular resolution better than smearing from physics




Modular Design





- a necessary part of installation in NuMI near hall is that detector should be constructed in thin modules
 - each module consists of *four planes* of active inner detector, absorbers and outer detector
- flexibility in design
 - MINERvA can run stand-alone
 - or can use MINOS as long muon catcher




Location in NuMI Near Hall



- MINERvA preferred initial running is without muon ranger, as close to MINOS as possible
 - if this is not possible, we can run initially stand-alone elsewhere in the hall



Detector Cost Summary



- Costs are primarily scaled from experience of MINERvA collaborators on CMS HCAL, MINOS

- \$2.55M equipment (no F&A)

- \$1.41M labor, EDIA

- \$1.54M contingency (39% avg.)


Sub-Project	Cost (kUSD)			
	M&S (no F&A)	SWF (w/ F&A)	EDIA (w/ F&A)	Contingency (%)
Extruded Scintillator	151	12	30	78 (40%)
Fiber and Glue	262	n/a	n/a	52 (20%)
WLS Fiber Prep.	50	104	16	85 (50%)
Optical Cables	77	162	11	100 (40%)
Absorbers	310	67	32	122 (30%)
Module Assembly	11	473	53	268 (50%)
Photosensors	772	n/a	25	159 (20%)
MAPMT Testing	6	45	n/a	26 (50%)
PMT Box and Optics	278	95	51	212 (50%)
Electronics and DAQ	628	33	206	435 (50%)
Totals	2545	990	423	1537 (39%)

- Schedule: estimate ~23 months from project start
 - module assembly, PMT box most uncertain sub-projects


Construction Model




- Our goal is to fund as much of detector as possible from University program funds and infrastructure programs



MINER_vA Design Status



- Working to improve our understanding of project
 - PMT Box construction schedule and module assembly procedure and schedule are most pressing
- Preliminary EDIA has begun
 - absorbers, fiber routing, FE electronics
- Prototypes of several systems in early spring
 - TRiP FE Readout (PPD, MINOS support for vertical slice test)
 - OD module (Rochester)



12 December 2003


**Ray Teng,
Rochester Nuclear
Physics Group
Mech. Technician
with OD prototype**



Kevin McFarland, MINER_vA


19

Needs from the Laboratory




- EDIA
 - TRiP FE Readout can be most effectively designed here (common design elements with D0 boards)
 - Critical safety systems: detector stand, magnet coil, low voltage distribution to electronics
- Staging area
 - Detector assembly
 - Physicist desks and counting room
- Installation
 - Rigging detector modules down shaft and into place
 - Utilities and outfitting for near hall site

Summary




- The opportunity: NuMI
 - NuMI is at the intensity frontier of neutrino physics for the latter half of the decade and beyond
 - Spacious near detector hall is *terra firma* for parasitic near detector experiments
 - happy to run with beam driven by MINOS
 - Opens a new field: “JLab of neutrinos”
 - *Rich physics program in its own right and support for oscillation program*




FERMILAB #98-1321D

Summary (cont'd)



- The means: the MINER_vA detector
 - low risk, (relatively) low cost design
 - scale is compatible with funding capability of University and other outside programs
 - willing and able collaboration ready to seek the funds and begin construction

410cm



571cm

355cm


Summary (cont'd)



- Our request to the PAC and Laboratory:
 - we seek timely approval of MINER ν A's proposed physics program
- With physics approval, we can begin the business of making this a reality
 - funding
 - complete design
 - begin this partnership between nuclear and particle physics

Backup Slides

Choice of Photosensors



- Photosensors are the first cost driver.
 - we took great care to evaluate options before choosing MAPMTs







Image Intensifiers with CCD readout

- large cost savings relative to MAPMT for sensor
- CCD readout dramatically inexpensive
- but... concerns about dynamic range, mean time to failure, and *no timing*

APDs. High Q.E.!


- low gain. Noisy.
- need to cool
- electronics is a challenge if we want to run soon





VLPCs. High Q.E.! Sexy!

- high performance
- but cryogenic, \$\$\$
- we conclude this isn't a worth the trouble and cost

Electronics (cont'd)





- TRiP ASIC provides sample and hold functionality in time slices
 - initial operation, planning to integrate ADC over spill





- could divide into sub-spills later if rates are higher
- each time over threshold also recorded in spill

Performance: DIS Kinematics Reconstruction



- inclusive reconstruction shown
- W resolution to separate resonance from DIS independent of exclusive reconstruction
- Q^2 resolution for form factor measurements
- x resolution for valence/sea
- y resolution for quark/antiquark




Costing Methodology



- most of our costs could be scaled from similar construction products in MINOS or CMS HCAL where *MINERvA collaborators have hands-on experience*
 - FE electronics boards. TRiP bottoms-up costs were significantly lower than analogous MINOS board costs. Used MINOS
 - PMT box costs scaled from MINOS for MUX boxes
 - MINOS costs for most electronics infrastructure, LV, slow
 - Optical cable, connectors, fiber mirroring from CMS HCAL
 - Gluing, extrusion costs from MINOS
 - Absorber costs based on preliminary sketches from Rutgers machine shop
 - Fiber, MAPMTs quoted from vendors (Kurary, Hamamatsu)
- Contingency: 40-50%
 - except Rutgers shop (30%) and vendor quotes (20%)

Schedule



- Schedule estimates are tentative
 - assembly schedule is more difficult to scale from past projects than M&S costs
- Module assembly
 - estimate ~6 months of prototyping and one year of assembly
 - need to improve model for assembly procedure
 - this is focus of EDIA work at Rochester
- PMT boxes
 - a labor intensive “craft” component. Scaled from MINOS. Accurate?
- FE electronics
 - scaling from D0 TRiP project is probably accurate. Need EDIA and prototyping now (underway, FNAL PPD/Rochester)
- Only obvious resource limit in critical path is ability to expend money at the start of the project for fixed costs and absorber M&S

Schedule (cont'd)



- Current model for module construction
 - needs fast start from Rutgers on initial absorbers.
 - then dominated by assembly (Rochester at FNAL)

