


Project X

Accelerator R&D Plan

Steve Holmes


P5 Meeting
January 31, 2008

Outline




-
- Project X Facility Overview
 - R&D Goals
 - R&D Strategy
 - Project X R&D Plan

Project X Facility Overview




Project X is a high intensity proton facility aimed at supporting a world leading program in neutrinos and rare decays.

NO_vA initially,
DUSEL later?



Project X Facility Overview


Scope



- The R&D program supports a facility scope that includes:
 - A new 8 GeV, superconducting, H^- linac;
 - A new beamline for transport of 8 GeV H^- from the linac to the Recycler Ring;
 - Modifications to the Recycler required for 8 GeV H^- injection, accumulation, and delivery of protons to the Main Injector;
 - Modifications to existing beamlines to support transfer of 8 GeV protons from the Recycler to the Main Injector;
 - Modifications to the Main Injector to support acceleration and extraction of high intensity proton beams over the range 60-120 GeV;
 - Modifications to the NuMI facility to support operations at 2 MW beam power;
 - Modifications to the Recycler to support a new extraction system that will allow delivery of 8 GeV protons in support of a dedicated flavor program.

Project X Overview

High Level Performance Goals



Linac

Particle Type	H ⁻	
Beam Kinetic Energy	8.0	GeV
Particles per pulse	5.6×10^{13}	
Pulse rate	5	Hz
Beam Power	360	kW

Recycler


Particle Type	protons	
Beam Kinetic Energy	8.0	GeV
Cycle time	1.4	sec
Particles per cycle to MI	1.7×10^{14}	
Particles per cycle to 8 GeV program	2.2×10^{14}	
Beam Power to 8 GeV program	206	kW

Main Injector

Beam Kinetic Energy (maximum)	120	GeV
Cycle time	1.4	sec
Particles per cycle	1.7×10^{14}	
Beam Power at 120 GeV	2300	kW


Project X Overview

Provisional Siting



DATE: 04 MAR 2005

REV	DATE	DESCRIPTION	BY	CHKD



FERMILAB NATIONAL ACCELERATOR LABORATORY

LINAC PROTON DRIVER


SITE PLAN

DATE: 04 MAR 2005

DRAWING: **4-2-1** CD-0 1 REV.

Project X R&D Goals


Program Goals



- The goal of the Project X R&D program is to provide support for a Critical Decision 1 (CD-1) in 2010, leading to a CD-2/3a in 2011.
 - Design and technical component development;
 - Fully developed baseline scope, cost estimate, and schedule for CD-2
 - Formation of a multi-institutional collaboration capable of executing both the R&D plan and the follow-on construction project.
- The primary technical goal is a complete facility design that meets the needs of the US research program, as established via CD-0.
 - 2 MW of beam power over the range 60 – 120 GeV,
 - simultaneous with at least 100 kW of beam power at 8 GeV.

Project X R&D Goals


Technical Goals



- Complete preliminary design and cost estimate for Project X:
 - technical and conventional construction elements,
 - systems integration, and
 - installation and commissioning plan.
 - A supporting technology development program targeting key accelerator physics and engineering challenges
 - Alignment with the ILC and SRF programs:
 - Development of shared technologies to the benefit of both efforts
 - Cavity/cryomodule design, rf sources, e-cloud, civil infrastructure
 - Project X linac designed to accommodate accelerating gradients in the range 23.6 – 31.5 MV/m (XFEL – ILC)
 - Final design gradient determined prior to CD-2.
 - Preliminary identification of performance upgrade paths
-

Project X R&D Goals


Management/Organization Goals



- Formation of a multi-institutional collaboration to carry out the Project X R&D program and to prepare a plan for construction.
- Development all project documentation and organizational structures required by DOE 413.3.
- Timeline:
 - 2008: CD-0
 - Form Project X R&D Collaboration
 - 2009:
 - Start project documentation (including CDR), and accompanying R&D program
 - 2010: CD-1
 - Finish CDR, form collaboration to undertake construction project
 - 2011: CD-2/3a
 - Establish project baseline (scope, cost, schedule)

Project X R&D Strategy

Preliminaries




- Proton Driver Design Studies over 2002-2004
 - Director’s Review in March 2005
 - Project X Preliminary Report - August 1, 2007
 - Delivered to Fermilab Directorate Long Range Steering committee
 - Reviewed by Fermilab Accelerator Advisory Committee
 - “We congratulate the Project X team on an innovative design...Project-X is especially suitable for Fermilab in the current scenario of a not well-defined schedule of ILC construction, because of synergies with ILC...The committee therefore very strongly supports the work that is planned for Project-X.”
<http://projectx.fnal.gov/AACReview/ProjectXAacReport.pdf>
 - Project X Accelerator Physics and Technology Workshop - Nov. 12-13, 2007
 - 175 attendees from 28 different institutions.
<http://projectx.fnal.gov/Workshop/ProjectXWorkshopReport.pdf>
-

Project X
360 kW 8GeV Linac
 20 Klystrons (2 types)
 436 SC Cavities
 56 Cryomodules

Front End Linac


325 MHz 0-10 MeV
 1 Klystron (JPARC 2.5 MW)
 16 RT Cavities

325 MHz 10-120 MeV
 1 Klystron (JPARC 2.5 MW)
 51 Single Spoke Resonators
 5 Cryomodules



325 MHz 0.12-0.42 GeV

3 Klystrons (JPARC 2.5 MW)
 42 Triple Spoke Resonators
 7 Cryomodules




1300 MHz 0.42-1.2 GeV

2 Klystrons (ILC 10 MW MBK)
 56 Squeezed Cavities ($\beta=0.81$)
 7 Cryomodules (8 cav., 4 quads)

1300 MHz 1.2-8.0 GeV


13 Klystrons (ILC 10 MW MBK)
 287 ILC-identical Cavities
 37 ILC-like Cryomodules

ILC LINAC



Project X R&D Strategy

Technical Elements Outline




- **Requirements** - develop major system requirements
 - Eight major systems
 - 17 base requirements
 - 68 derived requirements
- **Issues** - discuss issues arising from the requirements
- **Elements** - define the elements of an R&D plan that
 - Addresses the issues arising from the requirements
 - Are directed towards a completion of Conceptual Design Report
- **Resources and Schedule** - estimate:
 - The resources required to complete the R&D plan
 - The schedule required to complete the R&D plan

Note: The Project X R&D strategy assumes the existence of ILC, SRF, and HINS programs.

Project X R&D Strategy


Major Project X Components



- A front end linac operating at 325 MHz.
- An ILC-like linac operating at 1300MHz.
- An 8 GeV transfer line and H- Injection system.
- The Recycler operating as a stripping ring and a proton accumulator.
- The Main Injector acting as a rapid cycling accelerator.
- A slow extraction system from the Recycler.
- 120 GeV Neutrino beamline.
- Civil Construction and Utilities
- Controls

Project X R&D Strategy

Major System Requirements




Req. No.	Description	Req.	Unit	Reference Requirements
1.0	General			
1.1	120 GeV Beam Power	2.3	MW	
1.2	8 GeV Beam Power	360	kW	
1.3	8 GeV Slow Spill Beam Power	200	kW	
1.4	8 GeV Slow Spill Duty Factor	55	%	
1.5	120 GeV Availability	75	%	
1.6	8 GeV Availability	80	%	

Req. No.	Description	Req.	Unit	Reference Requirements
2.0	325 MHz Linac			
2.1	Average Beam Current	9	mA	1.2
2.2	Pulse Length	1	mS	1.2
2.3	Repetition rate	5	Hz	1.2
2.4	325 MHz Availability	98	%	1.6
2.5	Peak RF Current	14.4	mA	2.1 2.11 2.13 2.14
2.6	Final Energy	420	MeV	3.6
2.7	Energy Variation (rms)	1	%	3.10
2.8	Bunch Phase jitter (rms)	1	degree	3.11
2.9	Linac Species	H-		4.1
2.10	Transverse Emittance (95% normalized)	2.5	π -mm-mrad	5.7 5.8
2.11	Macro Bunch Duty Factor	67	%	5.10 5.12
2.12	Macro Bunch Frequency	53	MHz	5.12
2.13	Micro Pulse Length	10.4	μ S	5.13
2.14	Micro Pulse Period	11.1	μ S	5.13

Project X R&D Strategy


Major System Requirements



Req. No.	Description	Req.	Unit	Reference Requirements			
3.0	1300 MHz Linac						
3.1	Average Gradient (ILCportion)	26	MV/meter				
3.2	Average Gradient (S-ILCportion)	23	MV/meter				
3.3	Average Beam Current	9	mA	1.2			
3.4	Pulse Length	1	mS	1.2			
3.5	Repetition rate	5	Hz	1.2			
3.6	1300 MHz Availability	88	%	1.6			
3.7	Initial Energy	420	MeV	2.6			
3.8	Length (approx.)	700	meters	3.1	3.13		
3.9	Peak RF Current	14.4	mA	3.3	3.15	3.17	3.18
3.10	Linac Species	H ⁻		4.1			
3.11	Energy Variation (rms)	1	%	4.9			
3.12	Bunch Phase jitter (rms)	1	degree	4.9			
3.13	Final Energy	8	GeV	4.10			
3.14	Transverse Emittance (95% normalized)	2.5	π -mm-mrad	5.7	5.8		
3.15	Macro Bunch Duty Factor	67	%	5.10	5.12		
3.16	Macro Bunch Frequency	53	MHz	5.12			
3.17	Micro Pulse Length	10.4	μ S	5.13			
3.18	Micro Pulse Period	11.1	μ S	5.13			

Project X R&D Strategy

Major System Requirements




Req. No.	Description	Req.	Unit	Reference Requirements			
4.0	8 GeV Transfer Line						
4.1	Injection Stripping efficiency	98	%				
4.2	Length (approx.)	1000	meters				
4.3	Maximum average activation level	20	mrem/hr				
4.4	Availability	98	%	1.6			
4.5	Momentum Aperture	+/- 0.8	%	3.10			
4.6	Minimum Transverse Aperture	25	π -mm-mrad	3.13	4.3		
4.7	Maximum Dipole Field	0.05	T	4.1	4.3		
4.8	Transfer Efficiency	99.99	%	4.3			
4.9	Final Energy Variation	+/- 0.11	%	5.10			
4.10	Energy	8	GeV	5.1			

Req. No.	Description	Req.	Unit	Reference Requirements			
5.0	Recycler						
5.1	Energy	8	GeV				
5.2	Storage Efficiency	99.5	%				
5.3	Average Recycler Beam Current	0.6	A	1.2			
5.4	Availability	95	%	1.6			
5.5	Injection Rate	5	Hz	2.3			
5.6	Maximum Space Charge Tune Shift	0.05		5.2			
5.7	95% normalized transverse emittance	25	π -mm-mrad	5.6			
5.8	r.m.s. normalized transverse emittance	13	π -mm-mrad	5.6			
5.9	Bunching factor	2		5.6			
5.10	Longitudinal emittance per Bunch	0.5	eV-Sec	5.6	5.12		
5.11	Cycle Time	1.4	S	6.1			
5.12	RF Frequency	53	MHz	6.2			
5.13	Abort Gap Length	700	nS	6.3			
5.14	Peak Recycler Beam Current	2.4	A	6.5			

Project X R&D Strategy


Major System Requirements



Req. No.	Description	Req.	Unit	Reference Requirements
6.0	Main Injector			
6.1	120 GeV cycle Time	1.4	S	
6.2	RF Frequency	53	MHz	
6.3	Abort Gap Length	700	nS	
6.4	Acceleration Efficiency	99	%	
6.5	Main Injector Beam Current	2.4	A	1.1
6.6	Final Energy	120	GeV	1.1
6.7	120 GeV Beam Power	2.3	MW	1.1
6.8	Availability	87	%	1.5
6.9	Injection Energy	8	GeV	5.1
6.10	Longitudinal emittance per Bunch	0.5	eV-Sec	6.2 6.11
6.11	Space Charge Tune Shift	0.05		6.4
6.12	95% normalized transverse emittance	25	π -mm-mrad	6.11
6.13	r.m.s. normalized transverse emittance	13	π -mm-mrad	6.11
6.14	Bunching factor	2		6.11
7.0	8 GeV Slow Spill			
7.1	8 GeV Slow Spill Beam Power	200	kW	1.3
7.2	Peak Spill Rate	280	$\times 10^{12}$ pps	1.3 1.4 7.5
7.3	8 GeV Slow Spill Duty Factor	55	%	1.4
7.4	8 GeV Availability	80	%	1.6
7.5	Cycle Time	1.4	S	6.1
7.6	Peak Recycler Beam Current for slow spill	0.8	A	7.2
8.0	120 GeV Targeting			
8.1	120 GeV Beam Power	2.3	MW	1.1
8.2	120 GeV Availability	95	%	1.5
8.3	Cycle Time	1.4	S	6.1

Project X R&D Strategy


325 MHz Linac Issues



- No special accelerator physics issues are posed by a 420 MeV linac with this beam intensity.
- Development via the High Intensity Neutrino Source (HINS) program
 - 60 MeV front end demonstration based on scrf
- Technology choices
 - room temperature vs. superconducting
 - Upgrade path
- Beam duty cycle and machine availability requirements push the envelope of any existing H- ion source
- Superconducting triple-spoke accelerating cavity is outside the scope of the HINS program
 - RF power distribution and control
 - Cryomodules
 - Beam diagnostics

Project X R&D Strategy


325 MHz Linac Technical Elements



- FY08
 - Basic accelerator physics design
 - HINS vs. alternative technology study
- FY09
 - Basic machine design and technology decisions completed
 - Begin
 - Ion source development,
 - Triple-spoke cavity electromagnetic and mechanical design,
 - Material procurement,
 - Low level RF development
- FY10
 - Ion source prototyping and testing
 - Triple-spoke prototype fabrication,
 - vector modulator and RF distribution system development
- FY11
 - Fabrication triple-spoke cavities
 - Ion source development,
 - RF power distribution system design development
 - Beam instrumentation
 - Complete design
 - Complete cost estimates.

Project X R&D Strategy


1300 MHz Linac Issues



- Project X 1.3 GHz linac is based on the ILC cryomodule design.
 - ~40 CMs required for Project X
 - Accommodate cavity gradients in the range 23.6 – 31.5 MeV
 - GDE is developing a standardized CM design as a high priority near-term item, with goal of testing a complete 31.5 MeV/m CM by 2012.
 - ART plan calls for the assembly and testing of several CMs by 2012
 - Fermilab is playing a leading role in CM design, fabrication, and testing
- Project X has same average current as ILC (9 mA×1 msec×5 Hz)
 - Bunch structure is different
 - Beam test addresses significant, but not all, ILC issues.
- Project X construction will require a production rate of ~one cryomodule/month, with a procurement leadtime of <1 year.
 - Supported by SRF infrastructure program
 - Engage industry in a manner that leads to a cost effective design

Project X R&D Strategy

1300 MHz Linac Technical Elements




- FY08
 - initiate conceptual linac design :
 - lattice
 - RF systems
 - begin design of the S-ILC cavities
- FY09
 - Continue with conceptual linac design
 - Begin to prototype S-ILC tuners, couplers, and cavities
 - Initiate RF system test with first ILC-like cryomodule in concert with the ILC
- FY10
 - Finish conceptual design of the linac
 - Test dressed prototype S-ILC cavities
 - Continue with RF system tests
 - Begin design of the machine protection system
- FY11
 - Finish all prototype tests
 - Complete RF system and machine protection system design
 - Complete cost estimates

Aimed at test of complete rf unit in 2012

Project X R&D Strategy


8 GeV Transfer Line Issues



- Control and mitigation of beam loss due to single particle loss mechanisms in the transport line.
- Uncontrolled losses in the injection region due to the injected and circulating beam interaction with the stripping foil.
- The stripping efficiency and lifetime of the injection foil, or
- The stripping efficiency of a laser stripping injection system.
- The collection of the stripped electrons and neutrals from the injection process.

Project X R&D Strategy


8 GeV Transfer Line Technical Elements



- FY08
 - Begin physics design
 - Begin component specification for the Transfer line and the Injection system
- FY09
 - Finish physics design and component specification.
 - Begin component design of the chicane magnets, painting magnets, foil support and changer, electron catcher, power supply design, vacuum system design
- FY10
 - Finish component design
 - Initiate controls and instrumentation design
 - Begin prototyping of the painting magnets, foil support and changer, electron catcher, and cryogenic beam pipe
- FY11
 - Finish prototyping
 - Begin and finish cost estimates.

Project X R&D Strategy

Ring Issues




- **Recycler Ring**
 - Space Charge tune shift
 - Electron cloud instabilities
 - Storage efficiency

- **Main Injector**
 - Space Charge tune-shift
 - Electron cloud instabilities
 - RF Power
 - Beam loading
 - Transition crossing

Project X R&D Strategy


Ring Technical Elements



- **FY08**
 - Begin design of a two harmonic RF system
 - Run simulations for e-cloud (EC)
 - Continue EC measurements in MI; begin in other rings (e.g. CESR, RHIC, CERN)
 - Investigate the possibility of coating the beam pipe
- **FY09**
 - Select RF Frequency and finalize RF design
 - Begin RF system prototype
 - Continue with EC simulations and measurements
 - Begin beam coating prototype
- **FY10**
 - Finish RF system prototype and begin testing
 - Continue with EC simulations and measurements
 - Coat two MI and Recycler dipoles in a service building and evaluate the results
- **FY11**
 - Finish high power RF system prototype and install in MI tunnel for beam tests
 - Finalize EC mitigation plan
 - Begin and finish cost estimates.

Project X R&D Strategy


8 GeV Slow Spill Issues



- Extraction system configuration: chromatic effects on the transverse phase space at the extraction Lambertson
- Lattice requirements
 - existing gradient magnet harmonics,
 - new powered harmonic elements,
 - modifications to the Recycler lattice.
- RF beam structure requirements
- Duty factor
- Speed of the extraction process
- Extraction point location
- Loss mitigation and shielding requirements

Project X R&D Strategy


8 GeV Slow Spill Technical Elements



- FY08
 - Begin 1/3 and 1/2 integer extraction studies
 - Develop bunch structure specifications
- FY09
 - Finish 1/3 and 1/2 integer extraction studies
 - Decide on extraction strategy
 - Begin design of extraction devices
 - Lambertson,
 - Septum
 - Harmonic Elements
 - Recycler Lattice modifications
- FY09
 - Continue design of extraction devices
 - Begin necessary prototype construction (septum)
- FY10
 - Finalize physics design
 - Finish design of extraction devices
 - Test Prototypes (septum)
 - Begin and finish cost estimates

Project X R&D Strategy


Neutrino Beamline Issues



- Development of a proton target and magnetic horn system capable of handling 2.3 MW of beam power at 120 GeV
 - Project X will increase beam power by a factor of 5-6 beyond the original NuMI design.
 - Initial investigation suggest that the NuMI target hall could be upgraded to handle about 1-2 MW of beam power
 - NuMI beamline was conservatively designed,
 - Redundancy in the initial design.
- Reliability, maintainability, and uptime of the NuMI facility.
 - Limits on the decay pipe window
 - Residual radiation, airborne emissions, and ground water protection
 - Handling of radioactive components

Project X R&D Strategy


Neutrino Beamline Technical Elements



- **FY08**
 - Target design begins.
 - Study of decay pipe window begins.
- **FY09**
 - Target design continues.
 - Magnetic horn design begins.
 - Module upgrades design begins.
 - Study of decay pipe window continues.
 - Study of decay pipe system.
 - Remote handling study begins.
- **FY10**
 - Target design concludes.
 - Magnetic horn design continues
 - Module upgrades designs conclude.
- **FY10 (cont.)**
 - Target chase cooling design begins.
 - Study of decay pipe window continues.
 - Hadron absorber design begins.
 - Remote handling study continues.
 - Radiological study begins.
 - Infrastructure design.
- **FY11**
 - Magnetic horn design concludes.
 - Target chase cooling design concludes.
 - Study of decay pipe window concludes.
 - Hadron absorber design concludes.
 - Remote handling study concludes.
 - Radiological study concludes.

Project X R&D Strategy


Civil Construction Issues



- Existing design concept for Proton Driver facilities meets many Project X requirements
 - Wetland mitigation options
 - Re-use of existing utility capabilities?
 - Re-use of existing cryo facilities?
 - Large injection abort
 - Significant civil construction required
 - Project X has significant utility infrastructure in common with ILC (power distribution, HVAC, cooling, cryogenics, etc.)
 - Involved Fermilab resident expertise can be shared between the ILC and Project X efforts.
 - ⇒ Opportunity for shared development of cost effective designs in these areas.
-

Project X R&D Strategy


Civil Construction Technical Elements



- FY08
 - Update existing Proton Driver design
 - Revise cost estimate to match revised scope
 - Determine best approach for hiring of architect/engineer consultant
 - FY09
 - Begin NEPA process
 - Apply for ACOE 404 wetlands permit
 - Perform architect/engineer selection to help with drafting and graphics for CDR work in this phase
 - FY10
 - Work through iterations of EA
 - Finalize conceptual design and drawings
 - Contract with A/E for T1 work
 - Perform Construction Manager selection
 - FY11
 - Perform preliminary design
 - Perform soil borings for facilities
 - Provide cost estimate and schedule information
 - Develop site preparation package
 - Begin advanced conceptual design for other construction packages
-

Project X R&D Strategy


Controls Issues



- Scale
 - One million controllable properties
 - Up to 200 system users
- Availability
 - 2500-hr MTBF (mean time between failures)
 - 5-hr MTTR (meant time to repair)
 - 15 hours downtime per year
- Machine Protection and Safety
- Legacy Constraints


Project X R&D Strategy

Controls Technical Elements



- **FY08**
 - Do the requirements and design to modernize the controls software infrastructure. This includes front-end software, central services, the applications framework, and the software build environment.
- **FY09**
 - Machine Protection System R&D starts in parallel
 - Work on the controls software infrastructure begins implementation.
- **FY10**
 - Controls software infrastructure design and development is finished
 - Begin system testing
 - Development of the Machine Protection System and beam feedback system begins.
- **FY11**
 - Complete the infrastructure upgrade
 - New features are being designed and developed.
 - The Machine Protection and Beam Feedback systems finished and tested


Project X R&D Plan Master Schedule



- Based on resource loaded schedule (RLS – see report for readable version)
- Covers FY2008-2011
- Incremental to ILC, SRF, HINS



Major Milestones

CD-0 Approved	8/1/08
Start CD-1 Documentation	9/1/08
Complete CD-1 Document.	4/1/10
Start CD-2 Documentation	5/3/10
CD-1 DOE Review	6/1/10
CD-1 Approved	8/2/10
Complete CD-2 Document.	4/1/11
Start CD-3 Documentation	5/2/11
CD-2 DOE Review	6/1/11
CD-2/3a Approved	9/1/11



Project X R&D Plan



Resource Requirements and Profile



Funding requirements by major sub-system (incremental to ILC, SRF, HINS programs)

Project X R&D Plan


Resource Requirements and Profile



Personnel profile by skills types

Note: This includes total resources, not just Fermilab.
Incremental to ILC, SRF, and HINS programs

Project X R&D Plan Budget Profile




Project X R&D Plan Budget Profile							
(Dollar amounts in millions, fully burdened)							
	FY08	FY09	FY10	FY11	FY12	TOTAL	
SWF	\$6.7	\$10.5	\$19.1	\$26.3			\$62.6
M&S	\$1.5	\$4.9	\$6.2	\$13.7			\$26.3
TOTAL	\$8.1	\$15.5	\$25.4	\$40.0			\$88.9
				PED			
	CD-0		CD-1		CD-2/3a		

Project X R&D budget profile

- Scientists not included
- Can produce this table with any combination of scientists in or out, FY08 or AY\$, burdened or unburdened
- Incremental to ILC, SRF, and HINS programs


Project X R&D Plan

An Integrated Plan



	FY08	FY09	FY10	FY11	FY12	FY13
ILC C+CM	CM1	CM2	CM3 (Type IV)		CM4 rf unit syst.tst	
ILC RF Power		MBK	PFN modulator			
SRF Infra.				NML complete		CAF complete (1 CM/month)
HINS				60 MeV beam tests		
Project X		CDR	FE decision Gradient decision baseline docs		rf unit syst.tst	
	CD-0		CD-1	CD-2/3a		


Project X R&D Plan Collaboration Plan



Disclaimer: This is not formally agreed to, although institutions have been invited to comment as this has been developed.

- Intention is to organize and execute the R&D Program via a multi-institutional collaboration.
 - Goal is to give collaborators complete and contained sub-projects, meaning they hold responsibility for design, engineering, estimating, and potentially construction if/when Project X proceeds.
 - Project X R&D Collaboration to be established via a Collaboration Memorandum of Understanding (MOU) outlining basic goals of the collaboration, and the means of organizing and executing the work.
 - It is anticipated that the Project X R&D Program will be undertaken as a “national project with international participation”. Expectation is that the same structure of MOUs described above would establish the participation of international laboratories.


Project X R&D Plan Management Plan



- Fermilab responsible for management of the Project X R&D program.
 - Program managed by a Project X R&D Program Leader, assisted by a Program Team. Deliverables:
 - reviewable/defensible accelerator physics and engineering design, cost estimate, and schedule to achieve CD-2/3a;
 - including identification of possible upgrade paths;
 - organization of a supporting R&D program.
 - Collaboration Council established for the primary purpose of advising/assisting the Project Leader in inter-laboratory coordination.
 - Project X Technical Advisory Committee.
 - Fermilab 1.3 GHz program managed and coordinated jointly via the Assoc. Director for Accelerators and the ILC Program Director.
-


Project X R&D Plan

Institutional Expressions of Interest



- Goal of the November 2007 Project X Accelerator Workshop was to discuss accelerator physics and technology issues of Project X, and to explore possible areas of overlap and interest between potentially interested institutions.
 - Participation in the workshop included 175 individuals from 28 institutions in the U.S., Europe, and Asia.
- The Workshop report contains a record of discussions and a complete compilation of “expressions of interest” from the participating institutions.
 - Purpose of these EOIs is to provide an initial step in understanding how capabilities at interested institutions could be brought to bear in the R&D phase of Project X.

Summary



- Design concept exists for a facility capable of delivering in excess of 2 MW beam power over the energy range 60 – 120 GeV, simultaneous with 8 GeV beam power in the range 100 – 200 kW.
 - Major sub-system performance goals established
 - Potential upgrade paths to multi-MW at 8 GeV exist
 - Design aligned with needs of ILC development
- R&D plan developed covering the period through CD2/3a (2011)
 - Integrates effort on Project X, ILC, and HINS
 - Resource plan exists
- Working towards organizing as a national project with international participation.