



NOvA

Accelerator and NuMI Upgrades

Shutdown 2009


Paul Derwent

October 26, 2009



Accelerator and NuMI Upgrades for NOvA


- Current Operation: 2.2 sec MI cycle
 - Slip stacking in the Main Injector
 - 2 booster batches to pbar ($\sim 7e12$)
 - 9 booster batches to NuMI ($\sim 28e12$)
 - 11/15 (0.733) sec to accumulate protons
 - 1.47 sec Ramp (204 GeV/s)
 - $1e13/2.2$ sec at 120 GeV corresponds to 87 kW
 - 9 to NuMI: 240 kW
 - 11 to NuMI: 300 kW





NOvA/ANU

- Operation for NOvA: 1.33 second MI cycle
 - Slip Stacking in the Recycler
 - 12 booster batches for NOvA
 - Single turn fill in MI (11 μ sec)
 - 1.33 sec ramp (240 GeV/s)
 - $1e13/1.33$ sec at 120 GeV corresponds to 144 kW
 - $4.9e13 \rightarrow 700$ kW
- ALARA: minimize losses





Context of ANU

- Changes to the FNAL Accelerator complex to
 - Turn Recycler from pbar to proton ring
 - Injection and extraction lines
 - Associated kickers and instrumentation
 - 53 MHz RF
 - Shorten MI cycle to 1.33 seconds
 - RF upgrades
 - Power Supply upgrades
 - NuMI target station to 700 kW
 - Target
 - Horns
- On project and off project work that supports NOvA




Shutdown 2009

- Beamline Planning
 - Layout/inspection/interferences/stand design
- Civil construction work: MiNU (GPP, not in NOvA project)
 - 2 new service buildings: Need space
 - MI 14: Injection line into Recycler
 - MI 39: Beam abort kickers
 - New Anode Power supply room: more RF power
 - Faster ramp: 20 MI cavities vs 18, new Recycler 53 MHz RF
 - Floodplain Mitigation: new buildings
- Installation of Gap Clearing Kickers in MI (AIP, not in NOvA project)
 - 7 kicker magnets in MI-40 beam abort area
 - Clear injection gap of beam before next injection




Work in Progress – RR Injection Line Modeling





Work in Progress – RR Injection Line Modeling



8 GeV LINE AT 850



Off project work – MINU

- Main Injector Neutrino Upgrades GPP
 - New MI-14 & MI-39 Service Buildings
 - MI-60 Anode Supply Room addition
- For power supplies, controls, etc for new kicker systems and beamlines
- Construction during 2009 shutdown
 - Penetration conduits to MI tunnel
 - Building foundations
 - All utilities that impact the MI berm
- Buildings on surface to be complete December 2009



MINU Project Locations




MI-14 Service Building
(2250sf; also floodplain mitigation)

MI-60 4th Anode
Supply Room
(250sf)

MI-39 Service Building
(1500sf)



Penetrations in Tunnel



**CONDUITS NESTLED
BETWEEN CABLE TRAY
& RECYCLER**

**PENETRATIONS CURVE
INTO TUNNEL CEILING
FOR FUTURE KICKER
CABLES**

AT MI-14 BUILDING



**CABLE TRAY WAS
LOWERED TO
ACCOMMODATE
PENETRATIONS**

AT MI-39 BUILDING



MI 14 Conduits





MI-14 Building – at end of shutdown

**FOUNDATION
WORK COMPLETE**





MI-14 Building – Oct 15th

**AWAITING SIDING,
ELECTRICAL AND
PAINTING IN
PROGRESS**





MI 39 Berm and Penetrations





MI-39 Building – at end of shutdown

**FOUNDATION
WORK COMPLETE**





MI-39 Building – Oct 15th

**SIDING,
ELECTRICAL, FIRE
PROTECTION,
HVAC IN
PROGRESS**





MI-60 Anode Supply Room


**NEED ROOFING
AND SIDING TO BE
COMPLETED**





Off project work – Gap Clearing Kickers


- 7 magnets installed during 2009 shutdown: ALARA





Gap Clearing Kicker System

INSTALLED DURING
SHUTDOWN



REMAINING COMPONENTS TO BE INSTALLED IN NEW BUILDINGS EARLY 2010,
THEN IN TUNNEL IN SHORTER SHUTDOWNS



Off project work – Gap Clearing Kickers

- Gap Clearing Kickers remaining work installation plan:
 - After MI-39 Building is able to be occupied
 - install communications connections
 - Install racks, power supplies, cooling skids
 - During 2010 summer shutdown
 - Pull cables from building to tunnel
 - Install LCW piping
 - Make system operational
 - During NOvA Accelerator shutdown in 2011-12
 - Move these kickers to Recycler



NOvA/ANU Shutdown work

- Installation planning work for beamlines
 - Interferences and 3d models based on tunnel inspections and drawings
- MINU GPP:
 - 2 new service buildings (MI 14 and MI 39)
 - New anode power supply room
 - Floodplain mitigation
- Gap Clearing Kicker AIP:
 - 7 magnets in tunnel
 - When service buildings complete, installation in buildings
- Summer 2010
 - Cable pulls and final connections of GCK