

Recent Work Towards Increasing the AP2 & Debuncher Aperture

● *Goal*

- To increase the admittance of AP2 & Debuncher to 35π mm-mrad for beam of initial momentum spread of $\pm 2.25\%$
 - Accepting 320π mm-mrad beam emittance
- Transfer efficiently to Accumulator via D/A

● *Mitigation of known limiting apertures*

● *Orbit Control*

- History of Debuncher orbit correction - Quad Stands
- Debuncher Extraction Bump (D/A work & studies)

● *Instrumentation*

- Will be covered at a future All Experimenters' Meeting
 - Exception is Debuncher pbar Intensity monitor


● *Lattice Modeling & Survey and Alignment*

● *Beam Studies*

- *Character of studies has changed* from predominately dedicated reverse proton studies to mostly semi-parasitic stacking studies
 - Debuncher Bumping

To Discuss today

What & Where



Limiting Apertures

Device	Horizontal		Vertical
	$\frac{\Delta p}{p} = 0$	$\frac{\Delta p}{p} = 2\% \quad *$	
Band 4 H pickup	36.8 π	36.3 π	48.7 π
Band 4 V pickup	40.5 π	39.0 π	29.9 π
Band 4 H kicker	36.0 π	35.5 π	48.7 π
Band 4 V kicker	41.2 π	41.1 π	30.1 π
Deb Extr. kicker	109.1 π	21.9 π	35.8 π

Not to be
changed

* The numbers in this column were calculated using β -functions at $\Delta p/p = 0$

Central orbit ($\Delta p/p = 0$) limiting apertures:

Horizontal: 36.0 π mm-mrad

Vertical: 29.9 π mm-mrad

March Measurement:

29.5 π mm-mrad


24.9 π mm-mrad

Combined effect of Band 4 Vertical and Extr. Kicker upgrades is ~7.4% (from particle tracking); to be done during 2005 shutdown.

Orbit Control - Debuncher Correctors' History

Prior to Run II, there were only 12 Horizontal and 8 Vertical correctors. Many were removed for cooling upgrades. Only capable of very local bumps[†] for ~5% of Debuncher

In 2001 installed 5 motorized quad stands[‡] for correcting ability in both planes: ~10%



Shutdown 2003 added 10 more motorized quad stands: ~25%

Shutdown 2004 added 20 more motorized quad stands: ~90%

[†] Very local bumps means that bump is local to 10% of ring.

[‡] Beam off center in quad induces a dipole kick; can correct in both planes.

Orbit Control - Debuncher EXtraction Bump

During reverse proton studies during 2004, we achieved an admittance of 33π mm-mrad horizontally!




This was achieved with a closed orbit bump through the extraction region: horizontal position bump at the Debuncher extraction septum.

However, not able to transfer efficiently to the Accumulator via D/A beam line: bumped to far away from septum for extraction kicker.



This has led to adding a ramped Debuncher EXtraction (DEX) bump.

Orbit Control - Debuncher EXtraction Bump



Operational but not optimized; D/A studies

Component Centering & Debuncher Bumping

Requirements:

- *Working intensity monitors in AP2 & Debuncher*
- *Store colliding & no impending transfers (RunCo)*
- *Stable beam to be available for 4+hr*
 - *No Booster or MI tuning*
 - *No Switchyard or NUMI tuning; permit system connected*
 - *Timeline stable since beam line orbits different on different events changes the injection efficiency*
 - *Offline analysis to disentangle effects*


Measurement

- *Move component or bump and watch Debuncher pbar intensity normalized by beam line intensity*
 - *Bumps are slow due to motorized quad stands (movement speed as well as only capable to move stands serially)*

Debuncher Pbar Intensity Monitor


Requires ramping
DRF1 in the middle
of the stacking
cycle and then ramp
back down

Block diagram of
temporary intensity
monitor



Debuncher Bumping - Stacking

- Same measurement method used to center moveable devices on beam
- Constructed and verified 3-bumps that cover the Debuncher (43 horiz. + 42 vert. bumps)
- Scanning a single bump can take 10-30 minutes
- Transmission efficiency can decrease while bump device moving
- Feb-Mar ~75% of vert. bumps completed for 1st pass about Deb.
- Debuncher η change affected closed orbit; corrected late Apr



Summary

● *Much work has been done in making tools and procedures for Beam Based Alignment*

● *Will continue-*

- Rounds of local bumping in Debuncher
- Component centering about orbit after each round of bumping
- Completing DEX bump commissioning
- Commissioning AP2 and D2A BPM system (not discussed today)
 - Maximize/center in Debuncher injection aperture via reverse proton studies
 - Measure AP2 lattice using reverse protons
 - Center orbit in AP2 using both reverse protons and stacking secondaries