



AP2 Line & Debuncher Studies Status

Keith Gollwitzer
Antiproton Source
January 9, 2006




Many people involved with providing
the hardware and software that was
commissioned as well as performing
the beam studies




Story Starts Seven Weeks Ago...

- 
- McGinnis at the All Experimenters' Meeting was describing a two week block of pbar studies
 - TeVatron breaks
 - Scramble to find people for Thanksgiving weekend studies
 - Finished preparatory studies
 - Started on the designed study plan
 - Owl shifts: started studies for the Debuncher to Accumulator (D/A) transfers



One of the several preparatory items that was done before Thanksgiving




Attempt to remove RF cavities effect on reverse proton injection



Statistics

- 
- Length of Time: **Tue Nov 22 to Thu Dec 15**
 - Number of Elog shift pages: **72**
 - Number of Recorded Debuncher Orbits: **857**
 - Number of Recorded AP2 Orbits: **775**
 - Number of Commissioned items: **11**
 - Number of Major Accomplishments: **$6 + \frac{1}{2} + \frac{1}{2}$**
 - Number of Confusions (at the time): **∞**
 - Number of Other Things Done: **$6 + 1$**
 - Number of “Next Times” Known Items: **9**
- 


Commissioned Items



- Debuncher Reverse Proton Turn-By-Turn system
- Debuncher Reverse Proton partial turn extraction up AP2
- Debuncher Component Centering
- Debuncher Orbit-Quad offset
- AP2 Orbit-Quad offset
- AP2 Beam Line Correction
- One-Shot Time-line for acquiring Debuncher beam
- Admittance measurement from data-logger
- “Deb Heat Rev p’s to AP2” aggregate
- AP2-Debuncher Injection region setup
- Auto-tune 120 GeV orbit of P1-P2-AP1


Scheduled Studies Accomplishments

- Lattice measurements for Debuncher and AP2
- Determine Debuncher Orbit/BPM-Quad offsets
- **Corrected Debuncher Vertical Orbit to Quad Centers**
- Centered Debuncher Components about orbit
- Determine AP2 Orbit/BPM-Quad offsets
- Set Orbit, Stands and Settings for AP2-Debuncher Injection Region
- Corrected AP2 Orbit to near Quad Centers
- **Installed AP2 lattice that matches to current Debuncher Lattice**



Items ½ completed


Change in Debuncher Vertical Orbit




- Steered to center of quads
- Center components about orbit using motorized stands

Change in AP2 Stacking Orbit


AP2 Horizontal Beam Positions Record 995 - Record 228



AP2 Vertical Beam Positions Record 995 - Record 228




Top - November BPM Positions – NO orbit correction & drifting




Bottom – December BPM Positions – Orbit Auto-Correction active



Stacking Rate is Better



Weekly Statistics




Other Items Done


- 
- Replaced failed Li Lens
 - Installed Collimator in Target Station
 - Survey of AP2-Debuncher Injection Region
 - Commissioned Ramped Devices in AP1
 - D/A Beam Based Alignment
 - Accumulator aperture: Injection channel & orbit
 - Stacking tune-up
- 

Next Steps

- Investigate AP2 lattice
- Correct Debuncher Horizontal Orbit
- Center Debuncher Components
- Install new Debuncher Lattice
- Install matched AP2 Lattice
- Remove Lens Steering
- Steer AP2 on apertures
- D/A Orbit
- Accumulator Orbit and Aperture





New Shutdown Items




- Identified Debuncher limiting aperture to be the Transverse Schottky's
 - New larger aperture pickups to be installed
- Identified the need for four dipole trims in the AP2 beam line
 - Two vertical trims to set position and angle going into the AP2 bend
 - One trim in each plane to set position and angle prior to AP2 downward bend to Debuncher

Summary-1

- 
- AP2
 - Defined a better orbit based on quad centers
 - Installed matched lattice to Debuncher
 - Identified vertical scraping in main AP2 bend region
 - Set Injection Region orbit and motorized stand positions
 - Need to work on
 - Center orbit vertically in main AP2 bend region
 - Upstream orbit
 - Lattice
 - Debuncher
 - Defined the vertical orbit based on quad centers
 - Centered components on motorized stands about orbit
 - Identified next limiting aperture to be transverse Schottkys
 - Need to work on
 - Center orbit horizontally on quad centers
 - Center components on motorized stands about orbit
 - Lattice work to help beam size in tight apertures
 - Antiproton Accumulation has increased by 15%
- 

Summary-2

- 
- D/A and Accumulator Injection Orbit
 - Next stacking limitation
 - D/A orbit needs to be centered in quads
 - Measured Accumulator admittances are <75% of what were measured at the beginning of Run II
 - Lessons Learned from 3 Weeks of Studies
 - Configuration control
 - Focus
 - Feedback of the effect of any one change on performance
 - Applying the Lessons Learned
 - Break into 1 to 2 day study periods
 - Will request 3 or 4 such periods before the long shutdown