

# Operating CM-1, an 8-cavity TESLA-Style Cryomodule

Elvin Harms  
All Experimenters Meeting  
27 June 2011

# Outline

- CM-1 Introduction
- Milestones
- Test Plan
- Results
- Future Plans
- Conclusion

# Introduction / What is CM1?


- Cryomodule 1, also dubbed 'S-1 Local'
- TTF Type III+ 8-cavity cryomodule
  - First one in the U.S.
- Provided to Fermilab by DESY as a 'kit'
  - Assembly by Fermilab, DESY, INFN-Milano
  - In exchange for 3.9 GHz cryomodule
    - Now in routine operation at DESY/FLASH
- Assembly at Fermilab
- Now installed at the refurbished New Muon Lab experimental hall



# Milestones

- Significant Progress has been made towards making CM1 operational in the past 18 months
  - 22 January 2010: Cryomodule moved into final position and aligned
  - 23 February 2010: Warm side of input couplers under vacuum
  - March - May: Cryogenic piping connections
  - 11 June 2010: permission to initiate RF commissioning and warm coupler conditioning
  - June - July: RF/Klystron commissioning
  - 2 August 2010: Warm coupler conditioning begins, one cavity at a time, beginning with Cavity 8/S33
  - 16 August 2010: Cavity 8 conditioning complete (14 days)
  - 26 August 2010: Cavity 7/Z91 conditioning complete (10 days)
  - 2 September 2010: Cavity 6/Z98 conditioning complete (8 days)
  - 17 September 2010: Cavity 5/Z107 conditioning complete (15 days)
  - 22 September 2010: Cavity 4/Z106 conditioning complete (6 days)
  - 27 September 2010: Cavity 3/AC73 conditioning complete (6 days)
  - 30 September 2010: Cavity 2/AC75 conditioning complete (4 days)
  - 3 October 2010: Cavity 1/Z89 conditioning complete (4 days)

# Warm Coupler Conditioning



Pulse Width  
(20  $\mu$ s - 1.2 ms)

Input power  
(up to 1 MW)

Field Emission  
probe and PMT  
Response  
(0-5 volts)

Cavity #1 (Z89)

# Milestones (2)

- . 12 November 2010: Insulating vacuum space leak tight and pumped down
- . 23 February 2010: Warm side of Couplers under vacuum
- . 17 November 2010: Cool down begins
- . 19 November 2010: Cool down to 4.5 Kelvin complete
- . 22 November 2010: At 2 Kelvin
- . 10 December 2010: Permission to initiate cold RF operation
- . 13 December 2010: Cold coupler conditioning and Performance evaluation begins, one cavity at a time, first RF into CM-1 at Fermilab beginning with #1
- . 17 December 2010 - 26 January 2011: Cavity 1/Z89
- . 28 January 2011 - 7 March 2011: Cavity 8/S33
- . 7 - 16 March 2011: Cavity 2/AC75
- . 18 - 22 March 2011: Cavity 1/Z89 *reprise*
- . 26 March - 4 April 2011: Cavity 3/AC73
- . 20 April - 19 May 2011: Cavity 4/Z106
- . 20 - 25 May: Cavity 5/Z107
- . 3 - 9 June: Cavity 6/Z98
- . 9 - 11 June: Cavity 7/Z91


# Performance Evaluation Steps

- Each cavity is singly connected to the output of the klystron to determine its performance.
- A prescribed series of measurements are made following the 'DESY recipe' test sequence at the Cryo Module Test Bench (CMTB)
  - RF Cable Calibration
  - Technical Sensor/Interlock Check
  - RF/Waveguide Check
  - Warm Coupler Conditioning (off resonance)
  - Cooldown to 2K
  - Frequency spectra measurements
  - Cavity Tuning to 1.300 GHz via motorized slow tuner
  - $Q_L$  adjust to 3 E6
  - LLRF calibrations
  - Cold Coupler Conditioning (on resonance)
  - Performance Evaluation including
    - Maximum gradient
    - Dynamic Heat Load ( $Q_0$  vs.  $E_{ACC}$ )
    - Dark Current and X-rays vs.  $E_{ACC}$
- Once pairs of cavities are tested, they will be connected to the waveguide distribution system.
- Ultimately all 8 cavities will be powered simultaneously by the 5 MW Klystron.



# Evaluation Summary

- Cavity #1 (Z89) assessment complete
  - 18 MV/m, high heat load
- Cavity #8 (S33) assessment complete
  - 23.5 MV/m, tuner motor shorted
- Cavity #2 (AC75) assessment complete
  - 27.5 MV/m, ok
- Cavity #3 (AC73) assessment complete
  - 16.5 MV/m, high heat load
- Cavity #4 (Z106) assessment complete
  - 28.1 MV/m, ok
- Cavity #5 (Z107) assessment complete
  - 33.8 MV/m, ok
- Cavity #6/Z98 assessment complete
  - 28.1 MV/m, ok
- Cavity #7/Z91 assessment complete
  - 22 Mv/m, marginally high heat load, ok
- *All cavities have now been individually evaluated*






# Cavity 1/Z89 Performance



- Determination of Cavity gradient limit: 23-24 MV/m, consistent with Chechia tests (maximum 2 HZ repetition rate, 1.2 ms pulse length)
- Stable operation at 18 MV/m
- Cryo Heat Load larger than expected
- Large Q drop vs. gradient
- Insignificant Dark Current and X-rays

Variation of  $Q_L$  with gradient



# Cavity 1/Z89 Performance



- Cavity 1/Z89 re-testing
  - Previous results, especially larger than expected heat load reproducible? Yes
  - Dynamic Heat Load characterization



Quench?

# Cavity 8/S33 Performance

- Tuner Motor freezes after ~119/361 kHz motion, motor appears to be shorted
- LLRF master oscillator tuned to cavity frequency, 1.300 241 800 GHz
- Peak Gradient - 23.5 MV/m, quench limited (5 Hz repetition rate, 1.2 ms pulse)
- $Q_0 \sim 1.5 \text{ E}10$
- Dark current and X-rays detected



← 10 - 25 MV/m →

Maximum X-rays  
at opposite end of  
Cryomodule

Maximum Dark  
Current at  
opposite end of  
Cryomodule




ENERGY

10 - 25 MV/m

Fermilab


# Cavity 3/AC73 Performance

- Uneventful Coupler Conditioning
- Tuner operation fine (no motor problems)
- Maximum gradient achieved - 19 MV/m
  - Limited to 2 Hz
  - Significant cryogenic response
  - No X-rays or Dark current detected
  - No clear quench indication
- LLRF closed loop operation
- LFDC demonstrated




# Cavity 4/Z106 Performance

- Coupler Conditioning took quite a while
  - 200  $\mu$ s, up to 1MW sequence
- Tuner operation fine (no motor problems)
- Maximum gradient achieved - 28.1 MV/m
  - 5 Hz
  - Abrupt quenching
  - X-rays detectible only during higher gradient operation - at middle of cryomodule
- LLRF closed loop operation
- LFDC demonstrated




# Cavity 5/Z107 Performance

- Very quick Coupler Conditioning (24 hours)
- Tuner operation fine (no motor problems)
- No anomalous behavior seen (cryo is stable to quench limit)
- Some x-rays
- Peak performance
  - 33.8 MV/m, quench limited
  - LLRF closed loop set up
  - LFDC tuned up
  - Limited to 2.5 Hz operation with 1.2 ms pulse width by LCW temperature, flow



# Cavity 6/Z98 Performance


- Rapid Coupler Conditioning (3 days)
- Tuner operation fine (no motor problems)
- No anomalous behavior seen (cryo is stable to quench limit)
- No x-rays
- Peak performance
  - 28.1 MV/m, quench limited
  - LLRF closed loop set up
  - LFDC tuned up
  - 5 Hz operation with 1.2 ms pulse width






# Cavity 7/Z91 Performance

- Quick Turnaround and rapid Coupler Conditioning (2 days)
- Tuner operation fine (no motor problems)
- Cryo instabilities just above 21 MV/m, but prior to quenching
- $Q_L$  drop with gradient
- No x-rays
- Peak performance
  - 22 MV/m, cryo and quench limited
  - LLRF closed loop set up
  - LFDC tuned up
  - 5 Hz operation with 1.2 ms pulse width




Cryo Response ~ 20 MV/m

# $Q_0$ vs $E$




# Q vs E Compared to DESY Data



# CM-1 Comparative Gradients




**Comparison of CM-1 Cavity Gradients**



# Subsystem Performance - Microphonics

- System evolving
- Interfaced to ACNET
- Ongoing improvements

## Cavity 4 Operation



# Next

- Follow-up testing on selected cavities
  - More DHL on cavity 7
- Begin Module testing thereafter



# Module Test Plan

- 1) Signal calibrations verified (1/2 day) 0.5
- 2) Waveguide distribution system assembled to all cavities (2 weeks)  
10.0
- 3) Adjust Variable Tap Off's (VTO's) based on cavity maximum gradient data (2 days)  
2.0
- 4) Adjust phase shifters – minimize field emission, dark current?
- 5) Verify power to cavities as seen on directional couplers (1/2 day) 0.5
- 6) Set  $Q_L = 3 \text{ E}6$  for all cavities (1/2 day)
  - a. LLRF system should be ready for real time  $Q_L$  measurements 0.5
- 7) Set cavities to as close to the same resonant frequency as possible (except #8) (1/2 day)  
0.5
  - a. LLRF should be ready for real time df measurements
- 8) Determine maximum achievable  $E_{ACC}$  (1 day) 1.0
- 9) Verify system LFDC/piezo system (6 months/3 weeks) 15 (parasitic)
- 10) Investigate Microphonics (parasitic)



# Module Test Plan - 2

- |   |   |
|---|---|
| 11) Determine LLRF regulation limits (3 days)   | 3 |
| a. Assess any potential issue with 8/9 pi modes (7-8 of them)   |   |
| b. Adjustable gain in LLRF controller to control 7 or 8 cavities  |   |
| c. FF operation   |   |
| d. Test phase and amplitude calibration scheme  |   |
| e. FB operation   |   |
| f. Test real time measurements (QI, detuning, control error, system noise)  |   |
| g. Evaluate controller performance and regulation limits  |   |
| 12) Measure dark current/x-rays levels and source(s) (mostly parasitic)   |   |
| 13) HOM signal investigation (mostly parasitic)   |   |
| 14) Investigate possible cross-talk between cavities: de-tune one cavity at a time to investigate response (2 days) |   |
| 2   |   |
| 15) Cryo heat load (should be parasitic)  |   |
| 16) Life test – investigate stability over 100? Hours   | 5 |
| a. Stability / drift analysis (requires waveform DAQ storage system)  |   |
| 17) 9mA related studies (Carwardine et al, meeting next week) (tbd)   |   |
| 5   |   |
| 18) higher Q (1E7) /P-X studies resonance control   | 3 |

\*48 days/5 = 9+ weeks

# Not Just Cavity Testing

- Although the priority, CM-1 operation has competition for time:
  - NML is still a construction area
    - Tunnel extension
    - Electrical Upgrades
    - Water system
  - Gun window evaluation and conditioning (typically 1-2 days/week)
  - Photoinjector installation
  - Tours
  - Performance limitations
    - Insufficient LCW capacity and cooling
    - New skid coming on-line now
- Strive to run as much as possible
  - Overnights and weekends when practical and testing program allows
  - Growing involvement by MCR crews

# Summary

- Cold operation of CM-1 in progress since November 2010
- Single cavity performance measurements are completed
  - 8 cavities; mixed results
- All sub-systems being understood and characterized
- Successes
  - Stable Cryogenics system
  - Evolving and flexible Controls
  - Growing involvement by AD/Operations
- A few issues
  - Tuner motor - Cavity 8
  - Cavities 1, 3, 7 Heat Load: other things to look at
- Move on to Module testing in very near future

# the Team

