


SuperCDMS: New Payload Operation at Soudan Mine




Lauren Hsu Fermilab AEM December 12, 2011

Experiment Overview





CDMS Hardware Vocab



<u>iZIP</u> = 1-inch Ge crystal, ~0.6 kg each, interleavened charge and phonon sensor design

<u>Tower</u> = 4 temperature stages (4K, 600 mK, 50 mK and 10 mK) heat sunk to different stages of the fridge via nested layers of the icebox 3

What has CDMS been up to recently?

Dec. '09: Final CDMS II dataset analyzed, 2 events seen, consistent w/ surface event bg

Spring '09 - Spring '11: Two separate "engineering" installations to test 1-inch thick detector designs: mZIP and iZIP

March '11: Fire in Soudan shaft prematurely ends Spring engineering run, CDMS survives sudden warmup from base temp (thankfully) without incident

Summer '11: iZIP design wins out, fabrication of full payload completed at the end of the summer, at least 10X better surface event rejection expected from SuperCDMS

Major Milestones Since Spring Shutdown

- September: Fabrication and testing of SuperCDMS payload completed
- October: Best-performing detectors selected and assembled into 5 towers (total ~10 kg Ge, 15 detectors)
- October 25: Safe delivery of detectors to Soudan after cross-country ground transport (driver condition not as good as the detectors upon arrival)
- November 8: Tower installation complete, icebox closed
- November 29: Hit base temperature (60 mK), confirmed at detector thermal stage, 3 days ahead of schedule (!)

Other Activities

- Ongoing repair and reinforcement to mine shaft restricts access more than usual
- Backup diesel generator for CDMS was a casualty of the fire, replaced with a new generator that can supply power to the whole experiment (48+ hrs) in the event of a blackout.
- Working out ongoing teething problems with new He and N liquefiers (used to recycle exhaust and reduce overall consumption of cryogens)
- Development of new automated data quality system
- Minor upgrades to data acquisition hardware several computers replaced or decommissioned, digitization reconfiguration, trigger logic updates

SuperCDMS 5-Tower Installation

- Only detectors were replaced in current installation, other components, including cold hardware reused from CDMS II
- An opportunity to train new people (significant changes in personnel taking place this year)
- First CDMS installation to undergo thorough documentation in the form of videos and photos

Set a new record for fewest problems during an installation!




View overlooking icebox, Nov. 1 2011

Photo-log of SuperCDMS Installation

Delivery and Transport Underground


Tuesday October 25





Unpacking

Tuesday




Inserting Tower 3 into the Icebox

Thursday October 27




10 and 50 mK Thermal Connections In Place


Friday October 28




Rebuilding the IR Shielding

Tuesday November 1






Cold Hardware Installation





Tuesday – Thursday November 1-3



13 SQUET cards installed only 17 more to go...

Thermometry and Final Adjustments at the 4K Stage



Friday – Tuesday November 3-8



Cabling and Continuity Checks










Installation Complete!

Tuesday November 8



Closing the Icebox

Tuesday November 8





Pump Out and Cool Down

November 8 - 29




Rebuilding the Shielding

November 16-17



First Phonon Pulses from Physics Event!



Last Friday (Dec. 9)


Showing 7 of 8 phonon channels on a single iZIP (still tuning settings on 8th)

Continuity checked out ok on > 99% of channels

Minor Installation Snags

Very smooth installation when considering aging infrastructure and re-use of cold hardware

 Chassis short on tower thermometry, found and fixed



Closeup of "surgical repair"

 Installation of cold hardware results in one broken stripline. Solved by last minute swap with thermometry stripline



Base Temperature

Smoothest cool-down in recent memory, no incidents

- Base temperature slightly higher than past operation (~60 mK compared to ~50 mK)
- · All detectors expected to be operational
- Thought to be due to slight thermal touch between two temperature stages or poor thermal contact at the 50 mK stage

Next Steps


- Turn on remaining detectors
- Determine operating conditions (optimize for detector stability and noise)
- · Data Quality system commissioning
- Repair He liquefier (one of two failed and returned to manufacturer for repair)

Search for WIMPs (!)


Backup

Where things stand

So far, no clear evidence for WIMPs, but much progress made in probing interesting theoretical regions



Spin-Independent scattering above 10 GeV/c² WIMP masses



Spin-Independent scattering below 10 GeV/c² WIMP masses

Make Sure the Thermal Contact Points are Clean!

