

Capture Cavity 2 Update



Tim Koeth
April 3rd

The CC2 Project

Capture Cavity 2 is a high gradient superconducting cavity destined to upgrade the Photoinjector to 40 MeV. This opportunity has been used for FNAL to learn the intricacies of SCRF work as well as to test FNAL facilities.

It is a collaborative effort:

Tesla 9-Cell 1.3 GHz Cavity: DESY (33MV/m)

Slow Tuner: Saclay & FNAL

Cryo Vessel: IPN Orsay

LLRF: DESY & FNAL

Inside FNAL: AD, TD, CD

Calendar

Started Nov 2004

Approval for RF on Jan 17th (2006)

RF into Input Coupler Jan 17th

Coupler processing Jan 24th

Cool down Feb 6th (coupler still problematic)

Warm up Feb 16th


More Coupler Processing: Feb - March

2nd Cool Down March 13th

CC2 Testing: Gradients, Dark Current, LLRF, Piezo & More

Warm up to begin 1.8K Installation: March 29th

Understanding Input Coupler




We are operating at a bias of +1300 V on center conductor.

RF In CC2: Peak Gradient

Driving with a 1.38mSec ($\sim 100\text{kW}$) square RF pulse: “Full Blast”

Q-loaded: $4.28\text{E}6$



BLU = P-forward

YEL = P-reflected


RED = P-trans = gradient

$\sim 28\text{MV/m}$

(any higher in gradient and cavity displays quenching)

RF In CC2: Dark Current

A Faraday Cup is installed at both ends of CC2's beam pipe.



YEL = P-Trans = Gradient


GRN = "Up Stream" Faraday Cup

BLU = "Dn Stream" Faraday Cup

Peak Dark Current: 50nAmps

RF In CC2: LLRF Control

Using DESY SimCon3.1 LLRF controller



BLU = P-Trans = Gradient

YEL = P-Ref


RED = P-Fwd

← 15MV/m

← 85kW

RF In CC2: LLRF Control

O'scope persistence set to 30 events:



BLU = P-Trans = Gradient

YEL = P-Ref


RED = P-Fwd

LLRF System compensated for frequency changes due to cryogenic pressure fluctuations.


RF In CC2: Piezo Fast Tuner

Lorentz force compensation with Piezo tuner

Piezo pulse: Single sine pulse; $V_{hv}=40V$; $F=185Hz$; $5405\mu sec$; start $4140\mu sec$ before cavity pulse




Vibration Studies



← From Piezo Element

From Seismometer →



Warm Up to Cool Down !

Warmed up CC2 last Wednesday (3/29) to allow Cryogenics Dept to prepare pumps for 1.8K operation.

1.8K in early May.