




# NOvA Experiment Status

Steve Magill Argonne National Laboratory  
All Experimenter's Meeting February 10, 2014

# Detector Assembly Progress




## NOvA Far Detector Assembly Progress



FarDet, Feb 11, 2013

Status Date: 10FEB14




FarDet, Feb 3, 2014

**14 kilotons = 28 NOvA Blocks**  
 27 blocks of PVC modules are assembled and installed in place  
 24.77 blocks are filled with liquid scintillator  
 10.68 blocks are outfitted with electronics

# Far Detector Data-Taking


- Improvement in some DAQ processes increased uptime
- Moved to 3-Partition running (3 separate parts of the detector each running its own DAQ processes)
  - Partition 1
    - First 2 kilotons of detector
    - APDs running full gain, cold
    - Stable part of detector
  - Partition 2
    - Second ~3.5 kilotons of detector
    - APDs running full gain, mixed cold/warm
    - Commissioning section of FarDet
  - Partition 3
    - Next 5 kilotons of detector
    - Filled with scintillator, Front-End electronics only (no APDs)
- Neutrino search on Partition 1 with little downtime

# DAQ Uptime



- Plot for last week
- Average of ~92% for past week
- Stable running on Partition 1 (stable part of detector)

# Fraction of POTs Recorded



- Averaging little over 93% for past week
- Stable running of stable partition
- Recorded  $\sim 5.9E18$  POTs out of  $6.9E18$  delivered (86%)

# Summary

- Cooled APDs looking good – especially those without A174 primer coating
- DAQ improvements increased our uptime
- In past week, switched to 3-partition running (3 separate parts of the FarDet running partitioned DAQ)
  - Optimize our beam exposure for stable part of the detector
  - Optimize detector checkout for new installations
  - Improvement in POTs recorded