



NOvA Experiment Status

Steve Magill Argonne National Laboratory
All Experimenter's Meeting, October 21, 2013


Far Detector Progress



The Intensity Frontier

NOvA Far Detector Assembly Progress

Status Date: 14OCT13



S. Dixon

APD Noise



The Noise problem in 1 page

- Noise was absent for the first couple of months of installation
- Noise problem on the detector does not appear immediately on installation, takes hours for it to develop, and can decrease over time as well.
 - Standard tests over 4-5 minutes did not show any problems. Longer duration tests (“Soak” test) on the test stand were needed to observe the behavior
- Noise varies from batch to batch in production. It is not clear what it is correlated with that drives the variation between batches, and how well it correlates with noise on the detector



What we have learned

- No fluorescence detected, so noise is not light.
- Noise excursions appear to be unrelated to handling or cleaning methods prior to coating (first suspects)
- Noise appears on essentially all parts with adhesion promoter (Silane A174) applied before coating
- Excursions on parts with A174 applied can be driven away with baking
- Noise can be largely prevented with parylene coating without A174 step
- Plausible noise/conduction mechanism proposed by Anna Pla-Dalmau, consistent with data
- Cooling appears to help reduce noise on detector as well



The Road Ahead

- Working on the path forward on two fronts:
 - Not coated:
 - Tested parts without A174 adhesion promoter
 - Tested good on test stand and NDSBTest stand
 - Temperature cycled for adhesion tests
 - Plan to produce and install 1 diblock of this type ASAP
 - Coated:
 - Cooled running appears to reduce the noise
 - Working on a baking treatment to refurbish parts coated with A174
 - Initial tests promising, running cool may be an additional help
 - Uncertain if it is a permanent fix.
 - Aging test parts were baked >6 months and still look good.
 - Plan to bake and install 1 diblock of this type ASAP

Near Detector Status



Near Detector Status (T.Miao)



| Block | Modules from Minneapolis | Assembly Complete | Installation Underground complete | Scintillator filled | Electronics installed (FEB & APD) |
|---------------|--------------------------|-------------------|-----------------------------------|---------------------|-----------------------------------|
| μ catcher | Apr 07 | Aug 01 | Aug 01 | ~Nov 1/ 17 Jan | Nov - Jan |
| 1 | May 21 | Aug 14 | Aug 21 | 24 Jan | Jan/Feb |
| 2 | June 20 | Sept 12 | Sept 25 | 31 Jan | Jan/Feb |
| 3 | Aug 08 | Oct 01 | Oct 7/Oct 9 | 7 Feb | Jan/Feb |
| 4 | Sept 17 | Oct 28/Oct 14 | Nov 4 | 14 Feb | Jan/Feb |
| 5 | Sept 24 | Nov 5 | Nov 11 | 28 Feb | Jan/Feb |
| 6 | Oct 11 | Nov 21 | Nov 25 | 7 Mar | Jan/Feb |
| 7 | Nov 01 | Dec 12 | Dec 16 | 14 Mar | Jan/Feb |
| 8 | Nov 22 | Jan 8 | Jan 8 | 28 Mar | Jan/Feb |

- Done, ** = in progress, Estimated on 10/7, Est 10/15, In planning stage
- ESH&Q pushing us to fill after all blocks are inside secondary containment
- Electronics is critical path, FEBs in January (1st 16 in November)
- Use scintillator from Wolf Lake supply for near detector
- Cost ~\$150k

ND Block Construction



Block 5 under construction
• 6 layers (out of 24) glued


Block 4 underground



Near Detector Schedule



Installation Schedule



Muon catcher + 4 PVC blocks installed - Oct 21
ND installation to be completed by early Jan 2014