



# NOvA Experiment Status

Steve Magill Argonne National Laboratory  
All Experimenter's Meeting, December 9, 2013



# FarDet Outfitting Progress

## Di-Block Status (12/09/13)

Di-Block Outfitting Status														
Position	DiBlock													
	14	13	12	11	10	9	8	7	6	5	4	3	2	1
1			DCM Avail	Filling	FEB Avail	FEB Avail	FEB Avail	FEB Avail	FEB Avail	FEB Avail	APD Avail	APD Avail	APD Avail	
2			DCM Avail	Filling	FEB Avail	FEB Avail	FEB Avail	FEB Avail	FEB Avail	APD Avail	APD Avail	APD Avail	APD Avail	
3			DCM Avail	Filling	FEB Avail	FEB Avail	FEB Avail	FEB Avail	FEB Avail	APD Avail	APD Avail	APD Avail	APD Avail	
4			DCM Avail	Filling	FEB Avail	FEB Avail	FEB Avail	FEB Avail	FEB Avail	APD Avail	APD Avail	APD Avail	APD Avail	
5			DCM Avail	Filling	FEB Avail	FEB Avail	FEB Avail	FEB Avail	FEB Avail	APD Avail	APD Avail	APD Avail	APD Avail	
6			DCM Avail	Filling	FEB Avail	FEB Avail	FEB Avail	FEB Avail	FEB Avail	APD Avail	APD Avail	APD Avail	APD Avail	
7	DCM Avail	DCM Avail	DCM Avail	Filling	FEB Avail	FEB Avail	FEB Avail	FEB Avail	FEB Avail	FEB Avail	FEB Avail	APD Avail	APD Avail	APD Avail
8	DCM Avail	DCM Avail	DCM Avail	Filling	FEB Avail	FEB Avail	FEB Avail	FEB Avail	FEB Avail	FEB Avail	FEB Avail	APD Avail	APD Avail	APD Avail
9	DCM Avail	DCM Avail	DCM Avail	Filling	FEB Avail	FEB Avail	FEB Avail	FEB Avail	FEB Avail	FEB Avail	FEB Avail	APD Avail	APD Avail	APD Avail
10	DCM Avail	DCM Avail	DCM Avail	Filling	FEB Avail	FEB Avail	FEB Avail	FEB Avail	FEB Avail	FEB Avail	FEB Avail	APD Avail	APD Avail	APD Avail
11	DCM Avail	DCM Avail	DCM Avail	Filling	FEB Avail	FEB Avail	FEB Avail	FEB Avail	FEB Avail	FEB Avail	FEB Avail	APD Avail	APD Avail	APD Avail
12	DCM Avail	DCM Avail	DCM Avail	Filling	FEB Avail	FEB Avail	FEB Avail	FEB Avail	FEB Avail	FEB Avail	FEB Avail	APD Avail	APD Avail	APD Avail

Block Installation Status														
Status	Block													
	27	26	25	24	23	22	21	20	19	18	17	16	15	14
			APD	Set	Set	Set	Filling	Filled	Filled	Filled	Filled	Filled	Filled	Filled

Filling

Filling block 21 (22nd block) horizontals. Begin filling block 21 verticals. Fix problem FEBs di-blocks 6 downstream. Install FEB power cables top of di-block 101  
**Friday 12/13:** Begin topping up block 21 (22nd block) horizontals.


Block 21 Vertical Modules														
Position	31	29	27	25	23	21	19	17	15	13	11	9	7	5
0														
1														
2														
3														
4														
5														
6														
7														
8														
9														
10														
11														

Block 21 Horizontal Modules														
Position	30	28	26	24	22	20	18	16	14	12	10	8	6	4
11														
10														
9														
8														
7														
6														
5														
4														
3														
2														
1														
0														

Block 20 Vertical Modules														
Position	31	29	27	25	23	21	19	17	15	13	11	9	7	5
0														
1														
2														
3														
4														
5														
6														
7														
8														
9														
10														
11														


Block 20 Horizontal Modules														
Position	30	28	26	24	22	20	18	16	14	12	10	8	6	4
11														
10														
9														
8														
7														
6														
5														
4														
3														
2														
1														
0														

# FarDet performance – DAQ Uptime




- Very reliable, continuous running on weekends
- APD installation weekdays interrupts DAQ
- Weekday replacements also stops DAQ
- On when beam is off (commissioning with c-rays)

# FarDet Performance – Fraction of POTs Recorded



- Very reliable, continuous running on weekends
- DAQ uptime when beam is off (commissioning with c-rays)

# FarDet Performance – Integrated POT



- During APD installation and hardware replacement, DAQ uptime and POT exposure depends on location of work.

# FarDet Neutrino Search

- Search for excess of events at expected time of NUMI beam

Reminder – plot of events in NDOS (prototype at Fermilab) →  
Optimizing cuts using MC → Cut selection for best FOM ( $s/\sqrt{b}$ ) :

Cut	GENIE (Signal)		Cosmics (Background)	
	Slices	Fraction	Slices	Fraction
No Cuts	103	1.0	$4.34 \times 10^7$	1.0
Has a Track	86	0.84	$4.0 \times 10^7$	0.92
Has a 3D Track	78	0.76	$3.6 \times 10^7$	0.84
Min $\cos(\theta_{\text{NuMI}})$	40	0.39	$1.4 \times 10^4$	$3.24 \times 10^{-4}$
Containment	18	0.17	$4.0 \times 10^3$	$9.11 \times 10^{-5}$
Max Dir <sub>y</sub>	12	0.11	342	$7.87 \times 10^{-6}$

Expect  $\sim 3\sigma$  peak after  $\sim 3.5$  months


- Scan selected events for neutrino interactions

Refining filter cuts – optimizing scanning sample

Filters applied to entire time window of data (not just expected signal region)

Developing strict scanning procedures and scanning tutorials

Expect time when null observation of a fully contained event falls to below 5% is  $\sim 3.6$  months at  $\sim 4E18$  POT/week



# Near Detector Schedule



## News and Schedule



- Block #8 assembly to start Tuesday IF new modules arrive in the morning  
*Module delivery delayed due to whether in MN*  
*Bookend and bridge ladder modifications in MAB*
- PDB/DCM installed for last di-block → Commissioning phase  
*All cabling to be completed this month*  
*Commissioning discussions are to be in Monday ND meetings*  
*3rd rack ORC walkthrough last Friday: need to replace HVAC CAT5 cable*  
*Need DCS on power supply ASAP -Ralf/Xuebing-Marianna Gabrielyan/Athans*
- APD dryer and water installations are under way  
*Erik -Dan Markley-Dennis Nicklaus on readout -- ND group to help out*
- Venting piping P&ID requires separate vent line for each block during filling
- FNAL tanker to be moved to MSB late this week  
*Temporary generators moved out of the way*  
*Berm to be installed after MSB windows covered with 1hr fire rated insulations*  
*Hole on the MSB wall to let tanker hose in – ESH&Q recommendation*  
*New teflon lined tanker hose with 35' long (50'?)*



# Summary



- NDOS Prototype running smoothly, useful for testing of software/firmware/monitoring upgrades before rolling out at FarDet – presently testing new FEBs for Near Detector
- NDSBTest (Near Detector Surface Building Test) 30 APD test stand for cooling/monitoring tests of APDs
- FarDet – 2.5 diblocks running cold at full gain – very smooth running, >3 diblocks instrumented with APDs, 26<sup>th</sup> block (out of 28) in place – new APD installation ongoing – very good initial performance of APDs w/o A174 primer
- NearDet – 7/8 of the Near Detector blocks are in place – finish in early January 2014, scintillator filling to start immediately after