



# CMS/LHC Status Report

Kalanand Mishra  
Fermilab – CMS Center

## Communication from the CERN DG

“...we remain on course to restart the LHC safely this year, albeit currently about 2-3 weeks later than we'd hoped at Chamonix.”


“...will be ready by September or October to run ... in the range 4-5 TeV per beam.”

## Communication from the CMS spokesperson


CMS now moving **out of “maintenance” state & moving into “beam-ready” state.**

All Experimenters' Meeting, July 6, 2009


# LHC status: Vacuum cleaning in sector 3-4 done




**Beam Screen (BS):**  
Clean copper surface



**BS contaminated by MLI**  
(multi layer insulation)



**BS contaminated by soot. Gray color varies with soot thickness.**



# Enhanced Quench Protection System



- ◆ Repair in sector 3-4 has revealed new facts concerning the copper bus bar in which the superconductor is embedded.
- ◆ The **process** of soldering the superconductor in interconnecting splices can cause discontinuity between the superconducting cable and the copper busbar joint
  - ➡ **Dangerous in case of a quench**
- ◆ Studies are ongoing to find a safe limit for the joint resistance as a function of the current in magnet circuits (max energy in the machine)

**QPS upgrade allows precision measurements of the joint resistance (sub-n $\Omega$  range) for every Busbar segment.**

**This will allow complete mapping of the splice resistances.**

# Good interconnect



Magnet

We must be sure that the joint between the sc cables is good.  
Measurements of nano-Ohms at 1.9K

Magnet

copper bus bar 280 mm<sup>2</sup>

copper bus bar 280 mm<sup>2</sup>

current

interconnection (soldered)

superconducting cable

In case of quench, it's still safe! Copper bus  
takes the current during the current decay  
following the quench



## Bad interconnect: problem after quench

No problem while the sc cable remains superconducting. But in case of quench:

**Current path is deviated through the sc cable (which is no longer sc). Depending on the current and length of this path, the cable can suffer thermal runaway.**

Magnet

Magnet

copper bus bar 280 mm<sup>2</sup>

copper bus bar 280 mm<sup>2</sup>


interconnection

Non-superconducting cable

**Danger of melting the sc cable then electrical arc**

Need to ensure that the copper stabilizer is continuous.  
Measurements of micro-Ohms at warm/cold performed.

# Maximum safe current vs joint resistance



# LHC Schedule Snapshot today



## ◆ 3 weeks delay with respect to baseline due to

- Splice measurements and repairs
- Delay in cool down of S12 and repairs of splices
- (Re-warming of S45)

## ◆ Plan

- Need to measure the remaining sectors (S23, S78, and S81) at 80K ?
- Repair any high resistance splices (at 300K) !
- Measure S45 at 300k
- Prepare scenarios of safe operating energy vs date of first collisions
  - » Degree of repair of splices
- At start-up confirm all splice resistance measurements at cold

**For more details, see presentation by Steve Myers (CERN director) on July 2<sup>nd</sup>:**

**<http://indico.cern.ch/conferenceDisplay.py?confId=62277>**



## Some highlights:

- completion of the revision of the tracker cooling plant
- completion, installation and commissioning of the preshower (ES) detector in both endcaps of ECAL
- endcap ECAL triggers have been installed and tested
- re-commissioning of CMS – global runs with cosmic/0T continuing

## Target:

Close and start cosmic runs with magnet on (4T) by July 22<sup>nd</sup> – stable data taking prior to beam

## Tracker is back on track


- **Strip Tracker** Operations resumed on June 10<sup>th</sup> after 7 month shutdown. Commissioning is progressing well. To be ready for 4T run.
- **Pixel Detector** has been running at 4<sup>0</sup>C since mid May. Participating in cosmic global runs.




# Tracking Performance after Alignment



## Method of using split tracks



### Cosmic Track Splitting: absolute residuals (ALIGN vers.)



# Global Run Highlights



[slide from CMS plenary talk by Commissioning Coordinator, June 22 '09]

DAQ items						
	FED	FRL	EVM	RU	BU	FU
#Tot.	613	423	8	504	688	4816

## ■ DAQ

- ◆ Full Event Filter farm
- ◆ Routinely all participating readout FEDs to 90 kHz (~8% deadtime)
- ◆ Centralized DAQ error reporting GUI ("Hotspot")

## ■ L1 Trigger hardware commissioning

- ◆ Comprehensive set of calorimeter trigger firmware deployed:
  - HF minbias, Single Jet, Single EGamma, MET, ECAL Endcap trigger
- ◆ New Drift Tube Track-Finder hardware commissioning
- ◆ New RPC cosmic technical trigger (for cosmics during collisions)
- ◆ New CSC Track-Finder commissioning

## ■ Services (cooling, power, ventilation) more reliable than last year

- Systematic accounting of downtime: "Run time logger" in development
- Web-based monitoring is now remotely available again, passing security reviews

(developed at Fermilab)

# Snapshot of the CMS web-based monitoring



## CMS Web-Based Monitoring



### Subdetectors WBM

[ECALSummary](#)

[DTHVmon](#)

[HCALSummary](#), *coming soon*

[CSCSummary](#)

### Core Services

[RunSummary](#) [24h] [24h&1+trig]

[RunTimeSummary](#) (DownTime logger)

[TriggerRates](#)

[LumiScalers](#)

[LastValue](#)

[ConditionBrowser](#)

[MagnetHistory](#)

[LhcMonitor](#) | [BLM](#) | [BPM](#)

[PageZero](#)

### Links

[DQM Run Registry](#)

[Online DQM GUI](#)

[CMS Online](#)


[FNAL ROC](#)

[Commissioning & Run Coordination](#)

[Shift ELog](#)

[WBM Twiki Page](#) | [WBM Support & Contact](#)

Last modified: 2009.03.25 14:02:20 UTC



## Other developments and plans



### Concern about ECAL endcap trigger readout:

- Last batch of ECAL endcap (EE) readout boards (DCC) was bad & cannot be repaired.
- Need to make new ones.
- Problems with the manufacture.
- Hope to have 6 by August. Need 5 to complete whole EE trigger.
- Spares to follow in September.


### Cosmic runs with OT/4T

June 2009							July 2009							August 2009						
Mon	Tue	Wed	Thu	Fri	Sat	Sun	Mon	Tue	Wed	Thu	Fri	Sat	Sun	Mon	Tue	Wed	Thu	Fri	Sat	Sun
1	2	3	4	5	6	7	29	30	1	2	3	4	5	27	28	29	30	31	1	2
8	9	10	11	12	13	14	6	7	8	9	10	11	12	3	4	5	6	7	8	9
15	16	17	18	19	20	21	13	14	15	16	17	18	19	10	11	12	13	14	15	16
22	23	24	25	26	27	28	20	21	22	23	24	25	26	17	18	19	20	21	22	23
29	30	1	2	3	4	5	27	28	29	30	31	1	2	24	25	26	27	28	29	30
6	7	8	9	10	11	12	3	4	5	6	7	8	9	31	1	2	3	4	5	6


**CMS is  
again  
Ready  
and  
Waiting!**

**Backup slides**

# Maximum safe current vs joint resistance



# Joint resistance measurements



# Splice measurement status



Sector	Status on June 5 2009	Splices Calorimetric Ohmic		Stabilizers Biddle R16		Stabilizers Biddle	
		1.9K 7kA		Warm		80K	
		Dipoles	Quads	Dipoles	Quads	Dipoles	Quads
12	warm	Done	Done	Done	Done	No need	No need
23	2K						
34	warm			Done	Done	No need	No need
45	80K					Analysis	Problems
56	warm	Done	Done	Done	Done	No need	No need
67	warm	Done	Done	Done	Done	No need	No need
78	40K	Done	Done				
81	40K	Done	Done				