

Operations of the NOvA Near Detector on the Surface (NDOS)

Jonathan M. Paley
All Experimenters' Meeting
April 30, 2012

The NOvA NDOS



The NDOS is exposed to both NuMI and BN beams.

This is an aerial photograph of the NOvA NDOS site. A red line indicates the beam axis from the Brookhaven National Laboratory (BNB) to the detector. A blue line indicates the beam axis from the NuMI accelerator. The detector is located at the end of the BNB beam line, which is rotated relative to the beam axis. The NuMI beam line is shown as a blue line branching off the main axis.

NuMI ($\sim 6.1^\circ$ off-axis)

BNB (on-axis, but detector is rotated

$\sim 21.5^\circ$ wrt beam-axis)

- ▶ 210 ton **prototype** detector.
- ▶ $\sim 16,000$ highly reflective 4 cm x 6 cm x 4(3) m PVC cells filled with liquid scintillator.
- ▶ Muon catcher at end designed to capture muons from beam neutrino interactions.
- ▶ Partially instrumented during the 2011-12 run.



The NOvA NDOS


▶ Goals:

- ▶ Full test of assembly and integration of all detector components
- ▶ Light yield studies
- ▶ Improvements of DAQ and DCS functionality and stability

▶ Physics opportunities:

- ▶ Development of calibration and alignment techniques
- ▶ Improvements to MC detector response simulations
- ▶ Determination of cosmic-ray backgrounds
- ▶ Measurement of CC and NC rates
- ▶ Measurement of off-axis beam composition

Active Channels vs. Time



The NDOS APD Saga (or, this is why we build prototypes)


- ▶ APDs need to be cooled to -15°C to reach sufficient noise levels (at FD)
- ▶ Cooling done by active water system and thermo-electric cooler
- ▶ Photosensitive face of APD sits in desiccated, air-tight volume.
- ▶ Failure of seals led to air entering volume.
- ▶ Cooling led to formation of condensation on photosensitive surface of APD, which caused electrical shorts and scorching of surface.
- ▶ In order to guarantee more robust system, two-pronged approach now being tested:
 - ▶ Protective coating on surface of APDs (Silicone or parylene; both show $\sim 5\%$ drop in light)

▶ active dry-air purge system of APD volume


Jonathan Paley, ANL HEP Division



DAQ Stability




Overnight Uptime Fraction: 96.9%




Overnight Uptime Fraction: 100%


BNB POT vs. Time (for runs with > 1 subrun)



NuMI POT vs. Time (for runs with > 1 subrun)








InTime NuMI Events=2023 in last month



TimeNuMIPeakMonth	
Entries	32875
Mean	259.3
RMS	148.9

- Dedicated reconstruction and cuts optimized to find NuMI and BNB candidate events.





NDOS Commissioning – What Have We Learned?

- ▶ All sorts of construction and installation issues (what kept many of us up late at night): block construction and installation, manifold cracks, APD mounting + cooling challenges, APD, FEB and DCM checkout, scintillator filling, etc.
- ▶ Performance of both DAQ + DCS hardware and software, and how these scale from NDOS to FD.
- ▶ How to make DAQ and DCS systems work together (still some work to do, but huge progress). DCS uses the readout line as the DAQ system. Readout for these two systems had to be coordinated, not a trivial task!
- ▶ Much much more...

NDOS Commissioning – What Have We Accomplished?

- ▶ Created a very stable DAQ system!
- ▶ Developed file transfer, nearline, online-monitoring systems.
- ▶ Offline calibration and analysis of “difficult” data.
- ▶ Migration to new electronic logbook and shift scheduler: ECL (FNAL CD product)
- ▶ Active dry-air APD purge system designed and tested on NDOS; 12 APDs have been operating “cooled” for ~1 week.

NDOS Commissioning – What's Next?

- ▶ During shutdown (and beyond), NDOS will continue to run and collect cosmic data until NDOS is longer “needed”.
- ▶ New DCMs to be installed this week; NDOS will then have a full complement of new (FD) hardware
- ▶ New APDs + mounting hardware to be installed on NDOS in this week
- ▶ Continued DAQ development, eg partitioning and automatic error recovery.
- ▶ Continued DCS development.
- ▶ **ALL** of this work is absolutely **CRITICAL** to being ready to take data in partial FD on day 1 of beam turn-on next year; active analysis of commissioning data from this summer will continue.