

# A Status Report on the Fermilab Holometer (E990 at MP8)

**Jonathan Richardson**

University of Chicago


Fermilab All-Experimenters' Meeting

February 3, 2014

# Experimental Overview

## Twin Michelson interferometers

Each independently measures  $\Delta L = L_x - L_y$




# Experimental Overview

## Twin Michelson interferometers

Each independently measures  $\Delta L = L_x - L_y$

## Power recycling cavities

Beam power:  $P_{\text{Beamsplitter}} = 1 \text{ W} \rightarrow 1 \text{ kW}$



# Experimental Overview

## Twin Michelson interferometers

Each independently measures  $\Delta L = L_x - L_y$


## Power recycling cavities

Beam power:  $P_{\text{Beamsplitter}} = 1 \text{ W} \rightarrow 1 \text{ kW}$

## High-frequency sampling (100 MHz)

Shot noise-limited sensitivity:

$$\Delta L = \frac{1}{2\pi} \sqrt{\frac{hc\lambda}{P_{\text{Beamsplitter}}}}$$
$$= 2 \times 10^{-18} \text{ m} / \sqrt{\text{Hz}}$$




# Detector noise cross-correlation achieves design sensitivity

6.5 hours of data @ 1 ms/FFT

→ Average of 70,000,000 FFTs

→ 70 TB




# Two-Interferometer Cross-Correlation

Interferometer #1: 992 W

Interferometer #2: 865 W

Integration time: 30 s




# Two-Interferometer Cross-Correlation

Interferometer #1: 992 W

Interferometer #2: 865 W

Integration time: 30 s




# Contrast Defect

Astigmatism in optics is producing a halo of non-interfering “junk” light

~2/3 of total output power

## Mitigation efforts underway:

1. Mechanical iris to block halo
2. Optical fiber-based output mode cleaner
3. Replacement of suspect optics




Output beam profile.



# Holometer Commissioning Status

---




The central vacuum service vessels housing the beamsplitters and power recycling mirrors.

## Complete

- ✓ Infrastructure/vacuum system
- ✓ Final optics installed
- ✓ Interferometer control systems demonstrated
- ✓ Data acquisition system operating at design sensitivity
- ✓ **Full power build-up (1 kW)**

# Holometer Commissioning Status



The central vacuum service vessels housing the beamsplitters and power recycling mirrors.

## Complete

- ✓ Infrastructure/vacuum system
- ✓ Final optics installed
- ✓ Interferometer control systems demonstrated
- ✓ Data acquisition system operating at design sensitivity
- ✓ Full power build-up (1 kW)

## Ongoing

- Mitigating contrast defect
- Automating lock acquisition
- Improving lock stability
- Suppressing RF cross-talk