

# An Introduction to the NuMI Project and the Minos Experiment

Robert Plunkett/Fermilab NuMI Deputy Project Manager

Fermilab All Experimenters Meeting 6 October, 2003



### Why this introduction?

- Who we are
  - Project, Collaboration and Laboratory
- What we are doing
  - Construction activities and timetable
  - Soudan operations
- How we'll be telling you about it.
  - Preliminary schedule of presentations to this meeting.



### The NuMI Project


- Build and commission a major beamline, including tunnels and surface buildings, and all beamline components, for long-baseline neutrino physics
- A new cavern and lab facilities at Soudan, Minnesota
- Two major detectors
- \$170 M of net value
- Involvement and excellent support from all Fermilab Divisions and Sections

### The MINOS Collaboration

All Experimenters 6 October, 2003 R. Plunkett Page 4

Athens • Cambridge • College de France • ITEP-Moscow • Oxford • Protvino • Rutherford • Sussex • UCL • Argonne • Brookhaven • Caltech • Fermilab • Harvard • IIT • Indiana • Lebedev • Livermore • Macalester • Minnesota • Minnesota-Duluth • Pittsburgh • South Carolina • Stanford • Texas-Austin • Texas A&M • Tufts • Sao Paolo • Western Washington • UNICAMP/Campinas • Wisconsin


> 27 Universities, 4 National Laboratories, 6 Countries More than 150 collaborators




**MINOS** 

### MINOS Long-Baseline Experiment

All Experimenters 6 October, 2003 R. Plunkett Page 5



### Schematic of NuMI Complex (Fermilab Part)



- Major complicated conventional construction
- Three major installations in three different areas:
  - •Several hundred feet of accelerator enclosure—half of which is between two operating machines
  - Downstream end of carrier tunnel, Pre-Target and Target Areas--primary beam focus, entrance to decay tunnel
  - •MINOS area—beam monitoring, ~1 KT hadron absorber and ~ 1 KT neutrino

### Civil Construction of Two Buildings

All Experimenters 6 October, 2003 R. Plunkett Page 7



MI65, gateway to the Target Hall, will be finished first.

Minos Service
Building
houses a
300 ft. shaft
leading to the
detector.



### Completed NuMI Decay Tunnel

All Experimenters 6 October, 2003 R. Plunkett Page 8



6m diameter excavated via Tunnel Boring Machine


Descends at 3.3 degrees – 6%


Now filled with decay pipe, shielding, and access passageway.

## Beamline and Focusing Layout

All Experimenters 6 October, 2003 R. Plunkett Page 9

**Physicist** 






120 GeV primary Main Injector beam

2-horn beam adjusts for variable energy ranges

675 meter decay pipe for  $\pi$  decay 240 meter rock muon absorber


### NuMI Target Hall



High and narrow to allow installation of target and horn systems and shielding.

MINOS

### Status of Horns



Horn Function:

Focus pions, which decay to neutrinos

Pulsed current: 205,000 Amps

Max. field: 3 Tesla

Status (both horns): ready!

fabrication complete

have been pulsed > 400k times each magnetic field quality checked vibration checked

#### Next steps:

Test fit onto support/alignment modules

Practice remote (hot) handling
Install in target hall May 2004

# Magnet Installation in 6 MI and "Stub" Underway

All Experimenters 6 October, 2003 R. Plunkett Page 12


"Porch" Area, heading underground

Stub area, heading toward porch

### Soudan Underground Laboratory

All Experimenters 6 October, 2003 R. Plunkett Page 13

- Operated by U. of Minn. and Minnesota Dept. of Natural Resources
- Soudan Mine -tourist attraction during summer months
- 1 elevator shaft limits loads to 1m x 2m x
   9m








### Zoom View of MINOS Supermodule

All Experimenters 6 October, 2003 R. Plunkett Page 14

- •8m Octagonal Tracking Calorimeter
- 486 layers of 2.54cm Fe
- 2 sections, each 15m long
- 4.1cm wide solid scintillator strips with WLS fiber readout
- •Magnet coil provides <B $> <math>\approx 1.3$ T
- 5.4kt total mass





### Completed Minos Far Detector




Two supermodules finished, energized Summer '03

Operating on cosmic rays and atmospheric neutrinos (Magnetic field allows event-by-event separation of antineutrinos)


Currently commissioning remote operations model

### First Minos Neutrino Event (2002)



- •Upgoing muon passing through about 3.5 m of the detector. ( $p_u > 1.9 \text{ GeV/c}$ )
- Magnetic field was not on at this time so no measurement of the momentum.

### Layout View of MINOS Near Detector




Readout Electronics

90 m below ground Cavern 46 m in length, ~ 10 m high Access via ~ 6.5 m diameter shaft

### Near Detector Plane Assembly Complete

All Experimenters 6 October, 2003 R. Plunkett Page 18

Hole for Coil Insertion



Scintillator Strip Modules

Stored on racks in New Muon Lab
Installation equipment tested
Magnet coils delivered, ready
PMT systems (UK) delivered, ready



### Minos Hall Outfitting

#### **Detector Supports**



Egress Passageway

Detector's Eye View as it will be installed beginning spring 2004

### Status of NuMI Project

- MINOS far detector complete.
  - Reading out with magnet.
- MINOS near detector main construction complete.
  - Electronics in use at CERN testbeams.
  - Auxiliary systems being assembled.
- Buildings and Outfitting at Fermilab nearing end.
  - Finished by 1/31/04, 10/20/03 for MI65 section.
- Beamline installation ongoing.
- Expect to begin commissioning at end of 2004.


### Schedule of Future Presentations

- Beamline Installation in 2003 status.
- Far Detector Running in Soudan
- Minos Near Detector status
- Characteristics of NuMI Neutrino Beam
- Beamline installation plans for 2004
- Collaboration on accelerator projects.

Sequence preliminary Interval about every 2 weeks

# Beam and Oscillation Signal


All Experimenters 6 October, 2003 R. Plunkett Page 22



#### Medium Energy

Goals of choice of beam operating conditions

- \* Maximize signal
- \* Minimize systematics
- \* Optimize coverage for "appropriate" parameters



MINOS

## Underground Construction, cont.

All Experimenters 6 October, 2003 R. Plunkett Page 23




Decay pipe section coming underground

Interior of decay pipe





### Beam Energy Options



Example spectra from varying horn positions

#### CC Events in MINOS 5kt detector

High  $\sim 15,000/yr \quad (< 30 \text{ GeV})$ 


Medium  $\sim 6200/\text{yr}$  (< 20 GeV)

 $\sim 1500/yr$  ( < 15 GeV) Low



#### Oscillation Signals





High-statistics ratio of far/near spectra will provide dramatic evidence for oscillation, and effective tool for studying the effect


### MINOS as Atmospheric Neutrino Detector

MINOS is first large underground detector with a magnetic field.

Will directly compare  $\nu_{\mu}$  and anti- $\nu_{\mu}$  oscillations in atmospheric region.

More than 1000 total events expected in 24 kT-years

Competitive limits on CPT violation will be obtained.





# Physics Goals of the Minos Experiment

#### Demonstrate oscillation behavior.

Using the CC rate and spectrum

(2-4% sys. Uncertainty per 2 GeV bin) Look for "standard" oscillatory spectrum.

Using the NC/CC ratio.

Precisely Measure the oscillation parameters  $\delta m^2$  and  $sin^2 2\theta$ 

CC energy distribution the principal tool here.

Gain information about the oscillation modes.

NC/CC to check for  $v_{\tau}$  vs.  $v_{\text{sterile}}$  Identification of  $v_{e}$ 

Near Detector reduces uncertainties, provides normalization of rates.

Spectrometer provides powerful analysis tool