

---

# Run II Operational Status and Plans

DOE MiniReview  
September 8, 2004  
Dave McGinnis

---

# Outline

---

- Goals
- Performance
- Major Accomplishments
- Machine Issues
- FY05 Outlook
- Summary

---

Goals

---

## Major FY04 Goals

---


- Operate the Collider at the Main Injector project luminosity design goals
  - 80% Antiproton transform efficiency from the Accumulator to Low Beta
  - $260 \times 10^9$  protons per bunch
  - $18 \times 10^{10}$ /hour antiproton zero stack stacking rate
  - Peak Luminosity of  $80 \times 10^{30} \text{cm}^{-2} \text{sec}^{-1}$
- Integrate over  $300 \text{pb}^{-1}$  in 39 weeks
- Prepare the Collider for implementation of the initial stages of the Run II Upgrades
  - Slip Stacking
  - AP2-Debuncher Aperture
- Commission the Recycler for electron cooling

---


## FY04 Performance

---


# Integrated Luminosity




# Weekly Integrated Luminosity\*



# FY04 Average Store Hours per Week



# Peak Luminosity



# Data Summary Table

| <b>Luminosity Parameters</b>               |            |                        |              |                   |                 |   |
|--|------------|------------------------|--------------|-------------------|-----------------|---|
| Parameter                                  | Best Store | Best of FY04           | Best of FY03 | FY04 (End) Design | FY04 (End) Base |   |
| Initial Luminosity (Average)               | 102.8      | 87.6                   | 43.7         | 61.9              | 43.3            | $\times 10^{30} \text{cm}^{-2} \text{sec}^{-1}$ |
| Integrated Luminosity per Store (Averaged) | 4241       | 3221                   | 1518.5       | 2000              | 1300            | $\text{nb}^{-1}$                                |
| Luminosity per week (Averaged)             | -          | -                      | -            | 11.3              | 7.4             | $\text{pb}^{-1}$                                |
| Store Length                               | 32.4       | 26.7                   | 17.8         | 15.0              | 15.0            | Hours   |
| Store Hours per week                       | -          | -                      | -            | 85                | 84              | Hours   |
| Shot Setup Time                            | 2.4        | 2.6                    | 2.1          | 2.2               | 2.2             | Hours   |
|  |            |                        |              |                   |                 |   |
| <b>TEVATRON Parameters</b>                 |            |                        |              |                   |                 |   |
| Parameter                                  | Best Store | Best 10 stores Average | Best of FY03 | FY04 (End) Design | FY04 (End) Base |   |
| Protons per bunch                          | 246        | 249                    | 241.2        | 260               | 260             | $\times 10^9$                                   |
| Antiprotons per bunch                      | 43         | 36                     | 25.6         | 31                | 25              | $\times 10^9$                                   |
| Proton Efficiency to Low Beta              | 85         | 77                     | 54.8         | -                 | -               | %   |
| Pbar Transfer efficiency to Low Beta       | 86         | 81                     | 63.5         | 80                | 77              | %   |
| HourGlass Factor                           | 0.66       | 0.67                   | 0.6          | 0.65              | 0.65            |   |
| Initial Luminosity Lifetime                | 5.2        | 6.0                    | 8.9          | 8.3               | 7.0             | hours   |
| Asymptotic Luminosity Lifetime             | 17.7       | 19.3                   | 23.7         | 25.0              | 25.0            | hours   |
| Effective Emittance                        | 16.9       | 17.0                   | 22.4         | 21.0              | 23.0            | $\pi$ -mm-mrad                                  |
|  |            |                        |              |                   |                 |   |
| <b>Antiproton Parameters</b>               |            |                        |              |                   |                 |   |
| Parameter                                  | Best Store | Best 10 stores Average | Best of FY03 | FY04 (End) Design | FY04 (End) Base |   |
| Zero Stack Stack Rate                      | 13.2       | 12.7                   | 12.0         | 18.0              | 13.7            | $\times 10^{10}/\text{hour}$                    |
| Normalized Zero Stack Stack Rate           | 2.5        | 2.4                    | 2.4          | 3.6               | 2.7             | $\times 10^{-2}/\text{hour}$                    |
| Average Stacking Rate                      | 6.8        | 6.4                    | 7.8          | 9.3               | 7.6             | $\times 10^{10}/\text{hour}$                    |
| Stacking Time Line Factor                  | 86         | 78                     | 94.8         | 75                | 75              | %   |
| Stack Size at Zero Stack Rate              | 309        | 321                    | 299.7        | 300               | 300             | $\times 10^{10}$                                |
| Protons on Target                          | 5.3        | 5.2                    | 5.1          | 5.0               | 5.0             | $\times 10^{12}$                                |
| Start Stack                                | 198        | 179                    | 158.8        | 155               | 130             | $\times 10^{10}$                                |
| End Stack                                  | 17         | 18                     | 12.9         | 15                | 15              | $\times 10^{10}$                                |
| Unstacked Pbars                            | 181        | 161                    | 145.9        | 140               | 115             | $\times 10^{10}$                                |

---

## Major Accomplishments




---

# Major Accomplishments for the Collider in FY04

---

- Proton Source
  - Operational Improvements
    - Booster Aperture
      - Alignment of Booster cavities and Magnets
      - Long 3 septum
    - New dogleg magnets at Long 3
      - Removal of beta wave
      - Less tune shift
    - Damper mode number and Power increase
    - Matching of the 400 MeV Line
    - Harmonic Correction
    - Two stage collimation system
  - Record intensities-  $6.0 \times 10^{12}$  protons/pulse for stacking
  - Record efficiencies  $> 85\%$
  - Record throughput  $> 1.0 \times 10^{19}$  protons/week for Miniboone
- Antiproton Source
  - Stacking rate  $13.65 \times 10^{10}$  pbars/hour
  - Largest stack  $246 \times 10^{10}$
  - Longest sustained stack  $> 2$  months
  - Debuncher Aperture Increase
  - Main Injector - Debuncher Phase alignment system
    - Aperture Increase
    - 8 GeV alignment across the injector complex now possible

# Main Injector Accomplishments



## ■ Main Injector

- Bunch Length reduction from dampers and beam loading compensation
  - 20% for coalescing
  - 50% for stacking
- 2.5 MHz transfers - 95% pbar coalescing efficiency
- Slip Stacking for Pbar Stacking
  - Done operationally for the last 7 days of running
- Slow Spill to SY120
  - Mixed Mode Pbar Stacking and Slow spill on the same cycle

# Tevatron Major Accomplishments

---

- Tevatron

- Alignment

- Projects

- Tev-Net
      - Smart bolt retro-fit
      - Dipole Un-Rolls
      - P1 Line roll
      - IP low-beta regions
      - Tight aperture areas

- Results

- Better injection efficiency
      - Smaller emittance at collisions
      - Better ramp efficiency
      - Better store-store reproducibility

# Tevatron Major Accomplishments

---


## ➤ CDF IP

- Location of IP was 4-5 mm too high vertically
- Significant impact on CDF's
  - Silicon tracking efficiency
  - SVX longevity due to radiation damage
- Rapid response team was organized during the 1 week shutdown in early December (due to the 16 house quench) to find a solution to move the CDF IP down by 4 mm
  - Within 1 week: designed, installed, and commissioned a series of low beta quad moves that
    - » Moved the IP down by 4mm
    - » Put the beam through the center of the low beta quads
    - » Better aligned the quadrupoles

## ➤ New Low Beta optics (April 04 - June 04)

- 20-30% increase in luminosity
- Smaller beta\*
- Smaller emittance

# TEV Lattice Change



# Major Accomplishments

---

## ▪ Recycler

### ➤ At the end of FY03

- The Recycler was "on the ropes"
  - Lifetime was  $< 60$ hrs
  - Transverse emittance growth was  $12\pi$ -mm-mrad/hr
- Took drastic measures
  - Re-organized the department (broke it away from Main Injector)
  - Lengthened the Fall 03 shutdown to bake the entire Recycler
  - Instituted the Pbar Tax (Investment) to guarantee the Recycler adequate study time and access to the tunnel
  - Re-organized the Accelerator Physics Dept. to give the Recycler and Tevatron more accelerator physicists

### ➤ Recycler bake-out was extremely successful

- Transverse emittance growth reduced by a factor of 5-8
- Lifetime  $> 300$  hours

### ➤ Recycler commissioning has progressed rapidly


- Stand alone Recycler shots to the Tevatron (Jan. '04)
  - Initial Luminosity  $> 17 \times 10^{30} \text{cm}^{-2} \text{sec}^{-1}$
  - Integrated useable luminosity
- Stack of  $> 150 \times 10^{10}$  pbars in the Recycler

### ➤ Using the Recycler in Mixed Pbar operations makes it a luminosity enhancement

- The top 4 luminosity stores were done with using the Recycler

### ➤ Recycler is ready for Electron Cooling

# Recycler Pbar Tax for FY04



# Major Accomplishments

---

## ■ Operations

### ➤ Long Stores

- More integrated luminosity
- More reliability - minimize ramping & shot setup
- Better able to integrate machine studies

### ➤ Better Planning

- Permanent run coordinator (Jim Morgan)
- Daily 9 am operations meetings
- Focused control of machine studies
  - Integrate luminosity when the machine is running well
  - Do machine studies when the machine is behaving poorly


### ➤ Mixed Pbar Operation

- Proposed in February '04 by Brian Chase
- Initial proposal presented at the April '04 Run II PMG
- Dual energy ramps in the MI completed and tested by May '04
- First Attempt 6/13/04
- Record Luminosity of  $103 \times 10^{30} \text{cm}^{-2} \text{sec}^{-1}$  recorded 7/16/04

# Mixed Pbar Extraction

- Extracting pbars from both the Accumulator and the Recycler for the same store i.e.
  - Twenty four bunches from the Accumulator
  - Twelve bunches from the Recycler
- Reasons
  - Flexibility in the Run II Upgrade schedule
    - Natural merging of commissioning of electron cooling
  - Push Recycler commissioning progress by plunging it into operations
  - Luminosity enhancement - larger amount of pbars for smaller emittances
    - Accumulator stack size limited to <200 mA
      - Stacking Rate
      - Transverse emittance vs Stack Size
- Ratio  $I_{\text{Recycler}}/I_{\text{Accumulator}}$  is governed by:
  - Recycler phase space density (cooling)
  - Recycler transfer time (Rapid transfers)
- Obstacles
  - Stacking Rate
  - Injector Complex 8 GeV energy alignment
  - Longitudinal emittance in both the Accumulator and Recycler
  - Transfer time between Accumulator to Recycler
  - NEED TO UPDATE MIXED PBAR SOURCE OPERATIONS MODEL

# Mixed Pbar Luminosity Potential



---

# Machine Issues

---

# Machine Issues

---

## ■ Proton Source

- Radiation damage due to the proton demands of the neutrino program.
- Proton Demand
  - Collider with Slip Stacking, MiniBoone, SY120, NUMI
  - Preliminary stages of developing a proton plan
    - Pulse component upgrade
    - Aperture upgrade (RF stations and kickers)
    - Alignment upgrade (TEV style alignment network)
    - Closed orbit control (ramped magnets and power supplies)
    - Tune control

# Machine Issues

---

- Main Injector

- Slip Stacking

- Demonstrated  $7 \times 10^{12}$  protons on target
    - Bunch length on target within spec.
    - Need to get to  $8 \times 10^{12}$  stably

- Running the Fixed target program

- Commissioning of high intensity NUMI multi-batch cycles
      - Transverse and longitudinal dampers
    - Switchyard 120



- Mixed Pbar Source Operation

- 8 GeV Energy alignment

# Machine Issues

## ■ TEVATRON

- More alignment work this shutdown
- B2 Snapback Improvements
- Octupoles
  - Beam Stabilization
  - Differential Chromaticity
- Orbit Smoothing
  - Automated Orbit smoothing
  - New BPM system
- TEV Abort
  - Unmasking of inputs for protection
  - New BLM system as abort input
  - Kicker Pre-fires
    - Collimator design
    - Abort block reconfiguration



# Pbar Production

---

- **Goal**

- Zero Stack Stacking Rate  $18 \times 10^{10}$  pbars/hr
  - Beam on target  $5.0 \times 10^{12}$  protons per cycle
  - Production  $17 \times 10^{-6}$  pbars/proton
  - Cycle time 1.7 sec

- **Achieved**

- Zero Stack Stacking Rate  $12.7 \times 10^{10}$  pbars/hr\*
  - Beam on target  $5.2 \times 10^{12}$  protons per cycle
  - Production  $15 \times 10^{-6}$  pbars/proton
  - Cycle time 2.2 sec

- **Difference**

- Zero Stack Stacking Rate down 29%
  - Beam on target up 4%
  - Production down 12%
  - Cycle time up 29%

\*Averaged over the 10 stores with the highest initial luminosity

---

# Pbar Production

---

- The momentum spread extracted from the Debuncher into the Stacktail has been decreased by about 35% over the past year.
- The present Stacktail system with the bandwidth as measured should be capable of handling a static flux of 29mA/hr
  - At small stacks, the present Stacktail system can clear the deposition orbit as fast as 1.2 seconds
  - Note in the future, that the present 2-4 GHz Accumulator Core Momentum Cooling system will have to be replaced with either the present or modified 4-8 GHz Accumulator Core Momentum Cooling system if the Accumulator is going to have to continue support large stacks.
- In the range of cycle times of interest, the amount of beam reaching the injection orbit of the Accumulator is proportional to how long the transverse cooling is on in the Debuncher.
  - Indicates an aperture problem in the D-A line.
  - The transverse cooling can be increased marginally by optimizing transverse gain ramping

# D-A Line Plan of Work

---

- Plot the beam envelope against an accurate model of the D-A line aperture. (The D-A line model should go from kicker to kicker)
  - Assemble mechanical drawings of all components in the D/A line
  - Collect survey data of D-A line
    - Referenced to Debuncher Extraction and Accumulator Injection (not chalk line)
    - Double check survey data against "common" sense measurements
  - Develop an accurate lattice model of Debuncher - D/A line - Accumulator Injection orbit
    - Check these models with beam based measurements
- Open up the D-A line for visual inspection during the shutdown
- Install a Debuncher Extraction Ramped Bump
  - Optimizes maximum closed orbit aperture at injection
  - Optimizes extraction channel aperture
- Build a forward Pbar BPM system in the D-A line

---

# FY05 Outlook

---

## Plans for FY05


---

- Install electron cooling in the Recycler in Fall '04 shutdown
- Run Slip Stacking at  $8 \times 10^{12}$  protons/pulse every 2 secs
- Increase the pbar production aperture by 25%
- Stack at small stacks with a rate of  $26 \times 10^{10}$  pbars/hr
- Run the complex in Mixed Pbar operations
  - Assume the gain from Mixed Pbar operations is "break-even" (pessimistic?)
- Commission electron cooling for operations by the end of FY05


# FY05 Goals

| Luminosity Parameters                      |            |                        |              |                   |                 |                   |                 |   |
|--|------------|------------------------|--------------|-------------------|-----------------|-------------------|-----------------|---|
| Parameter                                  | Best Store | Best of FY04           | Best of FY03 | FY04 (End) Design | FY04 (End) Base | FY05 (End) Design | FY05 (End) Base |   |
| Initial Luminosity (Average)               | 102.8      | 87.6                   | 43.7         | 61.9              | 43.3            | 96.1              | 80.7            | $\times 10^{30} \text{cm}^{-2} \text{sec}^{-1}$ |
| Integrated Luminosity per Store (Averaged) | 4241       | 3221                   | 1518.5       | 2000              | 1300            | 3369              | 3190            | $\text{nb}^{-1}$                                |
| Luminosity per week (Averaged)             | -          | -                      | -            | 11.3              | 7.4             | 16.8              | 12.7            | $\text{pb}^{-1}$                                |
| Store Length                               | 32.4       | 26.7                   | 17.8         | 15.0              | 15.0            | 20.0              | 25.0            | Hours   |
| Store Hours per week                       | -          | -                      | -            | 85                | 84              | 100               | 100             | Hours   |
| Shot Setup Time                            | 2.4        | 2.6                    | 2.1          | 2.2               | 2.2             | 2.6               | 2.6             | Hours   |
| TEVATRON Parameters                        |            |                        |              |                   |                 |                   |                 |   |
| Parameter                                  | Best Store | Best 10 stores Average | Best of FY03 | FY04 (End) Design | FY04 (End) Base | FY05 (End) Design | FY05 (End) Base |   |
| Protons per bunch                          | 246        | 249                    | 241.2        | 260               | 260             | 260               | 250             | $\times 10^9$                                   |
| Antiprotons per bunch                      | 43         | 36                     | 25.6         | 31                | 25              | 42                | 34              | $\times 10^9$                                   |
| Proton Efficiency to Low Beta              | 85         | 77                     | 54.8         | -                 | -               | -                 | -               | %   |
| Pbar Transfer efficiency to Low Beta       | 86         | 81                     | 63.5         | 80                | 77              | 76                | 74              | %   |
| HourGlass Factor                           | 0.66       | 0.67                   | 0.6          | 0.65              | 0.65            | 0.65              | 0.65            |   |
| Initial Luminosity Lifetime                | 5.2        | 6.0                    | 8.9          | 8.3               | 7.0             | 6.4               | 6.4             | hours   |
| Asymptotic Luminosity Lifetime             | 17.7       | 19.3                   | 23.7         | 25.0              | 25.0            | 25.0              | 25.0            | hours   |
| Effective Emittance                        | 16.9       | 17.0                   | 22.4         | 21.0              | 23.0            | 18.5              | 17.0            | $\pi$ -mm-mrad                                  |
| Antiproton Parameters                      |            |                        |              |                   |                 |                   |                 |   |
| Parameter                                  | Best Store | Best 10 stores Average | Best of FY03 | FY04 (End) Design | FY04 (End) Base | FY05 (End) Design | FY05 (End) Base |   |
| Zero Stack Stack Rate                      | 13.2       | 12.7                   | 12.0         | 18.0              | 13.7            | 24.5              | 14.0            | $\times 10^{10}/\text{hour}$                    |
| Normalized Zero Stack Stack Rate           | 2.5        | 2.4                    | 2.4          | 3.6               | 2.7             | 3.1               | 2.3             | $\times 10^{-2}/\text{hour}$                    |
| Average Stacking Rate                      | 6.8        | 6.4                    | 7.8          | 9.3               | 7.6             | 10.1              | 6.6             | $\times 10^{10}/\text{hour}$                    |
| Stacking Time Line Factor                  | 86         | 78                     | 94.8         | 75                | 75              | 75                | 75              | %   |
| Stack Size at Zero Stack Rate              | 309        | 321                    | 299.7        | 300               | 300             | 300               | 300             | $\times 10^{10}$                                |
| Protons on Target                          | 5.3        | 5.2                    | 5.1          | 5.0               | 5.0             | 8.0               | 6.2             | $\times 10^{12}$                                |
| Start Stack                                | 198        | 179                    | 158.8        | 155               | 130             | 216               | 181             | $\times 10^{10}$                                |
| End Stack                                  | 17         | 18                     | 12.9         | 15                | 15              | 15                | 15              | $\times 10^{10}$                                |
| Unstacked Pbars                            | 181        | 161                    | 145.9        | 140               | 115             | 201               | 166             | $\times 10^{10}$                                |


# FY05 Goals Integrated Luminosity



# FY05 Goals Weekly Integrated Luminosity



# FY05 Goals Peak Luminosity



# Conclusions

---

- Collider performance in FY04
  - Exceeded the design FY04 design curve
  - The peak luminosity and the luminosity per week has doubled from FY03
  - Most of the Tevatron parameters are close to the design values
  - The Proton Source is operating at record intensities, efficiencies, and throughput.
  - Slip Stacking has been commissioned in the Main Injector
  - The Recycler is:
    - ready for electron cooling
    - Dramatically increases luminosity through mixed-pbar operations
  - Pbar production is well below the design parameters but the study plan executed over the summer indicates that the source of the shortfall is the result of a small effective aperture in the D-A line
- FY05 will be a pivotal year for the Run II Collider
  - Pbar stacking
  - Mixed Pbar operation
  - Electron cooling installation and commissioning