



# Osaka Meeting Overview: Progress and Issues

Michael S. Zisman  
Center for Beam Physics  
Lawrence Berkeley National Laboratory

NFMCC Friday Meeting  
March 10, 2006



# Outline




- Progress since Frascati meeting
- Meeting Plans
- Meeting Goals
- Issues from Technical Board
- Beam Line Issues
- Cooling Channel Issues
- Detector Issues
- Simulation Issues
- Controls/DAQ Issues
- Final Remarks

- Progress on many fronts is encouraging
  - PSI (decay) solenoid arrival
  - spectrometer solenoid purchase moving forward
  - 201-MHz cavity testing now under way (reached 16 MV/m!)
  - RF power source refurbishment under way at Daresbury
  - asymmetric heating of Be windows estimated and looks okay
  - progress on tracker design and definition of PID approach
  - hydride bed ordered (delivery in May)
  - new group (Kyoto) accepted into collaboration

# Cavity Ready for Testing



4616HT power supply being built at Daresbury for May 2006 test



201-MHz cavity at Fermilab MTA

- Plans for upcoming **MICE** meetings
  - June 8-11, 2006 at Fermilab (changed due to EPAC)
  - October 8-11, 2006 at RAL
    - in future consider two meetings at RAL, one elsewhere
- Plans for upcoming **ISS** meetings
  - April 25-28, 2006 at RAL (with BENE)
    - Accelerator Group workshop April 21-24, 2006 (also RAL)
    - Accelerator Group workshop May 20-22, 2006 (BNL)
  - August 21-22, 2006 at UC-Irvine

- Where are we on preparations for Steps 1 and 2?
- Issues
  - beam line, target, optics, tuning/correction algorithms, diffuser
  - TOF, CKOVs, MUCAL, tracker, spectrometer solenoids
  - trigger, DAQ, controls/monitoring
  - software (PID, reconstruction)
  - analysis (run plan, “beam” reconstruction, emittance, transmission)
  - installation/cabling


## PHASE I

### STEP I:

April 2007 = 394 days away!

### STEP II:

October 2007



- Power requirements need to be defined precisely
  - especially cryocoolers (about 10 kW per unit)
  - need efficient operation plan to stay below 700 kW (if possible)
- ISIS production target test schedule is tight
  - test vibration, vacuum, reliability issues well before June run
  - investigate commercial solution for 40 A programmable current source
- Need to “freeze” beam line front end
  - hold review by mid-April
  - generate standard files for G4Beamline
- Need sign-off on main features of Hall layout
  - ask for written list of objections/omissions
  - aim for formal sign-off at next Tech Board meeting

- Get safety sign-off on shielding approach by April
- Explore use of collimators, e.g., for “pencil” beam
  - Understand what happens to collimated particles
- Explore use of ISIS target station 2 correctors
  - can we piggyback on their order?
- Define tolerances (alignment, field strength, field quality) for all elements
- Define diagnostic needs for beam line
  - need to beef up optics effort

## • Magnets

- decide on AFC changes and formalize (e.g., using cooling pipes rather than liquid cooling)
  - is this needed for all magnets?
- formalize maximum force design values (50 → 70 tons)
  - implies bigger heat leak
  - add low-field polarity check to operational procedures
- formalize adoption of pulse-tube coolers rather than GM
  - requires vertical mounting and shielded rotary valve
  - prefer use of pulse tube cooler for H<sub>2</sub> R&D system!
  - note that compressors also need to be away from magnetic field
- decide on proper interface between AFC module and absorber
  - use dummy absorber
  - use pipe template for absorber fabrication
- design must be done by end of 2006
  - develop milestones to reach this result



# Cooling Channel Issues (2)



- $H_2$  R&D system

- complete and document formal HAZOP process
- evaluate practicality of non-flammable MLI
- avoid creating hydrogen zone in experimental area

- RF

- method to measure voltage at 1% level is not in hand
  - likely to require beam-based measurements to achieve this

# Detector Issues (1)

- Need to resolve—and get buy-in—on technical decisions
  - sandwich calorimeter vs. KLOE design
    - do we need one KL layer, or all plastic?
  - need for CKOV2 (almost ready; probably not needed)
    - need to document case better
  - design for CKOV1 (ring imaging?)
- Finalize spectrometer solenoid spec by mid-March
- Need plan for final magnetic mapping with field sensors
- Need to pay more attention to QA/QC
  - wiring errors
  - connector misalignments
  - build a fifth station using full QA procedures

- Understand 201 MHz RF backgrounds
  - has implications for operation of AFE II board (count rate capability)
  - MTA tests with Coupling Coil would go a long way toward answering which regime we'll be in
- Consider need for dual Fe shields at TOF2 to lower  $B_r$ 
  - a non-trivial perturbation on present design, if needed

- Understand predicted lack of cooling with large  $\Delta E$ 
  - consultation with Palmer and Fernow recommended (at RAL in April, or earlier at BNL?)
- Evaluate use of TOF2 to constrain timing at RF location
- Resolve discrepancy between ICOOL acceptance and analytic estimate

- Develop trigger scheme
- Specify/evaluate all required hardware, especially front-end electronics
  - assemble a test system
- Finalize DAQ scheme at Fermilab (CM15); approve at RAL (CM16)
  - architecture: PC + VME + Ethernet
- Need PID + track reconstruction algorithms for Step 1
  - also front-end electronics specification (late!)

# Final Remarks

- We continue to make progress but some things are moving more slowly than hoped
- Be vigilant about opportunities to publicize **MICE**
  - muon program got good press at HEPAP AARD Subpanel
  - need to think about journal publication(s)
- **MICE** management continues to be grateful for the hard work of the collaboration
- Now **394 days to target date for first beam**
- **See you at Fermilab** 😊