




*Muon Collaboration*

---

# MICE Tracker Update

Tracker test at KEK



Muon Collaboration


# Overview

- We are setup to test the 4 station tracker prototype in the KEK  $\pi^2$  beam line
- The Ingredients of the Test represent a reasonable approximation to MICE Phase I. They include:
  - ♦ 4 station tracker
  - ♦ VLPC readout system
    - 2 VLPC cassettes (2048 ch)
    - Cryostat with cryo-cooler
    - Readout electronics
    - VME/Linux based DAQ
  - ♦ TOF
  - ♦ Cerenkov
  - ♦ Beam Counters

# KEK $\pi^2$ Beam Line

## KEK test

Currently setup with beam entering this way




## Phase 2

w/ large emittance

Will attempt to get data of this type during the current run

## \* Study of emittance measurement



# Tracker

- Naked 4 Station prototype





Muon Collaboration

# Test Status


- Currently all components are installed in the line
- VLPC System is in place and cold
- AFE II boards are installed and all 4 have been tested successfully
- Calibrating Beam Counter, TOF, and Cerenkov PMTs
- Bess Magnetic is cold and has been energized
  - ♦ Fringe field map has been made
  - ♦ One problem discovered - Turbo pump for VLPC cryostat had to be moved - FF too high.
- Calibrating VLPCs
- Testing DAQ/Readout
- Setting up trigger timing



# Slide Show



Tracker installed in  
Bess Magnet. AL plate  
holds the upstream beam  
defining counter



Time Of Flight Hodoscope





Waveguides emerging from  
back of tracker










VLPC System in place and ready to go. The waveguides have not yet been attached to the cassettes. An LED calibration is being done.

# Overall Experiment Layout



- Run Plan
  - ◆ B=0 Straight on
  - ◆ 15° B=0
  - ◆ 15° B on (1 T)
  - ◆ Rotate 180°
  - ◆ Install 150 mm Defining Counter
  - ◆ Install diffuser (20 mm Pb)
  - ◆ Run straight-on with B=0
  - ◆ Run with B on
- 20 Shifts available



# Don't Ask

